

PARAGON

Paragon Building Certifiers Pty Ltd
RBC00045
Registered Certifier
APPROVED
Reference: 260314/02
26.08.2026



ADDRESS: LOT 04, 100 MILKY WAY CAMPBELLTOWN 2560

PROPOSED DOUBLE STOREY BRICK VENEER DWELLING

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

FACADE RENDER

Project number	070624	A001
Date	26.08.2026	
Drawn by FS	Checked by NS	
		Scale

PARAGON

Paragon Building Certifiers Pty Ltd
RBC00045
Registered Certifier
APPROVED
Reference: 260314/02
Date: 18/09/2026



LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560
PROPOSED DOUBLE STOREY BRICK VENEER DWELLING

Designed By:



SYDNEY DESIGNERS
AND PLANNERS

CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

COVER PAGE		
Project number	070624	A000
Date	26.08.2026	
Drawn by FS	Checked by NS	
		Scale

BCA COMPLIANCE

Section A General Provisions

2022 Vol. 2 Part H1 – Classifications:

CLASS 1: One or more buildings which, in association, constitute a dwelling. -
(a) Class 1A - A single dwelling, being -
(i) A detached house, or
(ii) One of a group of attached dwellings, each being a separate building, separated by a fire-resisting wall, including: row houses, terrace houses, townhouses, villa units.

CLASS 10: A non-habitable building or structure includes - Includes:
(i) private garage, carport, shed, or similar
(ii) structures like fences, retaining walls, pools
(iii) private bushfire shelters

Part H3 – Fire Safety (Fire Separation)

Performance Requirement (P2.3.1 / H3P1)

H3P1 Protection from the spread of fire :
A Class 1 building is to be protected from the spread of fire.

H3F2 Fire detection and early warning :
A Class 1 building is to be provided with safeguards so that occupants are warried of a fire in the building so that they may safely evacuate.

H3P1 Spread of fire :
(1) A Class 1 building must be protected from the spread of fire such that the probability of a building not being able to withstand the design heat flux of 92.6 kW/m² for a period of 60 minutes shall not exceed 0.01, when located within 900 mm from the allotment boundary or within 1.8 m from another building or from the same allotment from another building other than an associated Class 10 building; and (a) the allotment boundary, other than a boundary adjoining a road or public space (see Figure H3P1). (b)

(2) A Class 10a building must not significantly increase the risk of fire spread between Class 2 to 9 buildings.

H3P2 Automatic warning for occupants:
In a Class 1 building, occupants must be provided with automatic warning on the detection of smoke with an efficacy greater than 0.95 and a reliability greater than 0.95, so that they may evacuate in the event of a fire to a place of safety appropriate to the function and use of the building; and
(a) occupant characteristics
(b) fire load and combustion characteristics
(c) potential fire intensity
(d) fire hazard

H3D2 Fire hazard properties and non-combustible building elements

(1) The following materials, though combustible or containing combustible fibres, may be used wherever a noncombustible material is required:
(a) plasterboard, and
(b) perforated gypsum lath with a normal paper finish, and
(c) fibrous-plaster sheet, and
(d) fibre-reinforced cement sheeting, and
(e) pre-finished metal sheeting having a combustible surface finish not exceeding 1mm thick and where the Spread-of-Flame Index of the product is not more than 0; and
(f) bonded laminated materials, where -
(i) each lamina, including any core, is non-combustible; and
(ii) each adhesive layer does not exceed 1 mm in thickness and the total thickness of the adhesive layers does not exceed 2 mm; and
(iii) the Spread-of-Flame Index and the Smoke-Developed Index of the bonded laminated material as a whole do not exceed 0 and 3 respectively.

(2) The fire hazard properties of materials used in a Class 1 building, including floor or ceiling spaces common with a Class 10 building, must comply with the following:
(a) Sarking-type materials used in the roof must have a Flammability Index not greater than 5
(b) Flexible ductwork used for the transfer of products initiating from a heat source that contains a flame must comply with the fire hazard properties set out in AS 4254.1.

H3D3 Fire separation of external walls

Compliance with Part 9.2 of the ABCB Housing Provisions satisfies Performance Requirement H3P1 for fire separation of external walls.

H3D4 Fire protection of separating walls and floors

Compliance with Part 9.3 of the ABCB Housing Provisions satisfies Performance Requirement H3P1 for fire protection of separating walls and floors.

H3D5 Fire separation of garage-top dwellings

Compliance with Part 9.4 of the ABCB Housing Provisions satisfies Performance Requirement H3P1 for fire separation of garage-top dwellings.

H3D6 Smoke alarms and evacuation lighting

(1) Compliance with Part 9.5 of the ABCB Housing Provisions satisfies Performance Requirement H3P2 for smoke alarms and evacuation lighting. (2) For the purposes of (1), a Class 1 building includes a Class 10a private garage located above or below the Class 1 building.

Part 9.5 of the ABCB Housing Provisions specifies different smoke alarm requirements for Class 1a and Class 1b buildings. The main difference is that a Class 1b building is required to have a greater number of smoke alarms, i.e. smoke alarms must be installed in all bedrooms, and a system of lighting must be installed to assist evacuation. This is due to Class 1b buildings generally being used for more transient purposes and the occupants being less familiar with the building layout.

Location of smoke alarms

When deciding on the position of smoke alarms it is important to remember that they are intended to detect smoke before it reaches the sleeping occupants of a building. The ensuing alarm is designed to wake the occupants and give them time to evacuate the building.

Part H4 Health and amenity

Performance Requirements

H4P1 Wet areas

To protect the structure of the building and to maintain the amenity of the occupants, water must be prevented from penetrating— behind fittings and linings; or (a) into concealed spaces, (b) of sanitary facilities, bathrooms, laundries and the like.

H4P2 Room heights

A room or space must be of a height that does not unduly interfere with its intended function.

H4P3 Personal hygiene and other facilities

(1) Suitable sanitary facilities for personal hygiene must be provided in a convenient location within or associated with a building, appropriate to its function or use.
(2) Laundering facilities or space for laundering facilities and the means for sanitary disposal of waste water must be provided in a convenient location within or associated with a building, appropriate to its function or use.
(3) A food preparation facility must be provided which includes— (a) (b) (c) a means for food rinsing, utensil washing and the sanitary disposal of associated waste water; and a means for cooking food; and a space for food preparation.
(4) A sanitary compartment must be constructed with sufficient space or other means to enable an unconscious occupant to be removed from the compartment.

H4P4 Lighting

(1) A habitable room must be provided with windows, where appropriate to the function or use of that part of the building, so that natural light, when available, provides an average daylight factor of not less than 2%.
(2) Artificial lighting must be installed to provide an illuminance of not less than 20 lux appropriate to the function or use of the building to enable safe movement by occupants.

H4P5 Ventilation

(1) A space within a building used by occupants must be provided with means of ventilation with outdoor air which will maintain adequate air quality.
(2) A mechanical air-handling system installed in a building must control—
(a) (b) the circulation of objectionable odours; and the accumulation of harmful contamination by micro-organisms, pathogens and toxins. (3) Contaminated air must be disposed of in a manner which does not unduly create a nuisance or hazard to people in the building or other property.

Part H5 Safe movement and access

H5P1 Movement to and within a building

So that people can move safely to and within a building— walking surfaces must have safe gradients; and
(a) any stairway or ramp must—
(i) have suitable handrails where necessary to assist and provide stability to people using the stairway or ramp;
(ii) and have suitable landings to avoid undue fatigue of users; and
(b) be suitable for safe passage in relation to the nature, volume and frequency of likely usage; and
(iii) have slip-resistant walking surfaces on ramps, and on stairway treads or near the edge of the nosing.

H5P2 Full enclosure barriers

(1) A barrier must be provided where people could fall—
(a) 1 m or more from a floor or roof or through an opening (other than through an openable window) in the external wall, or
(i) due to a sudden change of level within or associated with a building; or
(b) 2 m or more from a floor through an openable window in a bedroom; or
(c) 4 m or more from a floor through an openable window not covered by (b).
(2) A barrier required by (1) must be—
(a) continuous and extend for the full extent of the hazard; and
(b) of a height of not less than 1.2 m; and
(c) constructed to prevent people from falling through the barrier; and
(d) capable of restricting the passage of children; and
(e) of a strength to withstand—
(i) the foreseeable impact of people; and
(ii) where appropriate, the static pressure of people pressing against it.

H5D2 Stairway and ramp construction

Compliance with Part 11.2 of the ABCB Housing Provisions satisfies Performance Requirement H5P1 for stairway and ramp construction.

H5D3 Barriers and handrails

Compliance with Part 11.3 of the ABCB Housing Provisions satisfies Performance Requirement H5P2 for barriers and
H5P1(b)(i) for handrails.

Part H6 Energy efficiency

H6P1 Thermal performance

(1) The total heating load of the habitable rooms and conditioned spaces in a building must not exceed the heating load limit in Specification 44.
(2) The total cooling load of the habitable rooms and conditioned spaces in a building must not exceed the cooling load limit in Specification 44.
(3) The total thermal energy load of the habitable rooms and conditioned spaces in a building must not exceed the thermal energy load limit in Specification 44.

H6P2 Energy usage

(1) The energy value of a buildings domestic services must not exceed 70% of the energy value with—
(a) 3-star ducted heat pump, rated under the 2019 GEMS determination, heating all spaces that are provided with heating; and
(b) a 3-star ducted heat pump, rated under the 2019 GEMS determination, cooling all spaces that are provided with cooling; and
(c) a 5-star instantaneous gas water heater, rated under the 2017 GEMS determination, providing all domestic hot water; and
(d) a lighting power density of 4 W/m2 serving all internal spaces that are provided with artificial lighting.

(2) Domestic services, including any associated distribution system and components must, to the degree necessary, have features that facilitate the efficient use of energy appropriate to—
(a) the domestic service and its usage; and
(b) the geographic location of the building; and
(c) the location of the domestic service; and
(d) the energy source.

Part H7 Ancillary provisions and additional construction requirements

H7P1 Swimming pool access

A barrier must be provided to a swimming pool and must—
be continuous for the full extent of the hazard; and
(a) be of a strength and rigidity to withstand the foreseeable impact of people; and
(b) restrict the access of young children to the pool and the immediate pool surrounds; and
(c) have any gates and doors fitted with latching devices not readily operated by young children, and constructed
(d) to automatically close and latch.

H7P3 Heating appliances

A heating appliance and its associated components within a building, including an open fire-place, chimney, or the like, must be installed—
(a) to withstand the temperatures likely to be generated by the appliance; and
(b) so that it does not raise the temperature of any building element to a level that would adversely affect the element's physical or mechanical properties or function; and
(c) so that hot products of combustion will not—
(i) escape through the walls of the associated components; and
(ii) discharge in a position that will cause fire to spread to nearby combustible materials or allow smoke to penetrate through nearby windows, ventilation inlets, or the like in the building containing the heating appliance.

H7P4 Buildings in alpine areas

(1) An external doorway from a building in an alpine area must be installed so that opening the door is not obstructed by snow or ice.
(2) A building in an alpine area containing external trafficable structures forming part of the means of egress must be constructed so that they remain, as far as practicable, useable under snow conditions.
(3) A building in an alpine area must be constructed so that snow or ice is not shed from the building onto the allotment, any adjoining allotment, road or public space in a location or manner that will—
(a) obstruct a means of egress from any building to a road or open space; or
(b) otherwise endanger people.

H7P5 Buildings in bushfire prone areas

A Class 1 building or a Class 10a building or deck associated with a Class 1 building that is constructed in a designated bushfire prone area must be designed and constructed to—
(a) reduce the risk of ignition from a design bushfire with an annual exceedance probability not more than 1:50 years; and take account of the assessed duration and intensity of the fire actions of the design bushfire; and
(b) be designed to prevent internal ignition of the building and its contents; and
(c) maintain the structural integrity of the building for the duration of the design bushfire.

H7V1 Combustion appliances

Compliance with H7P3(a) and (b) is verified when—
(a) components used within an appliance and its installation are constructed from—
(i) heat-resistant materials for maximum operating temperatures more than 600°C, where the material complies
(ii) heat-tolerant materials for maximum operating temperatures more than 150°C and less than 600°C, where (ii) the material complies with
(b) the building elements surrounding the appliance maintain their designed function and material properties inclusive of a full range of thermal movements when exposed to the heat effects of the appliance; and
(c) a sample of the material is tested to the maximum operating temperature, specified in (a)(i) or (a)(ii) for a (c) minimum of 96 hours; and

(d) The tested sample, when allowed to cool, must be free from—
(i) visible cracks and fractures
(ii) visible indication of de-lamination
(iii) linear distortion in excess of the equivalent of 10 mm per metre.
(iv) deterioration of the appearance of any surface finish, when compared to an unheated sample.

H7D5 Swimming pools

(1) Performance Requirement H7P1 is satisfied for a swimming pool with a depth of water more than 300 mm and which is associated with a Class 1 building, if it has safety barriers installed in accordance with AS 1926.1 and AS 1926.2.
(2) Performance Requirement H7P2 is satisfied for a water recirculation system of a swimming pool with a depth of water more than 300 mm, if it complies with AS 1926.3.

H7D5 Heating appliances, fireplaces, chimneys and flues

Performance Requirement H7P3 is satisfied for a heating appliance if it is installed in accordance with—
(a) for a domestic solid fuel burning appliance, AS/NZS 2918
(b) for a heating appliance, Part 12.4 of the ABCB Housing Provisions.

Part H2 Damp and weatherproofing

H2F1 Surface water

A building including any associated sitework is to be constructed in a way that protects people and other property from the adverse effects of redirected surface water.

H2F2 Weatherproofing and dampness

A building is to be constructed to provide resistance to moisture from the outside and moisture rising from the ground.

Limitations

H2F2 does not apply to a Class 10 building except where its construction contributes to the weatherproofing of the Class 1 building.

H2F3 Drainage from swimming pools

Adequate means for the disposal of swimming pool water and drainage is to be provided to a swimming pool.

H2P2 Weatherproofing

A roof and external wall (including openings around windows and doors) must prevent the penetration of water that could cause—
(a) unhealthy or dangerous conditions, or loss of amenity for occupants
(b) undue dampness or deterioration of building elements.

Note: Bushfire

The Building Construction to be done in accordance with BAL-12.5 Rating & comply with Planning for Bushfire Protection & AS 3959-2018 and refer the BAL- report for the details


SUMMARY OF CONSTRUCTION REQUIREMENTS FOR BAL12.5:

EXTERNAL WALL:
EXTERNAL WALL COVERING TO BE NON-COMBUSTIBLE OR COMPLYING TIMBER SPECIES WITHIN 400MM OF SURFACE LEVEL. ALL JOINTS ARE TO BE LESS THAN 3 MM. VENTS AND WEEPHOLES TO BE SCREENED WITH A MESH WITH A MAXIMUM APERTURE OF 2 MM, MADE OF CORROSION-RESISTANT STEEL, BRONZE OR ALUMINIUM, EXCEPT WHERE SHARKING LIKE MATERIAL IS USED IN WALL.

WINDOWS AND DOORS/GARAGE DOOR:
WINDOWS ASSEMBLIES TO BE METAL OR BUSHFIRE-RESISTING TIMBER. ALL GLAZING GREATER THAN 400 MM FROM THE GROUND SHALL BE ANNEALED. GLAZING LESS THAN 400 MM FROM GROUND SHALL BE GRADE A SAFETY GLASS MINIMUM 4MM THICK. WHERE FITTED, OPENABLE PORTIONS OF WINDOWS SCREENED WITH ALUMINIUM, STEEL, OR BRONZE FLY SCREEN WITH A MAXIMUM APERTURE OF 2 MM. DOORS HAVE SIMILAR REQUIREMENTS TO WINDOWS REGARDING FRAMES AND GLAZING. GAPS MORE THAN 3MM AROUND DOOR ARE TO BE SEALED. GARAGE DOOR TO BE NON-COMBUSTIBLE FITTED WITH NYLON BRUSH.

ROOF:
2ROOF MATERIAL TO BE A NON-COMBUSTIBLE AND FULLY SARKED. SARKING MATERIAL TO HAVE A SARKING FLAMMABILITY INDEX OF NOT MORE THAN 5 AND INSTALLED DIRECTLY BELOW TILE BATTENS. ALL JOINTS TO BE SEALED AND ROOF PENETRATIONS TO BE SCREENED TO PREVENT THE ENTRY OF EMBERS.

Typical FRL - 60/60/60 Details - Party Wall



A single leaf of 90 mm clay brick masonry with —

(a) a row of 70 mm × 35 mm timber studs or 64 mm steel studs at 600 mm centres, spaced 20 mm from each face of the masonry wall; and

(b) 50 mm thick mineral insulation or glass wool insulation with a density of 11 kg/m³ positioned between studs in each row; and

(c) one layer of 13 mm plasterboard fixed to studs on each outside face,

has an Rw + Ctr of not less than 50, if constructed in accordance with Figure

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

NOTES:

BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE BUILDING ACT, 1993, REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONCRETE SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

COVER PAGE NOTES

Project number	070624	A101	
Date	26.08.2026		
Drawn by	Checked by		
FS	NS		
		Scale	1 : 100

SHEET INDEX	
SHEET NUMBER	SHEET NAME
A000	COVER PAGE
A001	FACADE RENDER
A101	COVER PAGE NOTES
A102	SITE ANALYSIS
A103	SITE PLAN
A104	CUT AND FILL LAYOUT PLAN
A105A	AREA CALCULATIONS CDC
A106	LANDSCAPE PLAN
A107	STORMWATER DRAINAGE LAYOUT PLAN
A108	SEDIMENT AND EROSION CONTROL PLAN
A108A	CONCRETE SLAB PLAN
A109	SHADOW DIAGRAM
A110	GROUND FLOOR PLAN
A111	FIRST FLOOR PLAN
A112	ROOF PLAN
A113	ELEVATIONS
A114	ELEVATIONS
A115	BUILDING SECTION
A116	DOOR & WINDOWS SCHEDULE & LEGEND COMPONENT DETAIL
A117	MATERIAL & FINISHES SCHEDULE
A118	MATERIAL & FINISHES SCHEDULE
A120	BASIX COMMITMENT

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026



1 SITE ANALYSIS
1: 150

SITE ANALYSIS LEGEND	
SITE BOUNDARY 1800MM HIGH	---
PROPOSED BUILDING	PB
NEIGHBOURHOOD PROPERTIES	NP
PRIVATE OPEN SPACE	POS
WIND DIRECTION	↗

Designed By:

SYDNEY DESIGNERS
AND PLANNERS

CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

SITE ANALYSIS			
Project number	070624	A102	
Date	26.08.2026		
Drawn by	Checked by	Scale	
FS	NS		
		As indicated	

BUILDING SPECIFICATION NOTES:

NATIONAL CONSTRUCTION CODE – VOLUME 2 – BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022

SITE PREPARATION
- PART 3.1
EARTHWORKS
- TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979 AND DEVELOPMENT CONSENT CONDITIONS
- PART 3.2 - AS 4678:2002 - EARTH-RETAINING STRUCTURES

DRAINAGE
- PART 3.3 - AS/NZS 3500.1:2021 - PLUMBING & DRAINAGE - WATER SERVICES
- AS/NZS 3500.2:2021 - PLUMBING & DRAINAGE - SANITARY PLUMBING & DRAINAGE
- AS/NZS 3500.3:2021 - PLUMBING & DRAINAGE - STORMWATER DRAINAGE
- AS/NZS 3500.4:2021 - PLUMBING & DRAINAGE - HEATED WATER SERVICES

STRUCTURAL WORK
- PART 2.2 - AS 4100:2020 - STEEL STRUCTURES CODES
- AS/NZS 1170.0:2002 – GENERAL PRINCIPLES
- AS/NZS 1170.1:2002 – PARTS 1 PERMANENT, IMPOSED AND OTHER ACTIONS
- AS/NZS 1170.2:2021 – PART 2 WIND ACTIONS
- AS 3700:2018 - SAA MASONRY CODE
- AS 1684.3:2021- RESIDENTIAL TIMBER FRAMED CONSTRUCTION

FOOTINGS & SLABS
- PART 4 - AS 2159:2009 - PILING - DESIGN & INSTALLATION
- AS 2870:2011 - RESIDENTIAL SLABS & FOOTINGS
- AS 3600:2018 - CONCRETE STRUCTURES

MASONRY
- PART 5 - AS 3700:2018 - MASONRY STRUCTURES

FRAMING
- PART 6- AS 1684.2:2021 - RESIDENTIAL TIMBER-FRAMED CONSTRUCTION - NON-CYCLONIC AREAS
- AS 1720.1:2010 - TIMBER STRUCTURES -DESIGNMETHODS
- AS 4100:2020 - STEEL STRUCTURES
- AS 3660.1:2014 – TERMITE MANAGEMENT SYSTEM

ROOF & WALL CLADDING
- PART 7 - AS 1273:1991 - UNPLASTICIZED PVC (UPVC) DOWNPIPES & FITTINGS FOR RAINWATER
- AS 1562.1:2018 - DESIGN & INSTALLATIONOF SHEET ROOF & WALL CLADDING - METAL
- AS/NZS 1562.2:1999 - DESIGN & INSTALLATION OF SHEET ROOF & WALLCLADDING - CORRUGATED FIBRE- REINFORCED CEMENT
- AS/NZS 1562.3:2006 - DESIGN & INSTALLATIONOF SHEET ROOF & WALLCLADDING - PLASTIC
- AS 2049:2002 - ROOF TILES
- AS 2050:2018 - INSTALLATION OF ROOF TILES
- AS 4285:2019 – ROOFLIGHTS

GLAZING
- PART 8- AS 1288:2021 - GLASS IN BUILDINGS -SELECTION & INSTALLATION
- AS 2047:2014 - WINDOWS & EXTERNALGLAZEDOORS IN BUILDINGS
- AS/NZS 2208:1996 - SAFETY GLAZING MATERIALS IN BUILDINGS

FIRE SAFETY
- PART 9- AS 3786:2014 - SMOKE ALARMS USING SCATTERED LIGHT, TRANSMITTED LIGHTOR IONIZATION

HEALTH & AMENITY
- PART 10- AS/NZS ISO 717.1:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS -AIRBORNE SOUND INSULATION
- AS ISO 717.2:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - IMPACT SOUND INSULATION
- AS 1668.2:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - MECHANICAL VENTILATIONIN BUILDINGS
- AS 1668.4:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - NATURAL VENTILATION OFBUILDINGS
- AS/NZS 1680.0:2009 - INTERIOR LIGHTING
- SAFE MOVEMENT
- AS 3740:2021 - WATERPROOFING OF DOMESTIC WET AREAS
- AS 3000:2018 – ELECTRICAL INSTALLATION

ATERPROOFING
- AS 3740:2021 – WATERPROOFING TOWET AREA
- AS 4654:2012 – EXTERNAL WET AREAS

SAFE MOVEMENT & ACCESS
- PART 11- AS 1428.1:2009 - DESIGN FOR ACCESS &MOBILITY
- GENERAL REQUIREMENTS FOR ACCESS - NEWBUILDING WORK
- AS 1657:2018 - FIXED PLATFORMS, WALKWAYS, STAIRWAYS & LADDERS - DESIGN, CONSTRUCTION & INSTALLATION

HANDRAILS & BALUSTRADE
- PART 11.3.3 - PART 11.3.4 - PART 11.3.5- AS 1170.1:2002 – BALUSTRADEINSTALLATION

PROTECTION OF OPENABLE WINDOW
PART 11.3.7 AND 11.3.8

DEMOLITION
- AS 2601:2001 – DEMOLITION WORK

SWIMMING POOL
- PART 12.1.1 (H7D2)- AS 1926 PART 1:2012 – SWIMMING POOLSAFETY- SAFETY BARRIERS FOR SWIMMING POOLS
- AS 1926 PART 2:2007 - SWIMMING POOL SAFETY- LOCATION OF SAFETY BARRIERS FOR SWIMMING POOLS (INCORPORATING AMENDMENTS 1 AND 2)
- AS 1926 PART 3:2010 – SWIMMING POOL SAFETY- WATER RECIRCULATION SYSTEMS (INCORPORATING AMENDMENT 1)

ENERGY EFFICIENCY
- PART 13 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022 & BASIX Certificate

WE RELY ON SURVEY PROVIDED FOR SITE BOUNDARIES , LEVELS, EASEMENTS , SERVICES ETC.
OWNER SHOULD CHECK ANY INCONSISTENCIES PRIOR TO COMENCEMENT OF ANY WORK ON SITE.

PARAGON

Paragon Building Certifiers Pty Ltd

RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026

SITE PLAN
1 : 150

Riser and going dimensions (mm)

Stair type	Riser (R)		Going (G)		Slope relationship (2R+G)	
	Max	Min	Max	Min	Max	Min
Stairs	190	115	355	240	700	550

GENERAL NOTES:

- ALL WORKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH COUNCIL WORKS STANDARD AND TO THE SPECIFICATION.
- THE CONSTRUCTION SHALL REVIEW, BE AWARE AND AT ALL TIMES COMPLY WITH THE SPECIFIC REQUIREMENTS FOR THIS DEVELOPMENT AS SET OUT IN THE DEVELOPMENT APPROVAL FOR THE PROJCT.
- ENSURE ALL FILL IS PLACED IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARDS, GEOTECHNICAL ENGINEER AND STRUCTURAL ENGINEER NOTES AND SPECIFICATION.
- THE FILL IS TO BE COMPACTED IN ACCORDANCE WITH AS2870-2011 SECTION6.4.
- CUT/FILL DEPTHS DENOTED ON THIS PLAN ARE APPROXIMATELY ONLY. IF DIFFER CONTACT THIS OFFICE FOR ARRANGEMENT.
- LEVELS SHOWN ARE APPROXIMATE ONLY AND TO BE CONFIRMED ON SITE BY BUILDER/SURVEYOR.
- THE SITE SHALL BE KEPT IN A TIDY CONDITION AT ALL TIMES. LITTER RUBBISH AND BUILDING RUBBLE SHALL BE PLACED IN CONTAINERS OR BINS AND REGULARLY REMOVED FROM SITE AS REQUIRED.
- THE WORK SHALL BE CONSTRUCTED IN SUCH A MANNER THAT THERE IS MINIMUM DISTURBANCE TO EXISTING TREES AND VEGETATION.

SITE NOTES:
ONE OUTDOOR CLOTHES LINE ROTARY OR FIXED ON WALLMUST BE INSTALLED AS SELECTED BY CLIENT
RETAINING WALL AS PER ENG'S DETAILS (IF REQUIRED) THE CUT & FILL CALCULATIONS ARE BASED ON WAFFLE POD SLAB CONSTRUCTION

CUT AND FILL LAYOUT PLAN NOTES:
1. DRAWING TO BE READ IN CONJUNCTION WITH ARCHITECTURALS
2. REFER TO ARCHITECTURAL DRAWINGS FOR ALL SETOUT, LEVELS, FALL, ETC.

CHARGED STORMWATER SYSTEM CANNOT BE USED FOR DISPOSAL OF DRIVEWAY OR OTHER SURFACE STORMWATER, OWNER IS TO PROVIDE ALTERNATE DISCHARGE LINES IF DOWNPIPES ARE NOTED AS CDP ON PLAN. THE BUILDER PROVIDES CAPACITY FOR DISPOSAL OF ROOF COLLECTED STORMWATER ONLY AND TAKES NO RESPONSIBILITY FOR OVERFLOW OR DAMAGE TO PROPERTY IF OWNER ADDS ADDITIONAL DISCHARGE LOADS TO EXISTING STANDARD PROVISIONS.
+/- 100MM TOLERANCE TO NOM INATED FINISHED FLOOR LEVELS.
SUBJECT TO MAXIMUM DRIVEWAY PROFILE AND/OR ANY FLOOD RELATED LEVELS.


Note: Bushfire
The Building Construction to be done in accordance with BAL-12.5 Rating & comply with Planning for Bushfire Protection & AS 3959-2018 and refer the BAL- report for the details

SUMMARY OF CONSTRUCTION REQUIREMENTS FOR BAL12.5:

EXTERNAL WALL:
EXTERNAL WALL COVERING TO BE NON-COMBUSTIBLE OR COMPLYING TIMBER SPECIES WITHIN 400MM OF SURFACE LEVEL. ALL JOINTS ARE TO BE LESS THAN 3 MM. VENTS AND WEEPHOLES TO BE SCREENED WITH A MESH WITH A MAXIMUM APERTURE OF 2 MM. MADE OF CORROSION-RESISTANT STEEL, BRONZE OR ALUMINIUM, EXCEPT WHERE SHARKING LIKE MATERIAL IS USED IN WALL.

WINDOWS AND DOORS/GARAGE DOOR:
WINDOWS ASSEMBLIES TO BE METAL OR BUSHFIRE-RESISTING TIMBER. ALL GLAZING GREATER THAN 400 MM FROM THE GROUND SHALL BE ANNEALED. GLAZING LESS THAN 400 MM FROM GROUND SHALL BE GRADE A SAFETY GLASS MINIMUM 4MM THICK. WHERE FITTED, OPENABLE PORTIONS OF WINDOWS SCREENED WITH ALUMINIUM, STEEL, OR BRONZE FLY SCREEN WITH A MAXIMUM APERTURE OF 2 MM. DOORS HAVE SIMILAR REQUIREMENTS TO WINDOWS REGARDING FRAMES AND GLAZING. GAPS MORE THAN 3MM AROUND DOOR ARE TO BE SEALED. GARAGE DOOR TO BE NON-COMBUSTIBLE FITTED WITH NYLON BRUSH.

ROOF:
2ROOF MATERIAL TO BE A NON-COMBUSTIBLE AND FULLY SARKED. SARKING MATERIAL TO HAVE A SARKING FLAMMABILITY INDEX OF NOT MORE THAN 5 AND INSTALLED DIRECTLY BELOW TILE BATTENS. ALL JOINTS TO BE SEALED AND ROOF PENETRATIONS TO BE SCREENED TO PREVENT THE ENTRY OF EMBERS.



DRIVEWAY LONGITUDINAL SECTION
1 : 75

Designed By:	CLIENT:	No.	Description	Date	SITE PLAN
	LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560	C	Revised as per the comments	04.05.2026	Project number 070624
		D	Revised as per the comments	14.05.2026	Date 26.08.2026
		E	Revised as per the comments	22.05.2026	Drawn by FS
		F	Revised as per the CDc checklist	01.06.2026	Checked by NS
		G	Revised as per the engineers comments	01.07.2026	Scale
		H	Revised windows, doors & kitchen sink	26.08.2026	As indicated

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

CUT & FILL LEGEND		
APPROX CUT		
APPROX FILL		

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026



1 CUT&FILL PLAN
1 : 150

CUT AND FILL LAYOUT PLAN NOTES:

1. DRAWING TO BE READ IN CONJUNCTION WITH ARCHITECTURALS.
2. REFER TO ARCHITECTURAL DRAWINGS FOR ALL SETOUT, LEVELS. FALL, ETC.
- GENERAL NOTES:
1. ALL WORKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH COUNCIL WORKS STANDARD AND TO THE SPECIFICATION.
2. THE CONSTRUCTION SHALL REVIEW, BE AWARE AND AT ALL TIMES COMPLY WITH THE SPECIFIC REQUIREMENTS FOR THIS DEVELOPMENT AS SET OUT IN THE DEVELOPMENT APPROVAL FOR THE PROJCT.
3. ENSURE ALL FILL IS PLACED IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARDS, GEOTECHNICAL ENGINEER AND STRUCTURAL ENGINEER NOTES AND SPECIFICATION.
4. THE FILL IS TO BE COMPACTED IN ACCORDANCE WITH AS2870-2011 SECTION64.
5. CUT/FILL DEPTHS DENOTED ON THIS PLAN ARE APPROXIMATELY ONLY. IF DIFFER CONTACT THIS OFFICE FOR ARRANGEMENT.
6. LEVELS SHOWN ARE APPROXIMATE ONLY AND TO BE CONFIRMED ON SITE BY BUILDER SURVEYOR.
7. THE SITE SHALL BE KEPT IN A TIDY CONDITION AT ALL TIMES. LITTER RUBBISH AND BUILDING RUBBLE SHALL BE PLACED IN CONTAINERS OR BINS AND REGULARLY REMOVED FROM SITE AS REQUIRED.
8. THE WORK SHALL BE CONSTRUCTED IN SUCH A MANNER THAT THERE IS MINIMUM DISTURBANCE TO EXISTING TREES AND VEGETATION.

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

CUT AND FILL LAYOUT PLAN

Project number	070624	A104	
Date	26.08.2026		
Drawn by	Checked by		
FS	NS	Scale	As indicated


CDC CALCULATION

Site Area	465.10 sqm
Max Floor Coverage Allowed	290.0 sqm
Max Floor Coverage Proposed	278.29 sqm
Landscape Area Required	93.02 sqm (20% of Site Area)
Total Landscape Area Proposed	156.74 sqm (33.70% of Site Area)
Private Open Space Required	24.0 sqm
Private Open Space Provided	95.95 sqm


(Area measured from internal face of outerwall and does not include area of Porch, Alfresco, voids balcony and single garage)

SETBACKS:	
REQUIRED:	PROVIDED:
Front Articulation zone = 3.50m	4.01m
Front setback = 4.50m or average	4.50m
Garage setback = 5.5m	5.81m
Side setbacks:	Side setbacks:
Side = 0.90 (GF) 2.2(F.F)	Side = 1.66m (GF), 6.12m (F.F)
Rear setbacks: 3.0 (GF) 8.0 (F.F)	Rear setbacks: 7.60m (GF)
	9.49m (F.F)
Reference: 260314/02	
Date: 18/09/2026	

AREA SCHEDULE		
Name	Area	Area in Squares
GARAGE	38.85 m²	4.18 m²
GRANNY	54.66 m²	5.88 m²
PORCH	6.43 m²	0.69 m²
GROUND FLOOR	127.17 m²	13.69 m²
BALCONY	11.36 m²	1.22 m²
FIRST FLOOR	115.37 m²	12.42 m²
Grand total	353.84 m²	38.09 m²



1 GROUND FLOOR AREA
1 : 150



3 GROUND FLOOR
1 : 150



2 FIRST FLOOR AREA
1 : 150



4 FIRST FLOOR
1 : 150

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

AREA CALCULATIONS CDC

Project number	070624	A105A
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		1 : 150

SITE LEGEND	
SITE BOUNDARY 1800MM HIGH	
FENCE LINE	
DROP EDGE BEAM	
POS AREA	
CLOTHES LINE	CL



Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02


Date: 18/08/2026



LANDSCAPE PLAN


1 : 150

PLANTING DETAILS



1. TURF & GARDEN EDGE DETAIL

NOTE:
ALIGNMENT OF BRICK EDGE SHALL BE EVEN & FREE FROM
DIPS AND HUMPS.



2. TREE & SHRUB PLANTING IN GARDEN BED

NOTE:
DO NOT PLANT IN UNSUITABLE WEATHER CONDITIONS
SUCH AS EXTREME HEAT, COLD, WIND OR RAIN.
CLAY SOIL IS TO BE TREATED WITH CLAY BREAKER
AND ORGANIC COMPOST

PLANTING SCHEDULE

Mark	Type	NATIVE	POT SIZE	HEIGHT	Count	Image
HEDGE						
AS	Amena Smithii	YES	200MM	1.8m	6	
MP	Murraya Paniculata (Orange Jessamine)	YES	200MM	1.8m	10	
SHRUB						
DS	Dianella 'Silver Streak'	YES	150MM	500mm	3	
TREE						
EE	Baeocarpus Eumundii	YES	100L	1.5M	1	
WF	Waterhousea floribunda	YES	45L	8M	1	

LANDSCAPE NOTES

- THIS PLAN INDICATES THE GENERAL LANDSCAPE ARRANGEMENT ONLY AND IS NOT FOR CONSTRUCTION.
- ALL WEEDS TO BE REMOVED FROM SITE BY PHYSICAL REMOVAL OR BY SPRAYING HERBICIDE.
- ALL LANDSCAPED AREA TO HAVE A MINIMUM 1:100 FALL TO STORMWATER OUTLET POINT. REFER TO DRAINAGE DIAGRAM.
- MULCH LEVEL IN GARDEN BEDS IS TO BE MAINTAINED MINIMUM AT 75mm.
- EXCAVATE HOLE FOR PLANTING 200mm DEEPER AND 300mm WIDER THAN THE SIZE OF THE POT.
- ALL GARDEN BEDS ARE TO BE PREPARED WITH A MIX OF GOOD QUALITY TOPSOIL AND ORGANIC FERTILIZER TO A DEPTH OF 300mm AS SHOWN IN THE TREE PLANTING DETAIL.
- TURF AREAS ARE TO BE PREPARED WITH A MINIMUM OF 150mm GOOD QUALITY TOPSOIL.
- ALL PLANTS ARE TO BE PERIODICALLY PRUNED TO AN APPROPRIATE SIZE AND SPREAD.
- ALL FLOOR LEVELS SHOWN ARE APPROXIMATE ONLY.
- EXACT LEVELS TO BE DETERMINED ON SITE.
- NOMINATED PLATFORM LEVELS MAY VARY PLUS OR MINUS 100mm.

SPECIFICATIONS

Driveway	Proposed coloured concrete
Patio	Proposed Material
Steppingstones	400 x 400 mm stones on selected tiles with gravel bed.
Soils	All soil types as per Australian native landscape supply or equivalent
Lawn Area	1st Quality topsoil
Garden Bed	Native garden mix.
Lawn	Refer to detail 1 Sir Walter Buffalo No obvious signs of weed infestation in grass areas. pavements or moss planting beds.
Mulch	Refer to detail 1 & 2 Selected hard wood chip. Decorative gravel to OSD area.
Plant Material	As per planting Schedule No visible signs of wilting of leaves or stems, with all plant to be gully turfed always. Performance of planting will be indicated by new growth with visible sign of new leaves, plants to possess a level of greenness characteristics with the particular species, strong floral habitat and colour appropriate to the season and species. Absence of dead or damaged foliage, flowers or branches.
Illumination	Selected Samples
Fence	Selected Material
Hedge	Hedge planting to screen the backyard as shown.

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description
C	Revised as per the comments
D	Revised as per the comments
E	Revised as per the comments
F	Revised as per the CDC checklist
G	Revised as per the engineers comments
H	Revised windows, doors & kitchen sink

Date

04.05.2026
14.05.2026
22.05.2026
01.06.2026
01.07.2026
26.08.2026

LANDSCAPE PLAN

Project number	070624	A106
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		As indicated




Paragon Building Certifiers Pty Ltd
RBC00045

Registered Certifier
APPROVED
Reference: 260314/02
Date: 18/09/2026

RAINWATER TANK
FOR RE-USE

TANK SIZE SUBJECT TO CHANGE
TO COUNCIL AND BASIX
REQUIREMENTS
BASE RL: 89.800



CONNECTING TO EXISTING
STORMWATER PIT WITHIN
EASEMENT
SL: 89.040
IL: 88.740 OR LOWER TO SUIT

BALCONY FLOORWASTE
- NOT TO BE CONNECTED
TO RAINWATER TANK
FOR RE-USE

LEGEND

PL 0.00	PAVEMENT LEVEL
TOP 0.000	TOP OF PIT
INLET 0.000	INVERT LEVEL OF INLET PIPE
OUTLET 0.000	OUTLET INVERT LEVEL
FFL xx.xxx	FINISHED FLOOR LEVEL
1000 AT 1 IN 100	STORMWATER DRAIN
CHARGED STORMWATER LINE	
SWALE DRAIN	
SUBSOIL DRAINAGE	
EASEMENT LINE	
BOUNDARY LINE	
EXISTING RETAINING WALL/BLOCK	
RETAINING WALL	
RAINWATER TANK (REFER DETAIL ON S003)	
DIRECTION OF SURFACE RUNOFF 120 MIN	
DOWNPIPE (1000 UN.O.)	
SPREADER PIPE	
INSPECTION OPENING	
CAPPED RISER	
GRATED PIT	
PROPOSED CONCRETE DRIVEWAY	
TRENCH DRAINAGE	



NOTES:

- BUILDER TO ENSURE THAT ROOF GUTTER SIZE AND SLOPE TO COMPLY WITH AS3500.3 AND BCA REQUIREMENTS
- ALL STORMWATER GRAVITY PIPES TO HAVE MIN 1% FALL U.N.O.
- MIN. 200mm COVER TO BE PROVIDED FOR ALL STORMWATER PIPES. IF THE STORMWATER PIPES HAVE LESS THAN 200mm COVER, ADDITIONAL CARE TO BE TAKEN BY BUILDERS TO PROTECT PIPE DURING CONSTRUCTION
- THIS OFFICE IS TO BE NOTIFIED BEFORE THE COMMENCE OF THE CONSTRUCTION WORKS IF THE CONCEPT DESIGN CANNOT BE ACHIEVED

REFER TO ENDORSED PLAN FOR REMOVAL
& PROTECTION OF TREES.

WATER TANK STORAGE TO BE REUSED
FOLLOWING BASIX AND COUNCIL
REQUIREMENTS

1000mm OVERFLOW FROM WATER TANKS
TO BE CONNECTED TO UNDERGROUND
DRAINAGE SYSTEM (TYPICAL)



Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560


*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026


STORMWATER DRAINAGE LAYOUT PLAN

Project number	070624	A107
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale




1 : 100


Project number	070624	A108A
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale 1 : 100




① SHADOW ANALYSIS 9AM - 21 JUNE
1 : 300




④ SHADOW ANALYSIS 12PM - 21 JUNE
1 : 300




⑤ SHADOW ANALYSIS 1PM - 21 JUNE
1 : 300




② SHADOW ANALYSIS 10AM - 21 JUNE
1 : 300



⑦ SHADOW ANALYSIS 3PM - 21 JUNE
1 : 300



③ SHADOW ANALYSIS 11AM - 21 JUNE
1 : 300



⑥ SHADOW ANALYSIS 2PM - 21 JUNE
1 : 300

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560


*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

SHADOW DIAGRAM

Project number	070624	A109
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		1 : 300



A single leaf of 90 mm clay brick masonry with—

(a) a row of 70 mm x 35 mm timber studs or 64 mm steel studs at 600 mm centres, spaced 20 mm from each face of the masonry wall; and

(b) 50 mm thick mineral insulation or glass wool insulation with a density of 11 kg/m³ positioned between studs in each row; and(c) one layer of 13 mm plasterboard fixed to studs on each outside face, has an R_w + C_{tr} of not less than 50, if constructed in accordance with Figure**PARAGON**

Paragon Building Certifiers Pty Ltd

RBC00045


Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026

WATERPROOFING WORK TO BE AS PER PART 10.2 OF THE ABCB HOUSING PROVISIONS STANDARD 2022

**1 GROUND FLOOR**
1 : 100**Note: Bushfire**

The Building Construction to be done in accordance with BAL-12.5 Rating & comply with Planning for Bushfire Protection & AS 3959-2018 and refer the BAL- report for the details

SUMMARY OF CONSTRUCTION REQUIREMENTS FOR BAL12.5:

EXTERNAL WALL:
EXTERNAL WALL COVERING TO BE NON-COMBUSTIBLE OR COMPLYING TIMBER SPECIES WITHIN 400MM OF SURFACE LEVEL. ALL JOINTS ARE TO BE LESS THAN 3 MM. VENTS AND WEEPHOLES TO BE SCREENED WITH A MESH WITH A MAXIMUM APERTURE OF 2 MM, MADE OF CORROSION-RESISTANT STEEL, BRONZE OR ALUMINIUM, EXCEPT WHERE SHARKING LIKE MATERIAL IS USED IN WALL.

WINDOWS AND DOORS/GARAGE DOOR:
WINDOWS ASSEMBLIES TO BE METAL OR BUSHFIRE-RESISTING TIMBER. ALL GLAZING GREATER THAN 400 MM FROM THE GROUND SHALL BE ANNEALED. GLAZING LESS THAN 400 MM FROM GROUND SHALL BE GRADE A SAFETY GLASS MINIMUM 4MM THICK. WHERE FITTED, OPENABLE PORTIONS OF WINDOWS SCREENED WITH ALUMINIUM, STEEL, OR BRONZE FLY SCREEN WITH A MAXIMUM APERTURE OF 2 MM. DOORS HAVE SIMILAR REQUIREMENTS TO WINDOWS REGARDING FRAMES AND GLAZING. GAPS MORE THAN 3MM AROUND DOOR ARE TO BE SEALED. GARAGE DOOR TO BE NON-COMBUSTIBLE FITTED WITH NYLON BRUSH.

ROOF:
2ROOF MATERIAL TO BE A NON-COMBUSTIBLE AND FULLY SARKED. SARKING MATERIAL TO HAVE A SARKING FLAMMABILITY INDEX OF NOT MORE THAN 5 AND INSTALLED DIRECTLY BELOW TILE BATTENS. ALL JOINTS TO BE SEALED AND ROOF PENETRATIONS TO BE SCREENED TO PREVENT THE ENTRY OF EMBERS.

Designed By:

**CLIENT:****LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560***COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

GROUND FLOOR PLAN

Project number	070624	A110
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		1 : 100

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026



Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560


*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.



No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

FIRST FLOOR PLAN

Project number	070624	A111
Date	26.08.2026	
Drawn by	Checked by	Scale
FS	NS	
		1:100



1 ROOF PLAN
1 : 100




VENTILATION OF ROOF SPACES

ROOF SPACE AS PER 10.8.3.1(a)

(i) VENTILATED TO OUTDOOR AIR THROUGH EVENLY DISTRIBUTED OPENINGS IN ACCORDANCE WITH TABLE 10.8.3; OR

TABLE 10.8.3: ROOF SPACE VENTILATION REQUIREMENTS

ROOF PITCH	VENTILATION OPENINGS
< 10°	25,000 MM2/M PROVIDED AT EACH OF TWO OPPOSING ENDS
≥ 10° AND < 15°	25,000 MM2/M PROVIDED AT THE EAVES AND 5,000 MM2/M AT HIGH LEVEL
≥ 15° AND < 75°	7,000 MM2/M PROVIDED AT THE EAVES AND 5,000 MM2/M AT HIGH LEVEL, PLUS AN ADDITIONAL 18,000 MM2/M AT THE EAVES IF THE ROOF HAS A CATHEDRAL CEILING



WATERPROOFING NOTES

ALL WET AREA WATERPROOFING SHALL COMPLY WITH AS 3740:2021 AND NCC 2022 HOUSING PROVISIONS CLAUSES 10.2.1 TO 10.2.6 AND 10.2.12.

WATERPROOFING MEMBRANES SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS BY A LICENSED WATERPROOFING CONTRACTOR.

SHOWER WALLS TO BE WATERPROOFED TO A MINIMUM HEIGHT OF 1800mm ABOVE FINISHED FLOOR LEVEL.

ALL FLOOR/WALL JUNCTIONS, PENETRATIONS, WASTES, HOBS AND THRESHOLDS TO BE FULLY SEALED AND WATERPROOFED.

FLOORS SHALL BE GRADED TO FLOOR WASTES WITH FALLS IN ACCORDANCE WITH NCC 2022 CLAUSE 10.2.12.

ROOF AND GUTTERS

- BRICK PARAPET CONSTRUCTION TO BE IN ACCORDANCE WITH CLAUSE 3.3.1.2 OF BCA
- ALL ROOF CLADDING IS TO BE IN ACCORDANCE WITH AS.1562.1
- ALL BOX GUTTERS WILL COMPLY WITH PART 3.5.2 OF BUILDING CODE OF AUSTRALIA (BCA)
- GUTTERS & DOWNPIPES ARE TO BE IN ACCORDANCE WITH CLAUSE 3.5.2 OF BCA & AS 3500 WITH ALL DOWNPIPES BEING A MINIMUM SIZE OF EITHER 100X 75 OR 100DIA & ALL BOX GUTTERING WILL BE MINIMUM 400W X 200D.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

ROOF PLAN		A112
Project number	070624	
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		1 : 100


ALL DOWNPIPES TO BE PVC,
CIRCULAR & PLUMBER TO CONNECT
THE DOWNPIPES TO GUTTER.




Project number	070624	A113
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale 1 : 100



Paragon Building Certifiers Pty Ltd
RBC00045
Registered Certifier
APPROVED
Reference: 260314/02
Date: 18/09/2026



1 NORTH (STREET) ELEVATION
1 : 100



2 SOUTH ELEVATION
1 : 100

NOTES:

ALL WINDOW SIZES ARE NOMINAL ONLY AND ARE TO BE MEASURED AND VERIFIED ON-SITE PRIOR TO ANY MANUFACTURE.

ALL WET AREA GLAZING TO BE OBSCURE.

EXPANSION JOINTS TO BE PROVIDED AS PER BCA/AUSTRALIAN STANDARDS.

WHERE FLOOR LEVEL IS >2M ABOVE EXTERNAL SURFACE BENEATH WINDOW, AND WHERE THE OPENABLE SASH IS <1.7M, ANY OPENABLE WINDOW IN A BEDROOM MUST BE RESTRICTED TO A 125MM OPENING.
IN REGARDS TO OTHER ROOMS, THIS APPLIES WHERE THE FLOOR LEVEL IS >4M.

R DENOTES **R**ESTRICTION ON THE WINDOW.

ALL DOWNPIPES TO BE PVC, CIRCULAR & PLUMBER TO CONNECT THE DOWNPIPES TO GUTTER.

Designed By:

SYDNEY DESIGNERS
AND PLANNERS

CLIENT:
LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560
*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

ELEVATIONS			
Project number	070624	A114	
Date	26.08.2026		
Drawn by	Checked by		
FS	NS	Scale	1 : 100

3.9.2.6 Protection of openable windows — bedrooms

(a)A window opening in a bedroom must be provided with protection, where the floor below the window is 2 m or more above the surface beneath.
(b)Where the lowest level of the window opening covered by (a) is less than 1.7 m above the floor, the window opening must comply with the following:
(i)The openable portion of the window must be protected with—
(A)a device capable of restricting the window opening; or
(B)a screen with secure fittings.
(ii)A device or screen required by (i) must—
(A) not permit a 125 mm sphere to pass through the window opening or screen; and
(B)resist an outward horizontal action of 250 N against the—
(aa>window restrained by a device; or
(bb)screen protecting the opening; and
(C)have a child resistant release mechanism if the screen or device is able to be removed, unlocked or overridden.
(c)Where a device or screen provided in accordance with (b)(i) is able to be removed, unlocked or overridden, a barrier with a height not less than 865 mm above the floor is required to the openable window in addition to window protection.
(d)A barrier covered by (c) must not—
(i)permit a 125 mm sphere to pass through it; and
(ii)have any horizontal or near horizontal elements between 150 mm and 760 mm above

3.9.2.3 Construction of barriers to prevent falls

(a)The height of a barrier required by 3.9.2.2 must be in accordance with the following:
(i)The height must not be less than 865 mm above the nosings of the stair treads or the floor of a ramp.
(ii)The height must not be less than—
(A)1 m above the floor of any access path, balcony, landing or the like (see Figure 3.9.2.1); or
(B)865 mm above the floor of a landing to a stair or ramp where the barrier is provided along the inside edge of the landing and does not exceed a length of 500 mm.
(b)A transition zone may be incorporated where the barrier height changes from 865 mm on the stair flight or ramp to 1 m at the landing (see Figure 3.9.2.2).
(c)Openings in barriers (including decorative balustrades) must be constructed so that they do not permit a 125 mm sphere to pass through it and for stairs, the opening is measured above the nosing Line of the stair treads.
(d)A barrier to a stairway serving a non-habitable room, such as an attic, storeroom or the like that is not used on a regular or daily basis, need not comply with (c) if—
(i)openings are constructed so that they do not permit a 300 mm sphere to pass through; or
(ii)where rails are used, the barrier consists of a top rail and an intermediate rail, with the openings between rails not more than 460 mm.
(e)A barrier, except a window serving as a barrier, must be designed to take loading forces in accordance with AS/NZS 1170.1.
(f)For floors more than 4 m above the surface beneath, any horizontal elements within the barrier between 150 mm and 760 mm above the floor must not facilitate climbing.
(g)Where a required barrier is constructed of wire it is deemed to meet the requirements of (c) if it is constructed in accordance with the following:
(i)For horizontal wire systems—
(A)when measured with a strain indicator, it must be in accordance with the tension values in Table 3.9.2.1; or
(B)must not exceed the maximum deflections in Table 3.9.2.3.
(ii)For non-continuous vertical wire systems, when measured with a strain indicator, must be in accordance with the tension values in Table 3.9.2.1 (see Note 4).
(iii)For continuous vertical or continuous near vertical sloped wire systems—
(A)must have wires of no more than 2.5 mm diameter with a lay of 7×7 or 7×19 construction; and
(B)changes in direction at support rails must pass around a pulley block without causing permanent deformation to the wire; and
(C)must have supporting rails, constructed with a spacing of not more than 900 mm, of a material that does not allow deflection that would decrease the tension of the wire under load; and
(D)when the wire tension is measured with a strain indicator, it must be in accordance with the tension values in Table 3.9.2.2 and measured in the furthestmost span from the tensioning device

EXTERNAL DOOR SCHEDULE

(ASSUME LOOKING FROM OUTSIDE)

DOOR SCHEDULE					
DOOR TAG	WIDTH	HEIGHT	ROOM	FRAME	
D01	2020	2340	ENTRY	TIMBER	
D03	720	2340	BATH	TIMBER	
D04	720	2340	LAUNDRY	TIMBER	
D05	720	2340	GARAGE	TIMBER	
D06	1000	2400	G. ENTRY	TIMBER	
D07	820	2340	G.BED	TIMBER	
D08	720	2340	G.BATH	TIMBER	
D09	820	2340	BED 3	TIMBER	
D10	820	2340	BED 4	TIMBER	
D11	720	2340	BATH	TIMBER	
D12	820	2340	MASTER BED	TIMBER	
D13	720	2340	ENS	TIMBER	
D14	820	2340	BED 2	TIMBER	
D15	720	2340	ENS	TIMBER	
D24	820	2340	BUTLER'S	TIMBER	
D26	820	2340	BED 1	TIMBER	
GD01	4800	2400	GARAGE	TIMBER	
SD01	2700	2400	KITCHEN	ALUMINIUM	
SD02	2400	2400	RUMPUS	ALUMINIUM	
SD03	2400	2400	BED 3	ALUMINIUM	
SD04	2700	2400	KITCHEN	ALUMINIUM	
SD05	2400	2400			

ALUMINIUM WINDOWS SCHEDULE

(ASSUME LOOKING FROM OUTSIDE)

WINDOW TAG	ROOM	WIDTH	HEIGHT	SILL HEIGHT	FRAME	GLAZING	TYPE
W01	LOUNGE	2100	2100	300	ALUMINIUM	CLEAR	FIXED
W03	STAIRS	1500	2100	1800	ALUMINIUM	CLEAR	FIXED
W04	BED 1	1800	1800	600	ALUMINIUM	CLEAR	SLIDING
W05	DINING	2400	2100	300	ALUMINIUM	CLEAR	FIXED
W08	G.DINING	1800	1800	600	ALUMINIUM	CLEAR	SLIDING
W09	G.BED	1500	1500	900	ALUMINIUM	CLEAR	SLIDING
W10	G.DINING	1800	1800	600	ALUMINIUM	CLEAR	SLIDING
W12	VOID	900	2400	0	ALUMINIUM	CLEAR	FIXED
W13	ENS	900	600	1800	ALUMINIUM	FROSTED	SLIDING
W14	BED 2	2700	900	1500	ALUMINIUM	CLEAR	SLIDING
W15	MASTER BED	3000	1800	600	ALUMINIUM	CLEAR	SLIDING
W16	ENS	900	600	1800	ALUMINIUM	FROSTED	SLIDING
W17	BED 4	900	1800	600	ALUMINIUM	CLEAR	AWNING

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

DOOR & WINDOWS SCHEDULE & LEGEND

COMPONENT DETAIL

Project number	070624	A116	
Date	26.08.2026		
Drawn by	Checked by		
FS	NS	Scale	1 : 100

NOTES:

ALL WINDOW SIZES ARE NOMINAL ONLY AND ARE TO BE MEASURED AND VERIFIED ON -SITE PRIOR TO ANY MANUFACTURE.


ALL WET AREA GLAZING TO BE OBSCURE.

EXPANSION JOINTS TO BE PROVIDED AS PER BCA/AUSTRALIAN STANDARDS.


WHERE FLOOR LEVEL IS >2M ABOVE EXTERNAL SURFACE BENEATH WINDOW, AND WHERE THE OPENABLE SASH IS <1.7M, ANY OPENABLE WINDOW IN A BEDROOM MUST BE RESTRICTED TO A 125MM OPENING. IN REGARDS TO OTHER ROOMS, THIS APPLIES WHERE THE FLOOR LEVEL IS >4M.

R DENOTES **R**ESTRICTION ON THE WINDOW.

ALL DOWNPIPES TO BE PVC, CIRCULAR & PLUMBER TO CONNECT THE DOWNPIPES TO GUTTER.



1 SECTION-A
1 : 100



2 SECTION-B
1 : 100

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

BUILDING SECTION

Project number	070624	A115
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		1 : 100



Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026



1

EAST ELEVATION FINISHES

1 : 100

▼ RIDGE LEVEL
99150
▼ ROOF
98300

▼ FIRST FLOOR
95600

▼ CEILING LEVEL
95300

▼ GRANNY CEILING
94300

▼ GROUND FLOOR
92600


▼ LOWER GROUND
91600

▼ GRANNY FLOOR
91300

2

WEST ELEVATION FINISHES

1 : 100



MATERIAL AND FINISHES SCHEDULE		
	MATERIAL IMAGE	MATERIAL COMMENTS
1		ROOF COLORBOND SHALE GREY OR SIMILAR
2		PGH BLACK HEATH OR SIMILAR
3		FASCIA AND GUTTER COLORBOND SURFMIST OR ANY LIGHT COLOUR
4		WOODEN CLADDING AS SELECTED
5		RENDER & PAINT FINISH DULUX VIVID WHITE OR SIMILAR
6		RENDER & PAINT FINISH DULUX BEIGE OR SIMILAR
7		RENDER & PAINT FINISH DULUX GREY OR SIMILAR
8		STACKSTONE FINISH OR SIMILAR
9		RENDER & PAINT FINISH DULUX MONUMENT OR SIMILAR

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDC checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

MATERIAL & FINISHES SCHEDULE

Project number	070624	A117
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		As indicated

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260314/02

Date: 18/09/2026



2 NORTH (STREET) ELEVATION FINISHES
1 : 100

MATERIAL AND FINISHES SCHEDULE		
	MATERIAL IMAGE	MATERIAL COMMENTS
1		ROOF COLORBOND SHALE GREY OR SIMILAR
2		PGH BLACK HEATH OR SIMILAR
3		FASCIA AND GUTTER COLORBOND SURFMIST OR ANY LIGHT COLOUR
4		WOODEN CLADDING AS SELECTED
5		RENDER & PAINT FINISH DULUX VIVID WHITE OR SIMILAR
6		RENDER & PAINT FINISH DULUX BEIGE OR SIMILAR
7		RENDER & PAINT FINISH DULUX GREY OR SIMILAR
8		STACKSTONE FINISH OR SIMILAR
9		RENDER & PAINT FINISH DULUX MONUMENT OR SIMILAR



3 SOUTH ELEVATION FINISHES
1 : 100

HANDRAILS / BALUSTRADE TO CONSTRUCT IN ACCORDANCE WITH NCC PART 11.3.3 AND 11.3.4

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL REQUIREMENTS, RELEVANT CODES & STANDARDS. LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. WHERE ENGINEERS STRUCTURAL DRAWINGS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

MATERIAL & FINISHES SCHEDULE

Project number	070624	A118
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale
		As indicated

PARAGON
Paragon Building Certifiers Pty Ltd
RBC00045
Registered Certifier
APPROVED
Reference: 260314/02
Date: 18/09/2026



Designed By:

SYDNEY DESIGNERS
AND PLANNERS

CLIENT:
**LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560**

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A
REGISTERED SURVEYOR BEFORE COMMENCEMENT OF
ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT
IN ACCORDANCE WITH THESE DRAWINGS, COUNCIL
REQUIREMENTS, RELEVANT CODES & STANDARDS.
LEVELS SHOWN ARE BASED ON CONTOUR SURVEY
PREPARED BY A REGISTERED SURVEYOR. DRAWINGS
ARE TO BE READ IN CONJUNCTION WITH
SPECIFICATIONS PROVIDED & ENGINEERS DETAILS.
WHERE ENGINEERS STRUCTURAL DRAWINGS ARE
REQUIRED THE ENGINEERS PLAN WILL TAKE
PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF
ANY ALTERATIONS OR DISCREPANCIES, NOTIFY
BUILDERS IMMEDIATELY. FIGURED DIMENSIONS TO BE
READ IN PREFERENCE TO SCALING & TO BE CHECKED &
VERIFIED BEFORE WORK IS COMMENCED.

No.	Description	Date
C	Revised as per the comments	04.05.2026
D	Revised as per the comments	14.05.2026
E	Revised as per the comments	22.05.2026
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

3D VIEWS		
Project number	070624	A119
Date	26.08.2026	
Drawn by	Checked by	
FS	NS	Scale

DWELLING

Certificate Number: 1852148S_02 Date of Issue: 31 August 2026			
This is a summary of the BASIX Commitments as detailed in the BASIX Certificate For details, refer to the Current BASIX Certificate			
Water Commitments			
Fixture			
5 Stars Shower heads	Yes	4 Stars Kitchen / Basin taps	Yes
4 Stars Toilets	Yes		
Alternative Water			
Minimum Tank Size (L)	2000L	Collected from Roof Area (Sqm)	60 Sqm
Rainwater Tank Connected to:			
All Toilets	Yes	Laundry W/M Cold Tap	Yes
At least one outdoor tap	Yes		
THERMAL COMFORT COMMITMENTS - Refer to TPA Specification on plans			
ENERGY COMMITMENTS			
Hot Water	Gas instantaneous with a performance of 6 stars		
Cooling System	Living	1 Phase A/C Zoned	3Star
	Bedrooms	1 Phase A/C Zoned	3Star
Heating System	Living	1 Phase A/C Zoned	3Star
	Bedrooms	1 Phase A/C Zoned	3Star
Ventilation	Kitchen	Fan ducted to exterior	Manual on/off
	Bathroom	Fan ducted to exterior	Manual on/off
	Laundry	Fan ducted to exterior	Manual on/off
Natural Lighting	Window / Skylight in Kitchen		Yes
	Window / Skylight in Bathrooms/ Toilets		Yes
Artificial Lighting	Number of bedrooms	5	Dedicated
Fluorescent or LED	Number of Living/ Dining Rooms	2	Dedicated
	Kitchen, All bathrooms/toilets, laundry, and All Hallways		Dedicated
Other Commitments			
Outdoor Clothesline	Yes	Ventilated refrigerator space	Yes
Gas Cooktop & electric Oven	Yes		

GRANNY

Certificate Number: 1852150S_02			
Date of Issue: 31 August 2026			
This is a summary of the BASIX Commitments as detailed in the BASIX Certificate For details : refer to the Current BASIX Certificate			
Water Commitments			
Fixture			
5 Stars Shower heads	Yes		
6 Stars Toilets	Yes	6 Star Kitchen /Basin taps	Yes
THERMAL COMFORT COMMITMENTS - Refer to TPA Specification on plans			
ENERGY COMMITMENTS			
Hot Water	Gas instantaneous with a performance of 6 stars		
Cooling System	Living	1 Phase A/C Zoned	3Star
	Bedrooms	1 Phase A/C Zoned	3Star
Heating System	Living	1 Phase A/C Zoned	3Star
	Bedrooms	1 Phase A/C Zoned	3Star
Ventilation	Kitchen	Fan ducted to exterior	Manual on/off
	Bathroom	Fan ducted to exterior	Manual on/off
	Laundry	Fan ducted to exterior	Manual on/off
Natural Lighting	Window / Skylight in Kitchen		No
	Window / Skylight in Bathrooms/ Toilets		No
Artificial Lighting Fluorescent or LED	Number of bedrooms	1	Dedicated
	Number of Living/ Dining Rooms	1	Dedicated
	Kitchen, All bathrooms/toilets, laundry, and All Hallways		Dedicated
Other Commitments			
Outdoor Clothesline	Yes	Ventilated refrigerator space	Yes
Gas Cooktop & electric Oven		Yes	

Designed By:



CLIENT:

LOT 4 IN DP 1207938 No. 100 MILKY
WAY CAMBELTOWN 2560

*COPYRIGHT OF PLANS AND DOCUMENTATION
REMAIN THE EXCLUSIVE PROPERTY OF SYDNEY DESIGNERS AND PLANNERS

NOTES:
BOUNDARY SETBACKS MUST BE VERIFIED BY A REGISTERED SURVEYOR BEFORE COMMENCEMENT OF ANY BUILDING WORK. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THESE DRAWINGS. COUNCIL REQUIREMENTS, RULES, REGULATIONS, STANDARDS AND LEVELS SHOWN ARE BASED ON CONTOUR SURVEY PREPARED BY A REGISTERED SURVEYOR. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS PROVIDED & ENGINEERS DETAILS. REGISTERED ENGINEERS DRAWINGS AND DETAILS ARE REQUIRED THE ENGINEERS PLAN WILL TAKE PREFERENCE TO THESE DRAWINGS. IN THE EVENT OF ANY ALTERATIONS OR DISCREPANCIES, NOTIFY WISDOM HOMES IMMEDIATELY. FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING & TO BE CHECKED & VERIFIED BEFORE WORK COMMENCED.

No.	Description	Date
F	Revised as per the CDc checklist	01.06.2026
G	Revised as per the engineers comments	01.07.2026
H	Revised windows, doors & kitchen sink	26.08.2026

BASIX COMMITMENT

Project number	070624	A120	
Date	15.09.2026		
Drawn by FS	Checked by NS		
		Scale	N/A

BUILDING SPECIFICATIONS

**National Construction Code – Volume 2,
Amendment 1 – Building Code of Australia 2022
& Housing Provisions Standard 2022**

SITE PREPARATION

- PART 3.1 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.

EARTHWORKS

- TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979 AND DEVELOPMENT CONSENT CONDITIONS
- PART 3.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 4678:2002 - EARTH-RETAINING STRUCTURES

DRAINAGE

- PART 3.3 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS/NZS 3500.1:2021 - PLUMBING & DRAINAGE - WATER SERVICES
- AS/NZS 3500.2:2021 - PLUMBING & DRAINAGE - SANITARY PLUMBING & DRAINAGE
- AS/NZS 3500.3:2021 - PLUMBING & DRAINAGE - STORMWATER DRAINAGE
- AS/NZS 3500.4:2021 - PLUMBING & DRAINAGE - HEATED WATER SERVICES

STRUCTURAL WORK

- Part 2.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 4100:2020– STEEL STRUCTURES CODES
- AS/NZS 1170.0:2002 – GENERAL PRINCIPLES
- AS/NZS 1170.1:2002 – PARTS 1 PERMANENT, IMPOSED AND OTHER ACTIONS
- AS/NZS 1170.2:2021 – PART 2 WIND ACTIONS
- AS 3700:2018– SAA MASONRY CODE
- AS 1684.3:2021- RESIDENTIAL TIMBER FRAMED CONSTRUCTION

FOOTINGS & SLABS

- PART 4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 2159:2009 - PILING - DESIGN & INSTALLATION
- AS 2870:2011 - RESIDENTIAL SLABS & FOOTINGS
- AS 3600:2018 - CONCRETE STRUCTURES

MASONRY

- PART 5 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 3700:2018 - MASONRY STRUCTURES

FRAMING

- PART 6 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1684.2:2021 - RESIDENTIAL TIMBER-FRAMED CONSTRUCTION - NON- CYCLONIC AREAS
- AS 1720.1:2010 - TIMBER STRUCTURES - DESIGN METHODS
- AS 4100:2020 - STEEL STRUCTURES
- AS 3660.1-2014 – TERMITE MANAGEMENT SYSTEM

ROOF & WALL CLADDING

- PART 7 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1273:1991 - UNPLASTICIZED PVC (UPVC) DOWNPIPES & FITTINGS FOR RAINWATER
- AS 1562.1:2018 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - METAL
- AS/NZS 1562.3:2006 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - PLASTIC
- AS 2049:2002 - ROOF TILES
- AS 2050:2018 - INSTALLATION OF ROOF TILES
- AS 4285:2019 – ROOFLIGHTS

GLAZING

- PART 8 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1288:2021 - GLASS IN BUILDINGS - SELECTION & INSTALLATION
- AS 2047:2014 - WINDOWS & EXTERNAL GLAZED DOORS IN BUILDINGS
- AS/NZS 2208:1996 - SAFETY GLAZING MATERIALS IN BUILDINGS

FIRE SAFETY

- PART 9 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 3786:2014 - SMOKE ALARMS USING SCATTERED LIGHT, TRANSMITTED LIGHT OR IONIZATION

HEALTH & AMENITY

- PART 10 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS/NZS ISO 717.1:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - AIRBORNE SOUND INSULATION
- AS ISO 717.2:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - IMPACT SOUND INSULATION
- AS 1668.2:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - MECHANICAL VENTILATION IN BUILDINGS
- AS 1668.4:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - NATURAL VENTILATION OF BUILDINGS
- AS/NZS 1680.0:2009 - INTERIOR LIGHTING - SAFE MOVEMENT
- AS 3740:2021 - WATERPROOFING OF DOMESTIC WET AREAS
- AS 3000:2018 – ELECTRICAL INSTALLATION
- BCA Part 10.8.1, AS4200.1 & AS4200.2 – PLIABLE BUILDING MEMBRANE INSTALLED.

WATERPROOFING

- PART 10.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022
- AS 3740:2021– WATERPROOFING TO WET AREA
- AS 4654:2012 – EXTERNAL WET AREAS

SAFE MOVEMENT & ACCESS

- PART 11 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1428.1:2009 - DESIGN FOR ACCESS & MOBILITY – GENERAL REQUIREMENTS FOR ACCESS - NEW BUILDING WORK
- AS 1657:2018 - FIXED PLATFORMS, WALKWAYS, STAIRWAYS & LADDERS - DESIGN, CONSTRUCTION & INSTALLATION

HANDRAILS & BALUSTRADE

- PART 11.3.3 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- PART 11.3.4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- PART 11.3.5 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1170.1-2002 – BALUSTRADE INSTALLATION

PROTECTION OF OPENABLE WINDOW

PART 11.3.7 AND 11.3.8 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.

ENERGY EFFICIENCY


- PART 13 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022 & BASIX CERTIFICATE.

HEATING APPLIANCES, FIREPLACES, CHIMNEYS AND FLUES

- PART 12.4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.

MECHANICAL VENTILATION

- EXHAUST FROM A BATHROOM, SANITARY COMPARTMENT TO DISCHARGE DIRECTLY TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 25L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM². THIS EXHAUST SYSTEM MUST BE INTERLOCKED WITH LIGHT SWITCH AND INCLUDE RUN-ON TIMER SO THAT THE EXHAUST SYSTEM CONTINUES TO OPERATE FOR 10 MINUTES AFTER THE LIGHT SWITCH IS OFF.
- ANY INSTALLED - KITCHEN RANGEHOOD EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM².
- LAUNDRY EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM².



OVERFLOW TO BALCONY:

- SURFACE DRAIN & OVERFLOW TO BALCONY

TERMITE SHEET

- TERMITE SHEET EXTENDS THROUGH THE ENTIRE MASONRY LEAF AND IS VISIBLE AT THE FINISHED FACE OF THE WALL.







FIGURE 5.5 (in part) TYPICAL SHEET INSTALLATION TO EXTERNAL WALL WITH CONCRETE FLOOR SLAB




(a) Overflow through parapet

ENCLOSED SHOWER AREA

Figure 10.2.17: Typical hobless construction



Extent of treatment for shower areas — concrete compressed fibre-cement and fibre-cement sheet floors



(i) Plan view

(ii) Side view

(a) Enclosed shower

WATERPROOFING

FALL TO FLOOR WASTE TO BE MINIMUM 1:80 TO MAXIMUM 1:50

Figure 10.2.29: Typical membrane termination at drainage outlet






Figure 10.2.24: Typical bathroom door details for whole bathroom waterproofing




(a) After installation of architrave




(b) Prior to installation of architrave

BASIN & BATHTUB:

Figure 10.2.5: Bath and vessel abutting wall — areas to be protected



(a) Vessel abutting wall



(b) Wall/bath junction

DPC FOR BRICKS

DAMP-PROOF COURSE (DPC) TO EXTENDS THROUGH THE ENTIRE MASONRY LEAF AND NEED TO BE VISIBLE AT THE FINISHED FACE OF THE WALL FROM OUTSIDE

