

FOR CONSTRUCTION

LOT 2 - 65 McKENNA CRESCENT, ROUSE HILL. IN DP 1276530.

PROPOSED CONSTRUCTION OF A TWO STOREY DWELLING



Sheet List

Sheet Number	Sheet Name
CDC.01	COVER SHEET
CDC.03	LOCATION PLAN AND SITE PLAN
CDC.05	GROUND FLOOR PLAN
CDC.06	FIRST FLOOR PLAN
CDC.07	ROOF PLAN
CDC.08A	ELEVATIONS 01
CDC.08B	ELEVATIONS 02
CDC.09A	ELEVATIONS 03
CDC.09B	ELEVATIONS 04
CDC.10A	SECTIONS 01
CDC.10B	SECTIONS 02
CDC.11A	GROSS FLOOR AREA PLAN 01
CDC.11B	GROSS FLOOR AREA PLAN 02
CDC.14	COLOR SCHEDULE
CDC.15	LANDSCAPE PLAN
CDC.16	WINDOW AND DOOR SCHEDULE
CDC.17	SLAB SETOUT PLAN
CDC.17A	WATERPROOFING DETAILS
CDC.17B	WATERPROOFING DETAILS 02
CDC.19A	3D VIEWS 01
CDC.19B	3D VIEWS 02
CDC.20	ACOUSTIC DETAILS
CDC.21	ELECTRICAL PLAN 01
CDC.22	ELECTRICAL PLAN 02

CONSTRUCTION ISSUE


3	13-08-2026	Porch Pillar made hollow as per Structural Drawings, Downpipes added as per Stormwater Design,	
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	
REV	DATE	DESCRIPTION	BY




PROJECT:

65 McKenna Crescent, Rouse Hill

CDC.01
COVER SHEET



1
SITE PLAN CDC
 1 : 200



2
DRIVEWAY SECTION
 1 : 100

(A) - EASEMENT FOR REPAIRS 0.9 WIDE (VIDE DP1276530).

CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	




PROJECT:
 65 McKenna Crescent, Rouse Hill

CDC.03
 LOCATION PLAN AND SITE PLAN

ACOUSTIC NOTES:

REFER TO THE ACOUSTIC DETAILS SHEET FOR THE CONSTRUCTION SPECIFICATIONS



GROUND FLOOR PLAN CDC

1

1 : 100

CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



RUBY
H O M E S

PROJECT:


65 McKenna Crescent, Rouse Hill

CDC.05

GROUND FLOOR PLAN

ACOUSTIC NOTES:

REFER TO THE ACOUSTIC DETAILS SHEET FOR THE CONSTRUCTION SPECIFICATIONS



FIRST FLOOR PLAN CDC

1

1 : 100

CONSTRUCTION ISSUE


REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.06
FIRST FLOOR PLAN

ACOUSTIC NOTES:
REFER TO THE ACOUSTIC DETAILS SHEET FOR THE CONSTRUCTION SPECIFICATIONS



1 ROOF PLAN CDC
1 : 100

Roof Schedule		
Mark	Area	Comments
R3	10 m²	COLORBOND ROOF
R2	21 m²	COLORBOND ROOF
R1	115 m²	COLORBOND ROOF
Grand total	146 m²	


CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.07
ROOF PLAN




CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.08A
ELEVATIONS 01



1 EAST ELEVATION
1 : 100


CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.08B
ELEVATIONS 02




CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.09A
ELEVATIONS 03



1 NORTH ELEVATION

1 : 100


CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.09B
ELEVATIONS 04




CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.10A
SECTIONS 01



1 LONGITUDINAL SECTION

1 : 100


CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.10B
SECTIONS 02



GROUND FLOOR

1

1 : 100

Area Schedule (Gross Building)

Name	Area
GFA	93 m ²
GARAGE	21 m ²
PORCH	2 m ²
ALFRESCO	7 m ²
GROUND FLOOR: 4	123 m ²


CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.11A
GROSS FLOOR AREA PLAN 01



1 **FIRST FLOOR**
1 : 100

Area Schedule (Gross Building)	
Name	Area

FIRST FLOOR	88 m ²
BALCONY	6 m ²
STAIR	6 m ²
FIRST FLOOR: 3	100 m ²
Grand total	223 m ²

CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.11B
GROSS FLOOR AREA PLAN 02



	1. CRT	2. BR1	3. CD1	4. CD2	5. AL	6. ED	7. GD	8. FAS	9. GUT
	ROOF	MAIN WALLS	CLADDING	ACCENT 1/RENDER	WINDOWS/ BALUSTRADE	MAIN DOOR	GARAGE DOOR	FASCIA	GUTTER
MATERIAL	COLORBOND	BRICK	BLUEBOARD	BRICK	ALUMINIUM	TIMBER	COLORBOND	COLORBOND	COLORBOND
COLOUR									

NOTE: ALL COLOURS SPECIFIED ARE INDICATIVE ONLY AND ARE SUBJECT TO VARIATION AND TO AVAILABILITY
ANY DISCREPANCY PLEASE FOLLOW AS PER RENDERED IMAGE

CONSTRUCTION ISSUE

2	05-06-2026	CDC ISSUE					
1	21-04-2026	CONCEPT (Worsdell 25)					
REV	DATE	DESCRIPTION	BY				




RUBY
H O M E S

PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.14
COLOR SCHEDULE

MCKENNA CRESCENT




LANDSCAPE PLAN

1

1 : 200


LANDSCAPE AREA

FRONT AREA	32.8 m ²
BACKYARD AREA	41.4 m ²



2. TREE & SHRUB PLANTING IN GARDEN BED

NOTE:
DO NOT PLANT IN UNSUITABLE WEATHER CONDITIONS SUCH AS EXTREME HEAT, COLD, WIND OR RAIN
CLAY SOIL IS TO BE TREATED WITH CLAY BREAKER AND ORGANIC COMPOST



1. TURF & GARDEN EDGE DETAIL

NOTE:
ALIGNMENT OF BRICK EDGE SHALL BE EVEN & FREE FROM DIPS AND HUMPS.

CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.15
LANDSCAPE PLAN

Window Schedule				
Mark	Height	Width	Head Height	Window Style

LOWER GROUND LEVEL

GW1	2000	1500	2400	SLIDING
GW2	500	900	2400	SLIDING

LOWER GROUND LEVEL: 2

GROUND FLOOR

GW3	1400	900	2400	SLIDING
GW4	1400	900	2400	SLIDING
GW5	1400	1800	2400	SLIDING & FIXED
GW6	600	1800	1650	FIXED

GROUND FLOOR: 4

FIRST FLOOR

FW1	1400	1200	2450	SLIDING
FW2	500	900	2450	SLIDING
FW3	2050	1200	2450	FIXED
FW4	800	900	2450	SLIDING
FW5	1400	1500	2450	SLIDING
FW6	1400	1500	2450	SLIDING
FW7	800	1500	2450	SLIDING
FW8	800	1500	2450	SLIDING

FIRST FLOOR: 8

Door Schedule			
Mark	Height	Width	Description

LOWER GROUND LEVEL

D1	2340	820	FLUSH DOOR
D2	2340	720	FLUSH DOOR
D3	2340	720	FLUSH DOOR
D4	2340	800	FLUSH DOOR
D5	2340	820	FLUSH DOOR
D6	2340	720	FLUSH DOOR
GD	2400	2400	GARAGE DOOR
MD	2400	1200	SOLID CORE DOOR

LOWER GROUND LEVEL: 8

GROUND FLOOR

SD1	2300	2200	SLIDING DOOR
-----	------	------	--------------

GROUND FLOOR: 1

FIRST FLOOR

D7	2340	820	FLUSH DOOR
D8	2340	820	FLUSH DOOR
D9	2340	720	FLUSH DOOR
D10	2340	720	FLUSH DOOR
D11	2340	820	FLUSH DOOR
D12	2340	820	FLUSH DOOR
SD2	2300	2650	SLIDING DOOR

FIRST FLOOR: 7


CONSTRUCTION ISSUE

2	05-06-2026	CDC ISSUE	
REV	DATE	DESCRIPTION	BY



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.16
WINDOW AND DOOR SCHEDULE



1 SLAB SETOUT PLAN

1 : 100

CONSTRUCTION ISSUE

REV	DATE	DESCRIPTION	BY
2	05-06-2026	CDC ISSUE	



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.17
SLAB SETOUT PLAN



CONSTRUCTION ISSUE


2	05-06-2026	CDC ISSUE	
REV	DATE	DESCRIPTION	BY



RUBY
H O M E S

PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.19A
3D VIEWS 01



CONSTRUCTION ISSUE

2	05-06-2026	CDC ISSUE	
REV	DATE	DESCRIPTION	BY



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.19B
3D VIEWS 02

5.2 Lots 2 to 3, Lots 201 to 203

5.2.1 Entry Doors

Entry doors of Lots 2 to 3, Lots 201 to 203 should be of solid core timber construction with a nominal thickness of 45 mm.

Acoustic Seals should be fitted to the door as shown in the attached sketch AC809-5B.

Careful fitting of door frames and doors to minimise or plug edge gaps is essential. Door latches with a "backset" distance of 127 mm is preferred, but not less than 70 mm, to allow adequate finger clearance for acoustic seals.

5.2.2 Floor Coverings

All floors in Lots 2 to 3, Lots 201 to 203 should be carpet only (excluding bathrooms, laundries, and kitchens).

5.2.3 Walls

Double brick walls are acceptable.

If Brick veneer is proposed, the following construction should be implemented:

- 110 mm bricks (min. average weight 6kg), and
- 90 mm stud frame with 75 mm thick bulk insulation, and
- 13 mm fire rated plasterboard lining on 90 mm studs.

If lightweight walls are proposed, the following construction should be implemented:

- 16 mm fibre cement clad sheeting such as James Hardie Stria or equivalent or 9 mm fibre cement sheeting, fixed on to battens, and
- Sarking and 25 mm wall blankets installed between the battens; and
- 2 layers of 16 mm fire rated plasterboard (or 2 layers of 9 mm fibre cement) to the outside of 90mm timber studs; and
- 75 mm bulk insulation (min 14 kg/m³ density) installed between the studs; and
- 2 layers of 16 mm fire rated plasterboard on the internal side of the studs.

Normal cavity-brick walls make an excellent sound barrier, reducing outside noise intrusion by as much as 50 dBA. Brick veneer walls also make good sound barriers. However, care must be exercised with brick-veneer walls to minimise sound penetration near the eaves as shown in the attached Figure AC 806-J. Bricklayers should be instructed to ensure the perp-ends are filled and suitable cement-mortar used to eliminate shrinkage gaps during curing.



5.2.4 Ceiling and Roof System

- All roofs shall be of concrete tile or metal deck construction.
- Thermal insulation and a heavy Duty Sarking vapour barrier laid below the roof.
- Ceilings under the roof are to comprise one layer of 13 mm fire rated plasterboard.
- 160 mm thick bulk insulation batts (min 11 kg/m³ density) are to be placed between the ceiling joists.

5.2.5 Windows

Normal windows and doors will only reduce outside noise intrusion by 15 to 18 dBA.

Unless otherwise specified, window and door frames may be either sliding or casement style and be of robust sound-barrier construction having interlocking stiles and Schlegel (or similar) Q-lon or vinyl finned seals to minimise sound leakage.

Glazing for all rooms including the bedrooms, lounge, family room and dining room shall have R_w ratings as specified in Table 4. A typical glazing specification is given, however, an alternative glazing specification may be used if the R_w is achieved or exceeded.

Table 3 Schedule of Glazed Windows and Door Constructions

Room Description	Minimum R _w	Typical Glazing Specification
Lots 2 to 3, Lots 201 to 203		
Bedrooms Window (1800 x 1200)	35	10.38 mm laminated glass in an awning frame with Q-lon seals
Living/Dining Room Sliding Door/Window (2400 x 2100)	35	10.38 mm laminated glass in an awning frame with Q-lon seals
Kitchens/Bathrooms/Laundries Window (1800 x 1200)	31	6.38 mm laminated glass in an awning frame with Q-lon seals

It is most important that any sound leakage paths around the windows be sealed off. We recommend that prior to the fitting of architraves around the windows, the space between the frames and the wall structure be sealed off with polystyrene rod packers and silicone mastic, as shown in the attached datasheet AC809-4C. The window architraves can then be fitted.



CONSTRUCTION ISSUE

2	05-06-2026	CDC ISSUE	
1	21-04-2026	CONCEPT (Worsdell 25)	
REV	DATE	DESCRIPTION	BY



PROJECT:

65 McKenna Crescent, Rouse Hill

CDC.20
ACOUSTIC DETAILS

ABCB HOUSING PROVISIONS : PART 10.2 WET AREA WATERPROOFING

10.2.1 Wet Areas

- 1. Building elements in wet areas within a building must be protected with a waterproofing system.
- 2. The waterproofing system in (1) must be either waterproof or water resistant in accordance with 10.2.2 to 10.2.6.

10.2.2 Shower Area (enclosed and unenclosed)

- 1. For a shower area with a hob, step-down or level threshold, the following applies:
 - a. The floor of the *shower area* must be *waterproof*, including any hob or step-down (see Figure 10.2.2); and
 - b. The walls of the *shower area* must be *waterproof* not less than 1800 mm above the floor substrate (see Figure 10.2.2).
 - c. Wall junctions and joints within the *shower area* must be *waterproof* not less than 40 mm either side of the junction (see Figure 10.2.2).
 - d. Wall/floor junctions within the shower area must be *waterproof* (see Figure 10.2.2).
 - e. Penetrations within the *shower area* must be *waterproof*.
- 2. A shower with a *preformed shower base* must also comply with the requirements of (1), except for (a) which is not applicable.

Figure 10.2.2: Extent of treatment for shower areas - concrete compressed fibre-cement and fibre-cement sheet floors.




Figure Notes
Wall/floor junction heights are to be as per 10.2.2 to 10.2.6 (as applicable).

Notes
Where a shower is above a bath or spa, use requirements for shower.


10.2.3 Area outside shower area

- 1. For concrete, compressed fibre-cement and fibre-cement sheet flooring, the floor of the room must be water resistant.
- 2. For timber floors including particleboard, plywood and other timber based flooring materials, the floor of the room must be waterproof.
- 3. Wall/floor junctions must be -
 - a. waterproof, and
 - b. where a flashing is used, the horizontal leg must be not less than 40 mm.

10.2.4 Areas adjacent to baths and spas without showers

- 1. For areas adjacent to all baths and spas, the following applies:
 - a. For concrete, compressed fibre-cement and fibre-cement sheet flooring, the floor of the room must be water resistant.
 - b. For timber floors including particleboard, plywood and other timber based flooring materials, the floor of the room must be waterproof.
 - c. Tap and spout penetrations must be waterproof where they occur in horizontal surfaces.
- 2. For areas adjacent to non-freestanding baths and spas, the following applies:
 - a. Walls must be water resistant (see Figure 10.2.4a and Figure 10.2.4b)-
 - to a height of not less than 150mm above the vessel, for the extent of the vessel, where the vessel is within 75mm of a wall; and
 - for all exposed surfaces below vessel lip.
 - b. Wall junctions and joints must be water resistant within 150mm above a vessel for the extent of the vessel.
 - c. Wall/floor junctions must be waterproof for the extent of the vessel (see Figure 10.2.4a and Figure 10.2.4b).
- 3. For inserted baths and spas, the following applies.
 - a. For floors and horizontal surfaces:
 - Any shelf area adjoining the bath or spa must be waterproof and include a waterstop under the vessel lip.
 - There are no requirements for the floor under a bath or spa.
 - b. For walls:
 - Waterproof to not less than 150mm above the lip of a bath or spa.
 - There are no requirements for the floor under a bath or spa.
 - c. For wall junctions and joints, the following applies:
 - Waterproof junctions within 150mm of a bath or spa.
 - There are no requirements for junctions and joints in walls beneath the lip of a bath or spa.
 - d. Tap and spout penetrations must be waterproof where they occur in horizontal surfaces.

Figure 10.2.4a: Areas adjacent to baths and spas without showers for concrete, compressed fibre-cement and fibre-cement sheet flooring



CONSTRUCTION ISSUE


2	05-06-2026	CDC ISSUE					
REV	DATE	DESCRIPTION	BY				



PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.17A
WATERPROOFING DETAILS


Figure 10.2.4b: Areas adjacent to baths and spas without showers for timber floors including particle-board, plywood and other floor materials



10.2.5 Other areas

- For walls adjoining other types of vessels (e.g. sink, basin or laundry tub), the following applies:
 - Walls must be water resistant to a height of not less than 150mm above the vessel, for the extent of the vessel, where the vessel is within 75 mm of a wall (see Figure 10.2.5.)
 - Waterproof wall junctions where a vessel is fixed to a wall.
 - Waterproof tap and spout penetrations where they occur in surfaces required to be waterproof or water resistant.
- For laundries and WCs, the following applies:
 - The floor of the room must be water resistant.
 - Wall/floor junctions must be water resistant, and where a flashing is used, the horizontal leg must not be less than 40 mm.
- For WCs with handheld bidet spray installations, the following applies:
 - The floor of the room must be waterproof.
 - Walls must be -
 - waterproof in WC area within a 900 mm radius from the wall connection of the handheld bidet spray device to a height of not less than 150mm above the floor substrate; and
 - water resistant in WC area within a 900 mm radius from the wall connection of the handheld bidet device to not less than 1200 mm above the finished floor level of the WC.
 - Wall junctions within the WC area within 900 mm radius from the wall connection of the handheld bidet spray device must be waterproof.
 - Wall/floor junctions within the WC area within 1000 mm radius from the wall connection of the handheld bidet spray device must be waterproof.
 - Penetrations in the WC area must be waterproof.

Figure 10.2.5: Bath and vessel abutting wall - areas to be protected



10.2.6 Waterproofing systems

- For the purposes of this Part, a waterproofing system is deemed -
 - waterproof, if it complies with (2); or
 - water resistant, if it complies with (3).
- For a waterproofing system required to be waterproof in accordance with 10.2.2 to 10.2.5, the materials nominated in 10.2.8 must be used.
- For a waterproofing system required to be water resistant in accordance with 10.2.2 to 10.2.5, the materials nominated in 10.2.9 must be used in conjunction with the materials in 10.2.10.

10.2.12 Construction of wet area floors - falls

- Where a floor waste is installed -
- the minimum continuous fall of a floor plane to the waste must be 1:80; and
 - the maximum continuous fall of a floor plane to the waste must be 1:50.

CONSTRUCTION ISSUE

2	05-06-2026	CDC ISSUE					
REV	DATE	DESCRIPTION	BY				



RUBY
H O M E S

PROJECT:
65 McKenna Crescent, Rouse Hill

CDC.17B
WATERPROOFING DETAILS 02