



Mark Richardson
Certifier
BDC3297



NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

An architectural rendering of a modern, multi-story residential building. The structure features a mix of materials: light-colored brick on the ground floor, white horizontal siding on the upper floors, and large glass panels. A prominent feature is a cantilevered upper floor with a curved, white, overhanging edge. The building has several windows, some with dark frames and others with light-colored shutters. A series of steps leads up to the entrance, which is partially enclosed by a glass and metal screen. To the left, there is a small, covered outdoor area with a glass railing. The building is set against a plain white background, and a dark, low wall runs along the front of the property.



INHAUS-20	PARKING PLAN/DRIVEWAY PROFILE B
INHAUS-21	SUBDIVISION PLAN
INHAUS-22	SEDIMENT CONTROL PLAN
INHAUS-23	SCHEDULE OF COLOURS AND FINISHES
INHAUS-24	LANDSCAPE PLAN/MAINTENANCE PLAN
INHAUS-25	BASIX COMMITMENTS
INHAUS-26	NATHERS COMMITMENTS
INHAUS-27	NATHERS COMMITMENTS
INHAUS-28	NCC/AS - GENERAL NOTES
INHAUS-29	NCC/AS - STAIRS
INHAUS-30	AS3740 (WATERPROOFING)
INHAUS-31	AS3740 (WATERPROOFING)

INHAUSDESIGNS

bdaa

4 STAR RATING

RESIDENTIAL / COMMERCIAL / INTERIORS

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS FROM PTY LTD OR ITS AGENT

DESIGNER NAME: JUSTIN ELAZZI

MEMBERSHIP NO. 6605

EMAIL: ADMIN@INHAUSDESIGNS.COM.AU

BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA

- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER

- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

EXCLUDED AREA

DEEP SOIL

GFA

SWIMMING POOL

PRIVATE OPEN SPACE

SITE BOUNDARY

REGION LIMIT

TITLE

COMPLIANCE PAGE

CHECKED BY

JE

DWG #

INHAUS-01

REVISION

D

PROJECT #

2604

GFA GROUND FLOOR

1 : 100

GFA FIRST FLOOR

1 : 100

DEEP SOIL

1 : 100

COMPLIANCE TABLE

DWELLING (TYPE) - DUAL OCCUPANCY
COUNCIL - CUMBERLAND
DCP/LEP - CUMBERLAND LEP 2021
DP NUMBER - DP628
LOT NUMBER - 127
ZONING - R2 LOW DENSITY RESIDENTIAL

SITE AREA - 722.3 M ²	PERMISSIBLE	PROPOSED	
25% OF LOT AREA + 300M ²	480.575 M ²	477.56 M ²	
TOTAL GFA	LOT A		LOT B
GROUND FLOOR GFA	130.81 M ²		123.17 M ²
FIRST FLOOR GFA	114.02 M ²		109.56 M ²
TOTAL GFA	244.83 M ²		232.73 M ²
MAX HEIGHT	8.5 M	7.1 M	6.996 M
SETBACKS			
GROUND FLOOR FRONT SETBACK	7.494 M	8.02 M	8.02 M
GROUND FLOOR REAR SETBACK	3 M	8.97 M	8.97 M
SECONDARY RD GROUND FLOOR SIDE SETBACK	2 M	2 M	2 M
GROUND FLOOR SIDE SETBACK	0.9 M	0.9 M	0.9 M
FIRST FLOOR FRONT SETBACK	7.494 M	8.02 M	8.02 M
FIRST FLOOR REAR SETBACK	8 M	8.97 M	8.97 M
FIRST FLOOR SIDE SETBACK (BUILDING HEIGHT-4.5M) + 4 + 0.9M	1.55 M	1.6 M	1.6 M
SECONDARY FIRST FLOOR SIDE SETBACK	2 M	2 M	2 M
GARAGE SETBACK	1 M	5.5 M	9.02 M
PRIVATE OPEN SPACE	16 M ²	99.46 M ²	25.24 M ²
LANDSCAPE / DEEP SOIL	261.15 M ²	263.62 M ²	
50% OF PARENT LOT MINUS 100 M ²			
25% FORWARD OF BUILDING LINE 102.66 X 25 %	25.665 M ²	102.43 M ²	
50% BEHIND OF BUILDING LINE 182.118 X 50 %	91.059 M ²	161.19 M ²	

Nationwide House Energy Rating Scheme®

Class 1 Summary

NatHERS® Certificate No. #HR-8B76BD-02

Generated on 09 Mar 2026 using Hero 4.1

Property

Address 16 Henson Street, Merrylands, NSW, 2160

Lot/DP Lot 127/ DP 628

NatHERS climate zone 56 - Mascot AMO

Accredited assessor

Name Jamie Bonnefin

Business name Certified Energy

Email jobs@certifiedenergy.com.au

Phone +61 1300 443

Accreditation No. 10096

Assessor Accrediting Organisation HERA

Verification

To verify this certificate, scan the QR code or visit <http://www.hero-software.com.au/pdf/HR-8B76BD-02>.

When using either link, ensure you are visiting <http://www.hero-software.com.au>

National Construction Code (NCC) requirements

The NCC allows the use of NatHERS accredited software to comply with the energy efficiency requirements for houses (Class 1 buildings) and apartments (Class 2 sole-occupancy units and Class 4 parts of buildings). The applicable requirements for houses are detailed in Specification 4.2 of NCC Volume Two. For apartments the requirements are detailed in clauses J3D3 and J3D15 of NCC Volume One.

NCC 2022 includes enhanced thermal performance requirements for houses and apartments. It also includes a new whole-of-home annual energy use budget which applies to the major equipment in the home.

The NCC, and associated ABCB Standards and support material, can be accessed at www.abcb.gov.au.

Note, variations and additions to the NCC energy efficiency requirements may apply in some states and territories.

Summary of all dwellings

Certificate number and link	Unit Number	Heating load (load limit) (MJ/m ² -yr)	Cooling load (load limit) (MJ/m ² -yr)	Total load (MJ/m ² -yr)	Star Rating	Whole of Home Rating
HR-TVSWBA-02	A	13.9 (26)	16.0 (19)	29.9	7.0	n/a
HR-63WLHM-02	B	12.4 (26)	16.7 (19)	29.2	7.1	n/a

Thermal performance Star rating

7.0 Minimum Rating

NATIONWIDE HOUSE ENERGY RATING SCHEME®

The rating above is the minimum of all dwellings in this summary.

For more information on your dwelling's rating see: www.nathers.gov.au

Whole of Home performance rating

No Whole of Home performance rating generated for this certificate or not completed for all dwellings.

Nationwide House Energy Rating Scheme (NatHERS) is an initiative of the Australian, state and territory governments. For more details see www.nathers.gov.au

Generated on 09 Mar 2026 using Hero 4.1 for 16 Henson Street, Merrylands, NSW, 2160

Page 1 of 2



Mark Richardson
Certifier
BDC3297




NOTES

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- NON-TRAFFICABLE
- LANDSCAPE
- CONCRETE PATH
- CONCRETE SURFACE
- SWIMMING POOL
- TILED FLOOR
- ARTICULATION
- OVERHEAD
- HIDDEN
- SITE BOUNDARY
- SMOKE ALARM
- MECHANVENTILATION
- WET AREA FLOOR WALL
- 90 STUD WALL
- 110 BRICK
- 250 BRICK VENEER
- 270 DOUBLE BRICK
- 130 CLADDING
- 200 HEBEL WALL

PROJECT #
2604



1 : 100




VISUAL SCALE 1:100 @ A1

DAVIES

STREET

STREET

HENSON



MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

ddo COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	ISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- NON-TRAFFICABLE
- LANDSCAPE
- CONCRETE PATH
- CONCRETE SURFACE
- SWIMMING POOL
- TILED FLOOR
- ARTICULATION
- OVERHEAD
- HIDDEN
- SITE BOUNDARY
- SMOKE ALARM
- MECH-VENTILATION
- WET AREA FLOOR WASTE
- 90 STUD WALL
- 110 BRICK
- 250 BRICK VENEER
- 270 DOUBLE BRICK
- 130 CLADDING
- 200 HEBEL WALL

TITLE
GROUND FLOOR PLAN

CHECKED BY JE

DWG # INHAUS-03 REVISION D

PROJECT #


2604

GROUND FLOOR LEVEL


1: 100

0M 2M 4M 6M 8M 10M

VISUAL SCALE 1:100 @ A1



- WET AREA IN ACCORDANCE WITH H4D1, H4D2 & H4D3 OF THE NCC VOLUME TWO AND PART 10.2 OF THE HOUSING PROVISIONS OR CLAUSES 10.2.1 TO 10.2.6 & 10.2.12 AND AS 3740.
- MECHANICAL VENTILATION LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS 1668.2
- SMOKE ALARM LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS3786 & NCC HOUSING PROVISIONS CLAUSE 9.5.2
- EXTERNAL BALCONIES ARE TO BE WATERPROOFED IN ACCORDANCE PER NCC - H2D8 & AS 4654.1 & 2.
- EXTERNAL BALCONIES AND PATIOS/ALFRESCO HAVE A MINIMUM STEPDOWN OF 50MM (N2 WIND) OR 70MM (N3 WIND).
- WINDOWS LOCATED WITHIN SHOWER AREA HAVE A SILL HEIGHT OF MINIMUM 1800MM
- WET AREA FLOOR WASTE LOCATIONS AND FALLS BETWEEN 1:50 - 1:80 TO ALL FLOOR WASTES IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 10.2.12.
- NOMINATED HANDRAILS ARE LOCATED AND NOTED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.5.
- FIRST FLOOR BEDROOM WINDOWS ARE TO HAVE WINDOW RESTRICTORS OR SCREENS (CRIM-SAFE STYLE MESH) INSTALLED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.7.
- PROPOSED DISCHARGE LOCATIONS OF MECHANICAL EXHAUSTS ARE EXTERNALLY DUCTED THROUGH WALLS
- POOL PUMP EQUIPMENT TO BE HOUSED IN A SOUND PROOF ENCLOSURE AT 1800MM HIGH (NON-CLIMBABLE) AND CLEAR OF NON-CLIMBABLE ZONE (900MM AND 500MM AWAY)
- SWIMMING POOL FILTRATION SYSTEM IS TO COMPLY WITH AS 1926.3-2010
- MASONRY ARTICULATION JOINTS AS PER AS 4773.2 & NCC HOUSING PROVISIONS CLAUSE 5.6.8 (VERTICAL ARTICULATION JOINTS).



MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297



COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE DESCRIPTION

A	22.01.26	ISSUED FOR CLIENT REVIEW
B	04.02.26	ISSUED FOR CONSULTANTS
C	17.02.26	REISSUED FOR CONSULTANTS
D	06.03.26	ISSUED FOR CDC APPROVAL
E	XXXX	XXXX
F	XXXX	XXXX

LEGEND

	NON-TRAFFICABLE
	LANDSCAPE
	CONCRETE PATH
	CONCRETE SURFACE
	SWIMMING POOL
	TILED FLOOR
	ARTICULATION
	OVERHEAD
	HIDDEN
	SITE BOUNDARY
	SMOKE ALARM
	MECH VENTILATION
	WET AREA FLOOR WASTE
	90 STUD WALL
	110 BRICK
	250 BRICK VENEER
	270 DOUBLE BRICK
	130 CLADDING
	200 HEBEL WALL

TITLE

FIRST FLOOR PLAN

CHECKED BY JE

DWG # INHAUS-04
REVISION D

PROJECT #

2604

FIRST FLOOR LEVEL

1 : 100



VISUAL SCALE 1:100 @ A1



WET AREA IN ACCORDANCE WITH H4D1, H4D2 & H4D3 OF THE NCC VOLUME TWO AND PART 10.2 OF THE HOUSING PROVISIONS OR CLAUSES 10.2.1 TO 10.2.6 & 10.2.12 AND AS 3740.

MECHANICAL VENTILATION LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS 1668.2

SMOKE ALARM LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS3786 & NCC HOUSING PROVISIONS CLAUSE 9.5.2

EXTERNAL BALCONIES ARE TO BE WATERPROOFED IN ACCORDANCE PER NCC - H2D8 & AS 4654.1 & 2.

EXTERNAL BALCONIES AND PATIOS/ALFRESCO HAVE A MINIMUM STEPDOWN OF 50MM (N2 WIND) OR 70MM (N3 WIND).

WINDOWS LOCATED WITHIN SHOWER AREA HAVE A SILL HEIGHT OF MINIMUM 1800MM

WET AREA FLOOR WASTE LOCATIONS AND FALLS BETWEEN 1:50 - 1:80 TO ALL FLOOR WASTES IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 10.2.12.

NOMINATED HANDRAILS ARE LOCATED AND NOTED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.5.


FIRST FLOOR BEDROOM WINDOWS ARE TO HAVE WINDOW RESTRICTORS OR SCREENS (CRIM-SAFE STYLE MESH) INSTALLED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.7.

PROPOSED DISCHARGE LOCATIONS OF MECHANICAL EXHAUSTS ARE EXTERNALLY DUCTED THROUGH WALLS

POOL PUMP EQUIPMENT TO BE HOUSED IN A SOUND PROOF ENCLOSURE AT 1800MM HIGH (NON-CLIMBABLE) AND CLEAR OF NON-CLIMBABLE ZONE (900MM AND 500MM AWAY)

SWIMMING POOL FILTRATION SYSTEM IS TO COMPLY WITH AS 1926.3-2010

MASONRY ARTICULATION JOINTS AS PER AS 4773.2 & NCC HOUSING PROVISIONS CLAUSE 5.6.8 (VERTICAL ARTICULATION JOINTS).



MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

bdoo **bdoo**
BUILT DESIGN ORIGIN
RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- NON-TRAFFICABLE
- LANDSCAPE
- CONCRETE PATH
- CONCRETE SURFACE
- SWIMMING POOL
- TILED FLOOR
- ARTICULATION
- OVERHEAD
- HIDDEN
- SITE BOUNDARY
- SMOKE ALARM
- MECH-VENTILATION
- WET AREA FLOOR WASTE
- 90 STUD WALL
- 110 BRICK
- 250 BRICK VENEER
- 270 DOUBLE BRICK
- 130 CLADDING
- 200 HEBEL WALL


TITLE
ROOF PLAN

CHECKED BY JE

DWG # INHAUS-05 REVISION D


PROJECT #

2604



ROOF PLAN


1 : 100




VISUAL SCALE 1:100 @ A1



Mark Richardson
Certifier
GROUND FLOOR LEVEL 30.000
BDC3297



1 : 100



1 : 100

RESIDENTIAL / COMMERCIAL / INTERIORS

CORNER BLOCK DUAL-OCCUPANCY

DAVID BOURCHAN

NOTES

USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX


	NON-TRAFFICABLE
	LANDSCAPE
	CONCRETE PATH
	CONCRETE SURFACE
	SWIMMING POOL
	TILED FLOOR
	ARTICULATION
	OVERHEAD
	HIDDEN
	SITE BOUNDARY
	SMOKE ALARM
	MECH VENTILATION
	WET AREA FLOOR WASTE
	90 STUD WALL
	110 BRICK
	250 BRICK VENEER
	270 DOUBLE BRICK
	130 CLADDING
	200 HEBEL WALL

ELEVATIONS

DWG #	REVISION
-------	----------

2604

2604



1 : 100



1 : 100



VISUAL SCALE 1:100 @ A1

IN
HAUS
DESIGNS



 bdo

COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL
NOT BE COPIED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN
PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

TITLE

AXONOMETRIC

CHECKED BY

JE

DWG #


INHAUS-07

REVISION


D

PROJECT #

2604




AXONOMETRIC - 1



AXONOMETRIC - 2



AXONOMETRIC - 3



AXONOMETRIC - 4



Mark Richardson
Certifier
BDC3297



COPYRIGHT™

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NSW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS


DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- | | |
|--|----------------------|
| | NON-TRAFFICABLE |
| | LANDSCAPE |
| | CONCRETE PATH |
| | CONCRETE SURFACE |
| | SWIMMING POOL |
| | TILED FLOOR |
| | ARTICULATION |
| | OVERHEAD |
| | HIDDEN |
| | SITE BOUNDARY |
| | SMOKE ALARM |
| | MECH-VENTILATION |
| | WET AREA FLOOR WASTE |
| | 90 STUD WALL |
| | 110 BRICK |
| | 250 BRICK VENEER |
| | 270 DOUBLE BRICK |
| | 130 CLADDING |
| | 200 HEBEL WALL |

TITLE



SECTIONS

CHECKED BY _____

DWG #
INHAUS-08

PROJECT #

2604



CROSS SECTION

1 : 100



LONG SECTION

1 : 100



VISUAL SCALE 1:100 @ A1





COPYRIGHT
THE DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS FROM PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

· ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

· ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA

· ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

· BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER

· USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

NON-TRAFFICABLE

LANDSCAPE

CONCRETE PATH

CONCRETE SURFACE

SWIMMING POOL

TILED FLOOR

ARTICULATION

OVERHEAD

HIDDEN

SITE BOUNDARY

SMOKE ALARM

MECH-VENTILATION

WET AREA FLOOR WASTE

90 STUD WALL

110 BRICK

250 BRICK VENEER

270 DOUBLE BRICK

130 CLADDING

200 HEBEL WALL

TITLE

POOL SECTIONS/BACKYARD PLAN

CHECKED BY

JE

DWG #

INHAUS-09

REVISION

D

PROJECT #

2604

POOL SAFETY STANDARDS:

- FENCE MUST BE AT LEAST 1200MM HIGH ALL THE WAY AROUND MEASURED FROM THE OUTSIDE OF THE POOL
- IF A BOUNDARY FENCE FORMS PART OF THE POOL FENCE, IT MUST BE AT LEAST 1800MM HIGH MEASURED FROM THE INSIDE OF THE POOL AREA
- THE GAP BETWEEN THE BOTTOM OF THE FENCE AND THE GROUND IS NO MORE THAN 100MM
- THE GAP BETWEEN ALL VERTICAL OR NEAR VERTICAL RAILS ON THE FENCE IS LESS THAN 100MM
- NO POTENTIAL HAND HOLDS OR FOOT HOLDS WITHIN 900MM OF THE TOP OF THE POOL FENCE IN ANY DIRECTION
- THERE MUST BE A 300MM CLEARANCE FROM THE BARRIER INSIDE THE POOL AREA
- IF PERFORATED OR MESH FENCING IS USED, THE HOLES MUST BE 13MM OR LESS
- YOUR POOL FENCE MUST BE WELL MAINTAINED AND IN A GOOD STATE OF REPAIR (EG. NO HOLDS, BROKEN RAILS OR PAILINGS)
- THE GATE MUST BE SELF CLOSING AND LATCH ITSELF FROM ANY POSITION
- THE GATE LATCH MUST BE WORKING WELL SO THAT THE GATE IS SECURE AND, ONCE CLOSED, CAN'T BE PULLED OPEN
- THE GATE MUST OPEN OUTWARDS AWAY FROM THE POOL
- THE GAP BETWEEN VERTICAL BARRIERS OF A GATE MUST BE NO MORE THAN 100MM
- THE GAP BETWEEN VERTICAL BARRIERS OF A GATE MUST BE NO MORE THAN 100MM
- THE GATE MUST BE NO MORE THAN 100MM ABOVE GROUND LEVEL OR IF LOCATED INSIDE THE GATE, 120MM ABOVE GROUND LEVEL AND AT LEAST 150MM BELOW THE TOP OF THE GATE
- ARE YOU AWARE THAT IT IS DANGEROUS AND AGAINST THE LAW TO PROP THE GATE OPEN
- IF THE GATE IS PROP'D, THERE ARE NO OPENING GREATER THAN 100MM
- ALL WINDOWS CAN ONLY OPEN TO A MAXIMUM OF 100MM OR THE WINDOWS MUST BE TOTALLY COVERED BY BARS OR A METAL SCREEN
- THE HEIGHT FROM THE SILL OF THE LOWEST OPENING PANEL OF A WINDOW (TO THE POOL AREA) HAS TO BE 1800MM FROM THE FLOOR
- THERE MUST BE AN APPROPRIATE WARNING SIGN, INCLUDING DETAILS OF RESUCITATION (CPR) TECHNIQUES, IN THE IMMEDIATE VICINITY OF THE POOL AREA AND WHICH CAN BE EASILY READ FROM A DISTANCE OF 3 METRES
- YOUR POOL FENCE MUST BE CLEAR OF ANY OBJECTS SUCH AS BBQS, TREES, ROCKS, SHRUBS AND DECKCHAIRS THAT COULD HELP A SMALL CHILD CLIMB OVER THE FENCE

POOL COMPLIANCE NOTES:

- ALL FENCES TO COMPLY WITH AS1926 SWIMMING POOL SAFETY STANDARDS AND THE SWIMMING POOLS ACT
- ENSURE A WARNING/RESUSCITATION SIGN IS DISPLAYED IN ACCORDANCE WITH THE SWIMMING POOLS ACT
- ENSURE GATE FREE OF OBSTRUCTIONS THAT COULD HOLD GATE OPEN AND IS SELF CLOSING AND SELF LATCHING
- ENSURE POOL FENCE IS A MINIMUM OF 1200MM HIGH (MEASURED OUTSIDE POOL AREA)
- ENSURE MAXIMUM 100MM GAP UNDER POOL FENCE
- ENSURE BOUNDARY FENCES ARE 1800MM HIGH WHEN MEASURED POOL SIDE IN ACCORDANCE WITH SWIMMING POOLS ACT
- REMOVE ANY LANDSCAPING THAT INTRUDES INTO THE NON CLIMABLE ZONES IN ACCORDANCE WITH THE SWIMMING POOLS ACT.
- THERE MUST BE AN APPROPRIATE WARNING SIGN, INCLUDING DETAILS OF RESUSCITATION (CPR) TECHNIQUES, IN THE IMMEDIATE VICINITY OF THE POOL AREA AND WHICH CAN BE EASILY READ FROM A DISTANCE OF 3 METRES

NOTE:

- WATER FROM A SWIMMING POOL MUST BE DISCHARGED IN ACCORDANCE WITH AN APPROVAL UNDER THE LOCAL GOVERNMENT ACT 1993 IF THE LOT IS NOT CONNECTED TO A SEWER MAIN.
- THE PUMP MUST BE HOUSED IN AN ENCLOSURE THAT IS SOUNDPROOFED.

ALL CDC CODES NOW REQUIRE THE EDGE OF POOL (NOT COPING) TO BE BEHIND THE BUILDING LINE OF THE DWELLING TO BOTH THE PRIMARY AND SECONDARY ROADWAY. (THIS IS MEASURED FROM THE CLOSEST POINT OF THE DWELLING TO EITHER ROADWAY. AS ALWAYS IF YOUR UNSURE WITH IRREGULAR SHAPED LOTS WE CAN ASSIST WITH PRELIMINARY REVIEWS SO YOU HAVE CONFIDENCE WHEN SPEAKING WITH CLIENTS IF THEY WANT TO PURSUE THE CDC PATHWAY OF APPROVAL.

CDC SWIMMING POOL PUMP- THE PUMP IS TO BE MINIMUM 450MM FROM THE LOT BOUNDARY AND HOUSED IN A SOUNDPROOFED ENCLOSURE. NOTE: WHERE THE PUMP/FILTER EQUIPMENT IS ADJACENT TO THE POOL BARRIER/FENCE (BOUNDARY AND INTERNAL) THE EQUIPMENT INCLUDING HOUSING IS TO BE MINIMUM 500MM AWAY FROM BARRIER TO NOT REDUCE BARRIER HEIGHT.

CDC SWIMMING POOL HEAT PUMP WATER HEATER – WHERE PROVIDED, A HEAT PUMP WATER HEATER IS TO NOT OPERATE MORE THAN 5 DB(A) ABOVE AMBIENT BACKGROUND MEASURED AT ANY PROPERTY BOUNDARY DURING PEAK TIME AND DURING OFF PEAK TIME—AT A NOISE LEVEL THAT IS AUDIBLE IN HABITABLE ROOMS OF ADJOINING RESIDENCES.

Backyard pool plan for Dwelling A. The plan shows a rectangular pool with dimensions 1250m x 1250m, totaling 16,425 M³. The pool is surrounded by a 1200mm high child proof safety fence and a self-closing, self-locking gate. The pool is located within a larger area of 722.3 m². The plan also shows the pool pump equipment to be housed in a sound proof enclosure and clear of non-climbable zone (900mm and 500mm away). The pool filtration system is to comply with AS 1926.3-2010. The plan includes a legend for various materials and features, and a scale bar indicating 1:50.

BACKYARD POOL PLAN - DWELLING A

1 : 50

VISUAL SCALE 1:50 @ A1

Pool long section showing the pool depth, pump location, and boundary details. The pool is 16,425 M³. The pump is housed in a sound proof enclosure and clear of non-climbable zone (900mm and 500mm away). The pool filtration system is to comply with AS 1926.3-2010. The plan includes a legend for various materials and features, and a scale bar indicating 1:50.

POOL LONG SECTION

1 : 50

Pool cross section showing the pool depth, pump location, and boundary details. The pool is 16,425 M³. The pump is housed in a sound proof enclosure and clear of non-climbable zone (900mm and 500mm away). The pool filtration system is to comply with AS 1926.3-2010. The plan includes a legend for various materials and features, and a scale bar indicating 1:50.

POOL CROSS SECTION

1 : 50



Mark Richardson
Certifier
BDC3297



COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED IN WHOLE OR IN PART WITHOUT THE WRITTEN

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- | | |
|--|----------------------|
| | NON-TRAFFICABLE |
| | LANDSCAPE |
| | CONCRETE PATH |
| | CONCRETE SURFACE |
| | SWIMMING POOL |
| | TILED FLOOR |
| | ARTICULATION |
| | OVERHEAD |
| | HIDDEN |
| | SITE BOUNDARY |
| | SMOKE ALARM |
| | MECH VENTILATION |
| | WET AREA FLOOR WASTE |
| | 90 STUD WALL |
| | 110 BRICK |
| | 250 BRICK VENEER |
| | 270 DOUBLE BRICK |
| | 130 CLADDING |
| | 200 HEBB WALL |

TITLE


BACKYARD PLAN

CHECKED BY JE

DWG # INHAUS-10 REVISION D

PROJECT #

2604




BACKYARD PLAN - DWELLING B

1 : 50



VISUAL SCALE 1:100 @ A1



BACKYARD CROSS SECTION

1 : 50

- MECHANICAL VENTILATION LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS 1668.2
- SMOKE ALARM LOCATIONS ARE LOCATED AND NOTED IN ACCORDANCE TO AS3786 & NCC HOUSING PROVISIONS CLAUSE 9.5.2
- EXTERNAL BALCONIES ARE TO BE WATERPROOFED IN ACCORDANCE PER NCC – H2D8 & AS 4654.1 & 2.
- EXTERNAL BALCONIES AND PATIOS/ALFRESCO HAVE A MINIMUM STEPDOWN OF 50MM (N2 WIND) OR 70MM (N3 WIND).
- WINDOWS LOCATED WITHIN SHOWER AREA HAVE A SILL HEIGHT OF MINIMUM 1800MM
- WET AREA FLOOR WASTE LOCATIONS AND FALLS BETWEEN 1:50 – 1:80 TO ALL FLOOR WASTES IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 10.2.12.
- NOMINATED HANDRAILS ARE LOCATED AND NOTED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.5.
- FIRST FLOOR BEDROOM WINDOWS ARE TO HAVE WINDOW RESTRICTORS OR SCREENS (CRIM-SAFE STYLE MESH) INSTALLED IN ACCORDANCE TO NCC HOUSING PROVISIONS CLAUSE 11.3.7.
- PROPOSED DISCHARGE LOCATIONS OF MECHANICAL EXHAUSTS ARE EXTERNALLY DUCTED THROUGH WALLS
- POOL PUMP EQUIPMENT TO BE HOUSED IN A SOUND PROOF ENCLOSURE AT 1800MM HIGH (NON-CLIMBABLE) AND CLEAR OF NON-CLIMBABLE ZONE (900MM AND 500MM AWAY)
- SWIMMING POOL FILTRATION SYSTEM IS TO COMPLY WITH AS 1926.3-2010
- MASONRY ARTICULATION JOINTS AS PER AS 4773.2 & NCC HOUSING PROVISIONS CLAUSE 5.6.8 (VERTICAL ARTICULATION JOINTS).

INHAUSDESIGNS



bdag

ARCHITECTS & DESIGNERS

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOR P/LD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA

ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER

USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE

DESCRIPTION

A 22.01.26 ISSUED FOR CLIENT REVIEW

B 04.02.26 ISSUED FOR CONSULTANTS

C 17.02.26 REISSUED FOR CONSULTANTS

D 06.03.26 ISSUED FOR CDC APPROVAL

E XXXX XXXX

F XXXX XXXX

LEGEND

NON-TRAFFICABLE

LANDSCAPE

CONCRETE PATH

CONCRETE SURFACE

SWIMMING POOL

TILED FLOOR

ARTICULATION

OVERHEAD

HIDDEN

SITE BOUNDARY

SMOKE ALARM

MECH-VENTILATION

WET AREA FLOOR WASTE

90 STUD WALL

110 BRICK

250 BRICK VENEER

270 DOUBLE BRICK

130 CLADDING

200 HEBEL WALL

TITLE

WINDOW/ DOOR SCHEDULE

CHECKED BY

JE

DWG #

INHAUS-11

REVISION

D


PROJECT #

2604

WINDOW SCHEDULE

GROUND FLOOR LEVEL

ELEVATION



W01

W02

W03

W04

W05


W06

W07

W08

FIRST FLOOR LEVEL

ELEVATION



W06

W07

W09

W10

W11


W13

WINDOW SCHEDULE				
TYPE MARK	COUNT	LEVEL	WIDTH	HEIGHT
W02	1	GROUND FLOOR LEVEL	900	900
W03	1	GROUND FLOOR LEVEL	900	2700
W04	6	GROUND FLOOR LEVEL	900	2100
W05	1	GROUND FLOOR LEVEL	900	1200
W06	1	GROUND FLOOR LEVEL	2000	2700
W07	1	GROUND FLOOR LEVEL	900	2700
W08	1	GROUND FLOOR LEVEL	600	900
W15	2	GROUND FLOOR LEVEL	600	2100
W06	2	FIRST FLOOR LEVEL	2000	2700
W07	2	FIRST FLOOR LEVEL	900	2700
W09	6	FIRST FLOOR LEVEL	600	1800
W10	2	FIRST FLOOR LEVEL	2600	900
W11	1	FIRST FLOOR LEVEL	1000	1800
W13	1	FIRST FLOOR LEVEL	1800	2700
W16	3	FIRST FLOOR LEVEL	1000	1200
SK01	4	FIRST CEILING LEVEL	572	1181
SK02	2	FIRST CEILING LEVEL	900	900
GRAND TOTAL: 37				

DOOR SCHEDULE

FIRST FLOOR LEVEL

ELEVATION



D02


D03

D01

SD03

SD04

ELEVATION



D01

D02

SD01

SD02

DOOR SCHEDULE				
TYPE MARK	COUNT	LEVEL	WIDTH	HEIGHT
D01	1	GROUND FLOOR LEVEL	1520	2500
D01B	1	GROUND FLOOR LEVEL	1200	2500
D02	10	GROUND FLOOR LEVEL	820	2400
GARAGE DOOR	2	GROUND FLOOR LEVEL	2900	2500
POOL DOOR	1	GROUND FLOOR LEVEL	900	1125
SD01	1	GROUND FLOOR LEVEL	4720	2660
SD02	1	GROUND FLOOR LEVEL	4000	2700
D01	2	FIRST FLOOR LEVEL	1520	2500
D02	9	FIRST FLOOR LEVEL	820	2400
D03	1	FIRST FLOOR LEVEL	1000	2400
SD03	1	FIRST FLOOR LEVEL	3720	2660
SD04	1	FIRST FLOOR LEVEL	3320	2660
GRAND TOTAL: 31				

INHAUSDESIGNS



bdag

ARCHITECT

COPYRIGHT

THE DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AFFILIATES.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.

- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.

- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE

DESCRIPTION

A 22.01.26 ISSUED FOR CLIENT REVIEW

B 04.02.26 ISSUED FOR CONSULTANTS

C 17.02.26 REISSUED FOR CONSULTANTS

D 06.03.26 ISSUED FOR CDC APPROVAL

E XXXX XXXX

F XXXX XXXX

LEGEND

NON-TRAFFICABLE

LANDSCAPE

CONCRETE PATH

CONCRETE SURFACE

SWIMMING POOL

TILED FLOOR

ARTICULATION

OVERHEAD

HIDDEN

SITE BOUNDARY

SMOKE ALARM

MECH-VENTILATION

WET AREA FLOOR WASTE

90 STUD WALL

110 BRICK

250 BRICK VENEER

270 DOUBLE BRICK

130 CLADDING

200 HEBEL WALL

TITLE

WALL SCHEDULE/FENCE - DWELLING A

CHECKED BY JE

DWG # INHAUS-12

REVISION D

PROJECT # 2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

FENCE PLAN - DWELLING A













1 : 50

VISUAL SCALE 1:50 @ A1

FENCE ELEVATION - DWELLING A

1 : 50

WALL LEGEND

WALL TYPES	TYPE MARK	DESCRIPTION
	ST-01	STUD WALL - 90 MM INTERNAL WALLS - 90 MM TIMBER FRAME WITH 13 MM PLASTER LINING
	ST-02	STUD CLADDING - 130 MM 40MM CLADDED EXTERNAL WALLS - 90 MM STUD INTERIOR
	ST-03	STEEL FRAME CLADDING - 130 MM 40MM CLADDED EXTERNAL WALLS - 90 MM STEEL FRAME INTERIOR.
	H-01	HEBEL WALL - 200 MM 75MM HEBEL EXTERNAL WALLS - 90 MM TIMBER FRAME INTERIOR .
	CB-150	CONCRETE BLOCKWORK - 200 MM 200MM BLOCK WALL INTERIOR - 20MM RENDER FINISH.
	DIN-110	DINCEL WALL - 110 MM 110MM DINCEL WALL INTERIOR - RENDER FINISH.
	DIN-200	DINCEL WALL - 200 MM 200MM DINCEL WALL EXTERIOR/INTERIOR - RENDER FINISH.
	DIN-275	DINCEL WALL - 275 MM 275MM DINCEL WALL EXTERIOR - RENDER FINISH.
	C-100	CONCRETE WALL - 100 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-150	CONCRETE WALL - 150 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-200	CONCRETE WALL - 200 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-300	CONCRETE WALL - 300 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	BRK-01	BRICK WALL - 110 MM 110 MM THICK WITH A MASS PER UNIT AREA OF NOT LESS THAN 290 KG/M2.
	BRK-02	BRICK VENEER - 250 MM 90 MM TIMBER STUD WALL, MASONRY WALL 110 MM; AND 50 MM THICK MINERAL INSULATION WITH A DENSITY OF 11 KG/M3 POSITIONED BETWEEN STUDS AND BRICK.
	BRK-03	DOUBLE BRICK WALL - 270 MM TWO COURSES OF 110 MM CLAY BRICK MASONRY WITH A CAVITY NOT LESS THAN 50 MM BETWEEN COURSES AND 50 MM THICK INSULATION OR 50 MM THICK POLYESTER INSULATION IN THE CAVITY.
	P-01	PIER WALL - 350 MM MADE OF 110 BRICKS SQAURE, ATTACHED OR DETAHCED FORM.

REFER TO ARCH PLANS FOR DIMENSIONS AND LAYOUT

FENCE COMPLIANCE NOTES:

THE STANDARDS THAT FENCES MUST NEED TO BE BUILT WITHOUT PLANNING OR BUILDING APPROVAL IN RESIDENTIAL ZONES.

TO BE EXEMPT, FENCES MUST MEET THESE DEVELOPMENT REQUIREMENTS:

- SIDE AND REAR BOUNDARY FENCES MUST NOT BE HIGHER THAN 1.8 M, OR HIGHER THAN 1.2 M IF THE FENCE IS BUILT FROM MASONRY.
- FENCES ALONG A BOUNDARY OF, OR IN THE SETBACK AREA OF, A PRIMARY OR SECONDARY ROAD MUST NOT BE TALLER THAN 1.2 M (THIS INCLUDES THE FRONT OF THE SITE AND ANY SIDE BOUNDARY ON CORNER SITES).
- FENCES ALONG THE BOUNDARY WITH, OR WITHIN THE SETBACK AREA TO A SECONDARY ROAD MUST: O BE AT LEAST 20% TRANSPARENT, ABOVE 400 MM. O NOT HAVE SOLID PIERS OR POSTS WIDER THAN 350 MM.
- CORNER SITES CAN, HOWEVER, HAVE SOLID FENCES UP TO 1.8 M IN HEIGHT ALONG THE REAR 50% OF THE SECONDARY FRONTAGE

INHAUSDESIGNS



bdaa

ARCHITECTS

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AFFILIATES.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.

- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.

- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

NON-TRAFFICABLE

LANDSCAPE

CONCRETE PATH

CONCRETE SURFACE

SWIMMING POOL

TILED FLOOR

ARTICULATION

OVERHEAD

HIDDEN

SITE BOUNDARY

SMOKE ALARM

MECH. VENTILATION

WET AREA FLOOR WASTE

90 STUD WALL

110 BRICK

250 BRICK VENEER

270 DOUBLE BRICK

130 CLADDING

200 HEBEL WALL

TITLE

WALL SCHEDULE/FENCE - DWELLING B

CHECKED BY

JE

DWG #

INHAUS-13

REVISION

D

PROJECT #

2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297















FENCE ELEVATION - DWELLING B/A

1 : 100

FENCE PLAN - DWELLING B/A

1 : 100

WALL LEGEND

WALL TYPES	TYPE MARK	DESCRIPTION
	ST-01	STUD WALL - 90 MM INTERNAL WALLS - 90 MM TIMBER FRAME WITH 13 MM PLASTER LINING
	ST-02	STUD CLADDING - 130 MM 40MM CLADDED EXTERNAL WALLS - 90 MM STUD INTERIOR
	ST-03	STEEL FRAME CLADDING - 130 MM 40MM CLADDED EXTERNAL WALLS - 90 MM STEEL FRAME INTERIOR.
	H-01	HEBEL WALL - 200 MM 75MM HEBEL EXTERNAL WALLS - 90 MM TIMBER FRAME INTERIOR .
	CB-150	CONCRETE BLOCKWORK - 200 MM 200MM BLOCK WALL INTERIOR - 20MM RENDER FINISH.
	DIN-110	DINCEL WALL - 110 MM 110MM DINCEL WALL INTERIOR - RENDER FINISH.
	DIN-200	DINCEL WALL - 200 MM 200MM DINCEL WALL EXTERIOR/INTERIOR - RENDER FINISH.
	DIN-275	DINCEL WALL - 275 MM 275MM DINCEL WALL EXTERIOR - RENDER FINISH.
	C-100	CONCRETE WALL - 100 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-150	CONCRETE WALL - 150 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-200	CONCRETE WALL - 200 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	C-300	CONCRETE WALL - 300 MM REFER TO STRUCTURAL ENGINEER'S DRAWINGS AND SPECIFICATIONS.
	BRK-01	BRICK WALL - 110 MM 110 MM THICK WITH A MASS PER UNIT AREA OF NOT LESS THAN 290 KG/M2.
	BRK-02	BRICK VENEER - 250 MM 90 MM TIMBER STUD WALL, MASONRY WALL 110 MM; AND 50 MM THICK MINERAL INSULATION WITH A DENSITY OF 11 KG/M3 POSITIONED BETWEEN STUDS AND BRICK.
	BRK-03	DOUBLE BRICK WALL - 270 MM TWO COURSES OF 110 MM CLAY BRICK MASONRY WITH A CAVITY NOT LESS THAN 50 MM BETWEEN COURSES AND 50 MM THICK INSULATION OR 50 MM THICK POLYESTER INSULATION IN THE CAVITY.
	P-01	PIER WALL - 350 MM MADE OF 110 BRICKS SQAURE, ATTACHED OR DETAHCED FORM.

REFER TO ARCH PLANS FOR DIMENSIONS AND LAYOUT

FENCE COMPLIANCE NOTES:

THE STANDARDS THAT FENCES MUST NEED TO BE BUILT WITHOUT PLANNING OR BUILDING APPROVAL IN RESIDENTIAL ZONES.

TO BE EXEMPT, FENCES MUST MEET THESE DEVELOPMENT REQUIREMENTS:

- SIDE AND REAR BOUNDARY FENCES MUST NOT BE HIGHER THAN 1.8 M, OR HIGHER THAN 1.2 M IF THE FENCE IS BUILT FROM MASONRY.
- FENCES ALONG A BOUNDARY OF, OR IN THE SETBACK AREA OF, A PRIMARY OR SECONDARY ROAD MUST NOT BE TALLER THAN 1.2 M (THIS INCLUDES THE FRONT OF THE SITE AND ANY SIDE BOUNDARY ON CORNER SITES).
- FENCES ALONG THE BOUNDARY WITH, OR WITHIN THE SETBACK AREA TO A SECONDARY ROAD MUST: O BE AT LEAST 20% TRANSPARENT, ABOVE 400 MM. O NOT HAVE SOLID PIERS OR POSTS WIDER THAN 350 MM.
- CORNER SITES CAN, HOWEVER, HAVE SOLID FENCES UP TO 1.8 M IN HEIGHT ALONG THE REAR 50% OF THE SECONDARY FRONTAGE



Mark Richardson
Certifier
BDC3297



COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS


DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

-
- NEIGHBORS
 LANDSCAPED AREA
 CONCRETE PATH
 PROPOSED DWELLING
 SWIMMING POOL
 TILED FLOOR
 PREVAILING WINDS
 VIEW CORRIDORS FROM ADJOINING BUILDINGS
 VIEWS FROM SUBJECT SITE
 PROPERTY BOUNDARY LINE
 EXISTING OUTLINE
 SUN PATH

SITE ANALYSIS

1 : 150




VISUAL SCALE 1:150 @ A1

TITLE
SITE ANALYSIS

CHECKED BY	JE
------------	----

DWG #	REVISION
INHAUS-14	D

PROJECT #
2604





Mark Richardson
Certifier
BDC3297



COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL

RESIDENTIAL / COMMERCIAL / INTERIORS


DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026



SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEN

- | | |
|---|----------------------|
|  | NON-TRAFFICABLE |
|  | LANDSCAPE |
|  | CONCRETE PATH |
|  | CONCRETE SURFACE |
|  | SWIMMING POOL |
|  | TILED FLOOR |
|  | ARTICULATION |
|  | OVERHEAD |
|  | HIDDEN |
|  | SITE BOUNDARY |
|  | SMOKE ALARM |
|  | MECH VENTILATION |
|  | WET AREA FLOOR WASTE |
|  | 90 STUD WALL |
|  | 110 BRICK |
|  | 250 BRICK VENEER |
|  | 270 DOUBLE BRICK |
|  | 130 CLADDING |
|  | 200 HEBEL WALL |

TITLE


SHADOW DIAGRAMS

CHECKED BY	J
------------	---

DWG #	REVISION
INHAUS-15	D


PROJECT #

2604



9AM 21 JUNE

1 : 150



10AM 21 JUNE

1 : 150



11AM 21 JUNE

1 : 150




VISUAL SCALE 1:100 @ A1



12PM 21 JUNE

1 : 150

INHAUSDESIGNS



 BDO

REGISTERED BUILDING DESIGNER

COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS


DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT


SCALE
AS INDICATED
@ A1

NOTES
. ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
. ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
. ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
. BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
. USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

 NON-TRAFFICABLE

 LANDSCAPE

 CONCRETE PATH

 CONCRETE SURFACE

 SWIMMING POOL

 TILED FLOOR

 ARTICULATION

 OVERHEAD

 HIDDEN

 SITE BOUNDARY

 SMOKE ALARM

 MECH VENTILATION

 WET AREA FLOOR WASTE

 90 STUD WALL

 110 BRICK

 250 BRICK VENEER

 270 DOUBLE BRICK

 130 CLADDING

 200 HEBEL WALL

TITLE
SHADOW DIAGRAMS

CHECKED BY
JE

DWG #
INHAUS-16

PROJECT #
2604

REVISION
D

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

1PM 21 JUNE

1:150

2PM 21 JUNE

1:150

3PM 21 JUNE

1:150

4PM 21 JUNE

1:150

VISUAL SCALE 1:100 @ A1

INHAUS
DESIGNS



COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI

MEMBERSHIP NO. 6605

EMAIL: ADMIN@INHAUSDESIGNS.COM.AU

BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

TITLE

3D HEIGHT BLANKET PLAN

CHECKED BY

JE

DWG #

INHAUS-17

REVISION

D

PROJECT #

2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

8.5M HEIGHT PLANE AXONOMETRIC

VISUAL SCALE 1:100 @ A1




Mark Richardson
Certifier
BDC3297



DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO: 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

16 HENSON STREET, MERRYLANDS

14.01.2026



NOTES

NOTES


- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA.
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEN

NOTE: RED DASH LINES INDICATES
WHAT IS TO BE DEMOLISHED

NOTE: DEMOLITION TO BE UNDERTAKEN
IN ACCORDANCE WITH AS2601




DEMOLITION NOTES:

1. ALL DEMOLITION BY CONTRACTOR UNLESS OTHERWISE NOTED.
2. ALL DEMOLITION MATERIAL SHALL BE REMOVED FROM SITE UNLESS OTHERWISE SPECIFIED TO BE RE-USED OR NOMINATED TO BE RETAINED.
3. EXISTING SERVICES TO BE RETAINED AND PROTECTED THROUGHOUT.
4. THE CONTRACTOR SHALL ALLOW FOR THE PROVISION OF HOARDING/SITE FENCING TO THE PERIMETER OF THE SITE FOR THE DURATION OF THE WORKS.
5. THE CONTRACTOR SHALL UNDERTAKE A SURVEY OF ALL EXISTING INGROUND SERVICES.
6. DEMOLITION PLAN CONFIRMING DEMOLITION TO BE CARRIED OUT IN ACCORDANCE WITH AS 2601—2001, THE DEMOLITION OF STRUCTURES.

DEMOLITION PLAN

1 : 100



VISUAL SCALE 1:100 @ A1

TITLE
DEMOLITION PLAN

CHECKED BY JE

INHAUS-18

PROJECT #

2604

INHAUS
DESIGNS

COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- NON-TRAFFICABLE
- LANDSCAPE
- CONCRETE PATH
- CONCRETE SURFACE
- SWIMMING POOL
- TILED FLOOR
- ARTICULATION
- OVERHEAD
- HIDDEN
- SITE BOUNDARY
- SMOKE ALARM
- MECH-VENTILATION
- WET AREA FLOOR WASTE
- 90 STUD WALL
- 110 BRICK
- 250 BRICK VENEER
- 270 DOUBLE BRICK
- 130 CLADDING
- 200 HEBEL WALL

TITLE

PARKING PLAN/DRIVEWAY

PROFILE A

CHECKED BY	JE
DWG #	REVISION
INHAUS-19	D
PROJECT #	
2604	

PARKING PLAN - DWELLING A

1 : 50


VISUAL SCALE 1:50 @ A1

DRIVEWAY PROFILE - DWELLING A

1 : 50

REFER TO CIVIL ENGINEERING
DRAWINGS/ COUNCIL DRIVEWAY
APPROVAL FOR ANY CONSTRUCTION
LEVELS

INHAUSDESIGNS



COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI

MEMBERSHIP NO. 6605

EMAIL: ADMIN@INHAUSDESIGNS.COM.AU

BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

- NON-TRAFFICABLE
- LANDSCAPE
- CONCRETE PATH
- CONCRETE SURFACE
- SWIMMING POOL
- TILED FLOOR
- ARTICULATION
- OVERHEAD
- HIDDEN
- SITE BOUNDARY
- SMOKE ALARM
- MECH-VENTILATION
- WET AREA FLOOR WASTE
- 90 STUD WALL
- 110 BRICK
- 250 BRICK VENEER
- 270 DOUBLE BRICK
- 130 CLADDING
- 200 HEBEL WALL

TITLE

PARKING PLAN/DRIVEWAY

PROFILE B

CHECKED BY

JE

DWG #

INHAUS-20

REVISION

D

PROJECT #

2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

PARKING PLAN - DWELLING B

1 : 50

DRIVEWAY PROFILE - DWELLING B

1 : 50

VISUAL SCALE 1:50 @ A1

REFER TO CIVIL ENGINEERING
DRAWINGS/ COUNCIL DRIVEWAY
APPROVAL FOR ANY CONSTRUCTION
LEVELS

INHAUSDESIGNS

bdoo

REGISTERED DESIGNER

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUSDESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE

AS INDICATED @ A1

NOTES

· ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

· ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA

· ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

· BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.

· USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

TITLE

SUBDIVISION PLAN

CHECKED BY

JE

DWG #

INHAUS-21

REVISION

D

PROJECT #

2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

Diagram illustrating the subdivision plan with dimensions:

- Lot A: 23045m x 15799m = 364,062 M²
- Lot B: 22675m x 15799m = 358,238 M²
- Total Width: 45720m
- Total Depth: 15799m

SUBDIVISION PLAN

1 : 100

VISUAL SCALE 1:100 @ A1

SUBDIVISION CERTIFICATE DOES NOT
FORM PART OF THIS APPROVAL. A
SUBDIVISION CERTIFIER WILL NEED TO
BE ENGAGED TO FORMALLY RECIEVE
SUBDIVISION APPROVAL.

INHAUSDESIGNS

Copyright

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE

DESCRIPTION

A22.01.26ISSUED FOR CLIENT REVIEW

B04.02.26ISSUED FOR CONSULTANTS

C17.02.26REISSUED FOR CONSULTANTS

D06.03.26ISSUED FOR CDC APPROVAL

EXXXXXXXX

FXXXXXXXX

LEGEND

BUILDER'S WASTE BIN

ALL WEATHER ACCESS SURFACE

SWIMMING POOL

SILT FENCE

CONSTRUCTION FENCE

STOCKPILE

PORTALOO

TITLE

SEDIMENT CONTROL PLAN

CHECKED BY

JE

DWG #

INHAUS-22

REVISION

D

PROJECT #

2604

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297

DAVIES

STREET

SEDIMENT CONTROL PLAN

1:100

VISUAL SCALE 1:100 @ A1

SEDIMENT CONTROL NOTES

EROSION CONTROL NOTES

1. ALL SEDIMENT DAMS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMUM OF 60 % FULL OF SOIL & DEBRIS.
2. SAND BAGS SHALL BE WELL PACKED AGAINST ADJOINING BAGS.
3. FILTER SHALL BE CONSTRUCTED BY REMOVING & WRAPPING GRATE IN FILTER FABRIC (PROPEX OR APPROVED EQUIVALENT) WITH MINIMUM 75MM FREE FABRIC OUTSIDE ALL EDGES OF GRATE WHEN IT IS REINSTALLED.
4. ALL EROSION AND SEDIMENTATION CONTROL MEASURES, INCLUDING REVEGETATION AND STORAGE OF SOIL AND TOPSOIL, SHALL BE

1. ALL EROSION AND SEDIMENTATION CONTROL MEASURES, INCLUDING REVEGETATION AND STORAGE OF SOIL AND TOPSOIL, SHALL BE IMPLEMENTED TO THE STANDARDS OF THE SOIL CONSERVATION OF NSW.
2. ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILIZED AS EARLY AS POSSIBLE DURING DEVELOPMENT.
3. SEDIMENT TRAPS SHALL BE CONSTRUCTED AROUND ALL INLET PITS, CONSISTING OF 300mm WIDE X 300mm DEEP TRENCH.
4. ALL SEDIMENT BASINS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMUM OF 60 % FULL OF SOIL MATERIALS, INCLUDING THE MAINTENANCE PERIOD.
5. ALL DISTURBED AREAS SHALL BE REVEGETATED AS SOON AS THE RELEVANT WORKS ARE COMPLETED.
6. SOIL AND TOPSOIL STOCKPILES SHALL BE LOCATED AWAY FROM DRAINAGE LINES AND AREA WHERE WATER MAY CONCENTRATE.
7. FILTER SHALL BE CONSTRUCTED BY STRETCHING A FILTER FABRIC (PROPEX OR APPROVED EQUIVALENT BETWEEN POST AT 2.0m CENTRES. FABRIC SHALL BE BURIED 150 ALONG ITS LOWER

1. ERECT SILT FENCE AND GRAVEL DRAIN.
2. DEMOLISH EXISTING STRUCTURES.
3. EXCAVATE STRIP FOOTINGS, ACCORDING TO ENGINEERS DETAILS.
4. FINISH CONSTRUCTION.
5. FINISH LANDSCAPING.
6. SILT FENCES ARE NOT TO BE REMOVED UNTIL ALL CONSTRUCTION AND VEGETATION HAS BEEN COMPLETED.

1. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSTALLED PRIOR TO ANY SITE DISTURBANCE.
2. ALL CONTROL MEASURE TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.
3. STRIPPING OF GRASS AND OTHER VEGETATION SHALL BE KEPT TO A MINIMUM.
4. TOPSOIL FROM ALL AREAS THAT WILL BE THAT WILL BE DISTURBED TO BE STRIPPED AND STOCKPILED, AND TO BE KEPT CLEAR FROM GUTTERS, DRAINS, STORMWATER, AND FOOTPATHS.
5. DRAINAGE TO BE CONNECTED TO STORM WATER AS SOON AS POSSIBLE.
6. ROAD AND FOOTPATH TO BE KEPT CLEAN, AND MUST BE SWEEP DAILY.
7. ALL SEDIMENT CONTROL STRUCTURES MUST BE INSPECTED AFTER RAINFALL FOR ANY STRUCTURAL DAMAGE. ALL TRAPPED SEDIMENT WILL BE REMOVED TO A NOMINATED STOCKPILE.

INHAUSDESIGNS

bdo

MEMBERSHIP NO. 6605

COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE
AS INDICATED @ A1

NOTES
- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND


TITLE
SCHEDULE OF COLOURS AND FINISHES

CHECKED BY JE
DWG # INHAUS-23
PROJECT # 2604


REVISION
D

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026


Mark Richardson
Certifier
BDC3297



SELECTED WINDSPRAY
(LIGHT) COLORBOND
STEEL FINISH



SELECTED MONUMENT
COLORBOND STEEL
FINISH



SELECTED CHARRED
TIMBER
SLATS:
- DARK WOOD
- LIGHT WOOD



SELECTED FRAMELESS
GLASS BALUSTRADES AT
1200MM HEIGHT TO AS
STANDARDS.



SELECTED MASONRY
BRICK PGH OPALINE
TOURMALINE BRICKS.



SELECTED WHITE
RENDER




SELECTED STONE
CLADDING FROM
ARMSTONE; LOOSE
STONE CLADDING



MONUMENT GREY
TRAPEZOIDAL ROOF.
(MIN. 2 DEGREE PITCH)



INHAUSDESIGNS



bdaa

© 2024 INHAUSDESIGNS PTY LTD

COPYRIGHT

THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUSDESIGNS PTY LTD OR ITS AGENT

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU


CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT



SCALE

AS INDICATED @ A1

NOTES

- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE

DESCRIPTION

A 22.01.26 ISSUED FOR CLIENT REVIEW

B 04.02.26 ISSUED FOR CONSULTANTS

C 17.02.26 REISSUED FOR CONSULTANTS

D 06.03.26 ISSUED FOR CDC APPROVAL

E XXXX XXXX

F XXXX XXXX

LEGEND

TITLE

LANDSCAPE PLAN/MAINTENANCE PLAN

CHECKED BY

JE

DWG #

INHAUS-24

PROJECT #

2604

REVISION


D


MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier
BDC3297


LANDSCAPE PLAN

1 : 100







TYPICAL PLANTING DETAIL



PLANT DETAIL AT BUILDING LINE



TYPICAL GRASS DETAIL



TREE DETAIL

MidCoast Council AUS-SPEC
02 SITE, URBAN AND OPEN SPACES

0259 Landscape – maintenance

Item	Action
Turf	Thin out planting Pruning/trimming Returfing Seeding Treat for disease Topdressing Weeding Mowing/trimming Soil Erosion/bank stabilisation Additional soil Soil conditioner Weeding Mulch Top up mulch Rubbish removal Generally remove bottles, paper, cigarette butts etc. Remove leaf litter from path and paved areas Irrigation Replace parts Repair Clean out Adjust Clean out subsurface drains Paving and pathways Repair dips, hollows, irregularities Remove stains and graffiti Replace sections of upfit Clear main pathway drains of debris Weeding Infant playground Make sure that all play structures are secure and in working order Fencing Repair fence or damaged parts Bollard Reinstall in original position Lighting Replace blown lamps and damaged diffusers Barriers Replace broken or dislocated railings or rails

4.3 MAINTENANCE PROCEDURE

WEEK	SPRING (Sept, Oct, Nov)	SUMMER (Dec, Jan, Feb)	AUTUMN (Mar, Apr, May)	WINTER (Jun, Jul, Aug)
1	Mow and trim lawns	Mow lawns; weed	Mow lawns	Weed
2	Weed, trim and	Weed; mow lawns;	Weed; mow lawns;	Mow and trim lawns

© NATSPEC (Oct 20)

10

December 2020

MidCoast Council AUS-SPEC
02 SITE, URBAN AND OPEN SPACES

0259 Landscape – maintenance

WEEK	SPRING (Sept, Oct, Nov)	SUMMER (Dec, Jan, Feb)	AUTUMN (Mar, Apr, May)	WINTER (Jun, Jul, Aug)
3	Mow and fertilise lawns; treat plant material for insects and disease	Mow lawns; weed; treat plant material for insects and disease	Mow and trim lawn	Weed
4	Weed; topdress, condition lawns and overtop bare patches; issue maintenance report	Weed; mow lawns; issue maintenance report	Weed; mow lawns; issue maintenance report	Mow lawns; issue maintenance report
5	Fertilise all trees and shrubs in garden beds; mow and trim lawns	Mow lawns; weed	Mow lawns	Mow lawns
6	Weed; inspect mulch for deficiencies in cover; check and adjust irrigation	Mow lawns; check and adjust irrigation	Weed; inspect mulch for deficiencies in cover; check and adjust irrigation	Mow and trim lawns; treat for insects and disease; check and adjust irrigation
7	Remove leaf litter from path and paved areas	Mow lawns; weed	Reinstate mulch as required; treat plant material for insects and disease; mow lawns	Weed
8	Weed; inspect condition of paving and furniture; issue maintenance report	Mow and trim lawns; inspect condition of paving & furniture; issue maintenance report	Weed; inspect condition of paving and furniture; issue maintenance report	Mow lawns; inspect condition of paving and furniture; issue maintenance report
9	Mow and trim lawns	Mow lawns; treat plant material for insects and disease	Mow lawns	Weed
10	Weed; mow lawns	Mow and topdress lawns	Weed; treat plant material for insects and disease	Mow and trim lawns
11	Mow and fertilise lawns; trim and adjust trees and shrubs	Mow lawns; trim and adjust lawns; weed	Mow and trim lawns; trim and adjust trees and shrubs	Prune back trees and shrubs after flowering
12	Weed; mow lawns; treat plant material for insects and disease	Mow, trim & fertilise lawns	Weed	Mow lawns; treat plant material for insects and disease
13	Check and adjust irrigation; mow lawns; issue maintenance report	Check and adjust irrigation; mow lawns; weed; issue maintenance report	Check and adjust irrigation; mow lawns; weed; issue maintenance report	Check and adjust irrigation; weed; issue maintenance report

4.4 IRRIGATION

Item	Frequency
------	-----------

© NATSPEC (Oct 20)

11

December 2020

MidCoast Council AUS-SPEC
02 SITE, URBAN AND OPEN SPACES

0259 Landscape – maintenance

Filters – mainline	Monthly
Electrical source output (auto system)	Monthly
Controller (automatic systems)	Monthly
Operation – progression - Station to Station.	Weekly
Proper activation of valves	Monthly
Proper timing of stations	6 monthly
Proper time and day readings	Weekly
Exterior appearance	6 monthly
Valve operation	6 monthly
Open, close completely (weeping)	Weekly
Sprinkler operation	Weekly
Rotaries – clogged nozzles	2 monthly
Plant obstructed pattern	2 monthly
Arc coverage	2 monthly
Radius adjustment	2 monthly
Pop-up action	2 monthly
Riser seal leaks	2 monthly
Set to grade	2 monthly
Coverage pressure	2 monthly
Rotational speed	2 monthly
Clogged screens	2 monthly
Head damage	2 monthly
Piping	2 monthly
Leaks – broken or cracked pipe	As Needed
Bad solvent welds, bad threaded	As Needed
Connection	As Needed
Clogged pipe	As Needed

4.5 ANNEXURE - REFERENCED DOCUMENTS

The following documents are incorporated into this worksection by reference:
AS 4373 2007 Pruning of amenity trees
AS 4419 2019 Soils for landscaping and garden use
MidCoast Council 2019 Development Engineering Handbook

5 ANNEXURE M – MIDCOAST COUNCIL SPECIFIC CLAUSES











M1:	Variations to or non-conformances with Council's AUS-SPEC are to be evaluated with reference to the procedure in Council's Development Engineering Handbook. Acceptance is to be obtained in writing from: a) an authorised representative of Council's Director of Infrastructure and Engineering Services, or b) an accredited certifier where they are the Principal Certifier and hold the relevant accreditation category for the type of work.	Variation procedure
M2:	This specification applies in addition to any development consent (DA) conditions. If there is any inconsistency, the conditions of consent shall	DA conditions

© NATSPEC (Oct 20)

12

December 2020

LANDSCAPE TEMPLATE

SYMBOL															
SPECIES	HYMENOSPORUM FLAVUM	DODONEA 'MR GREEN SHEEN'	PHORMIUM TENAX 'BRONZE BABY'	DIANELLA CAERULEA	MELALEUCA LINARIIFOLIA	MAGNOLIA 'LITTLE GEM' (PLEACHED)	LIRIOPE MUSCARI	LEUCOPHYTA BROWNII	PHILODENDRON XANADU	LOMANDRA TANIKA	HELICHRYSUM PETIOLARE 'LIME LIGHT'	SAPPHIRE BUFFALO TURF	DICHONDRA 'SILVER FALLS'	CASUARINA GLAUCA PROSTRATE 'SHAGPILE' - SHE-OAK	ELAEOCARPUS RETICULATUS BLUEBERRY ASH
MAXIMUM HEIGHT	15M	2.5M	0.75M	1M	8M	5M	0.3M	1M	1.2M	0.6M	0.6M	-	0.1M	0.2M	8-15M
IMAGE															

INHAUS
DESIGNS

bdag

COPYRIGHT
THIS DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOW PTY LTD OR ITS AGENT.

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI
MEMBERSHIP NO. 6605
EMAIL: ADMIN@INHAUSDESIGNS.COM.AU
BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE AS INDICATED @ A1

NOTES
- ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS
- ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA
- ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.
- BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.
- USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

TITLE
BASIX COMMITMENTS

CHECKED BY JE
DWG # INHAUS-25
PROJECT # 2604

REVISION
D

MLR Certified Pty Ltd
Reference: 26-023/01
Date: 13/03/2026

Mark Richardson
Certifier

BDG3297

CERTIFIED ENERGY - SUMMARY COMMITMENTS TABLE

1300 443 674
quote@certifiedenergy.com.au
www.certifiedenergy.com.au

Project Details

15/05/2026

Mark Richardson

Certifier

BDC3297

Proposed: Lot Number: 127

Dual Occupancy

Accreditation Number: HERA 10056

Address: 16 Henson Street, Merrylands, NSW, 2160

DP Number: 628

NatHERS Certificate Number: #HR-8B76BD-02

Windows

For detailed window specifications please refer to NatHERS Certificate

(NSW BASIX Thermal Protocol allows for ± 10% tolerance of SHGC Value & U Value <= than which overrides NatHERS Certificate)

Frame TypeGlass TypeGlazing (Dwelling or Unit)Glass TypeFrame Type

Aluminium (Standard)Dwelling ADouble Glazed ClearAluminium (Standard)

Skylights

Double Glazed Low-E ClearWood

External Walls

Brick VeneerLight ColourR2.70 Bulk Insulation

Cavity BrickLight ColourR1.70 Bulk Insulation

Metal CladLight ColourR2.70 Bulk Insulation

Internal Walls

Cavity wall, direct fix plasterboardR2.50 Bulk Insulation

Cavity wall, direct fix plasterboardNo insulation

Cavity BrickNo insulation

Floors

Suspended concrete slabUnder Slab InsulationSlab Edge InsulationAdditional Notes

Suspended timberAll Dwellings R3.50 Bulk InsulationN/A

Suspended timberDwelling A R3.50 Bulk InsulationN/A

Suspended timberDwelling B R4.00 Bulk InsulationN/A

Suspended timberDwelling C No insulationN/A

Suspended timberDwelling D R2.50 Bulk InsulationN/A

Ceiling

External ceiling - PlasterboardInsulationAdditional Notes

Internal ceiling - PlasterboardR6.00 Bulk Insulation

No insulation

Roof

InsulationAdditional Notes

Corrugated ironMedium Colour (polar absorbance 0.475-0.7)

R1.8 Bulk + Reflective side down, No air gap above (Anticon 75, 80mm)

Ceiling Penetrations

Lighting specificationDwelling is rated with Assumed daylight as per NatHERS Tech Note "Ceiling Penetrations 9.4 to 9.8"

Ceiling fansCeiling fans of 1200mm & 1400mm must be installed in the rooms mentioned in the NatHERS report

Overshadowing DetailsAdjoining units calculated into model calculations

Site

Orientation of nominal north elevationAs shown on plans

* Approved fireproof daylight covers HAVE been specified, which can be fully covered by insulation. Ceiling penetrations for exhaust dampers have been allowed (to all bathrooms, ensuites and internal laundry's) at the rate of 0.04 meters squared per exhaust fan penetration.

Thermal Comfort

BASIX Certificate Number: 1836261M_02

Fixtures4 star (>6 but <= 7.5 L/min)Rainwater tank sizeIndividual2000L

Shower head rating4 starConnected to Tank/;Outdoor Garden TapsAll ToiletsLaundry

Toilet rating4 starYesYesNo

Kitchen taps rating4 star

Bathroom Taps rating4 star

Individual SystemGas instantaneous6 StarLightingLight emitting diode

Refer to NatHERS Certificate for Full Count (if Applicable)

Bathroom Exhaust - Individual fan, ducted to facade or roofLaundry Exhaust - Individual fan, ducted to facade or roof

Control Switch - Manual switch on/offControl Switch - Manual switch on/off

CoolingHeating

Systems to - Living areas3-phase airconditioningEER 3.0 - 3.5Systems to - Living areas3-phase airconditioningEER 3.0 - 3.5

Systems to - Bedroom areas3-phase airconditioningEER 3.0 - 3.5Systems to - Bedroom areas3-phase airconditioningEER 3.0 - 3.5

Appliances

Cooktop - GasPhotovoltaic System (Minimum)

Oven - Electric1.5 Peak kW

PoolSpa

Volume16.8kLNo HeatingN/A

Heating SystemNo heatingNo Heating

Pool coverNoNo

Pool shadedNoNo

TimerYesNo

Energy & Water

Nationwide House Energy Rating Scheme®
Class 1 Summary
NatHERS® Certificate No. #HR-8B76BD-02

Generated on 09 Mar 2026 using Hero 4.1

Property

Address 16 Henson Street, Merrylands, NSW, 2160
Lot/DP Lot 127/ DP 628
NatHERS climate zone 56 - Mascot AMO



Accredited assessor

Name Jamie Bonnefin
Business name Certified Energy
Email jobs@certifiedenergy.com.au
Phone +61 1300 443
Accreditation No. 10056
Assessor Accrediting Organisation HERA

Verification

To verify this certificate, scan the QR code or visit <http://www.hero-software.com.au/pdf/HR-8B76BD-02>.
When using either link, ensure you are visiting <http://www.hero-software.com.au>



National Construction Code (NCC) requirements

The NCC allows the use of NatHERS accredited software to comply with the energy efficiency requirements for houses (Class 1 buildings) and apartments (Class 2 sole-occupancy units and Class 4 parts of buildings). The applicable requirements for houses are detailed in Specification 42 of NCC Volume Two. For apartments the requirements are detailed in clauses J3D3 and J3D15 of NCC Volume One.
NCC 2022 includes enhanced thermal performance requirements for houses and apartments. It also includes a new whole-of-home annual energy use budget which applies to the major equipment in the home.
The NCC, and associated ABCB Standards and support material, can be accessed at www.abcb.gov.au.
Note, variations and additions to the NCC energy efficiency requirements may apply in some states and territories.

Summary of all dwellings

Certificate number and link	Unit Number	Heating load (load limit) (MJ/m².yr)	Cooling load (load limit) (MJ/m².yr)	Total load (MJ/m².yr)	Star Rating	Whole of Home Rating
HR-TVSWBA-02	A	13.9 (26)	16.0 (19)	29.9	7.0	n/a
HR-63WLHM-02	B	12.4 (26)	16.7 (19)	29.2	7.1	n/a

Thermal performance
Star rating




NATIONWIDE
HOUSE
ENERGY RATING SCHEME®

The rating above is the minimum of all dwellings in this summary.

For more information on your dwelling's rating see: www.nathers.gov.au

Whole of Home
performance rating

No Whole of Home performance rating generated for this certificate or not completed for all dwellings.



#HW-TYVSWA-62	Netherlands Certificate	7.8 Star Rating as of 09 Mar 2026										
Window and glazed door type and performance Default* windows												
Window ID	Window Description		Maximum U-value*	SHGC*	SHGC substitution tolerance ranges lower limit upper limit							
HAAWS-05-056	Housing Aluminium Asewing Window Single Glazed		5.0	0.54	0.52	0.57						
HAASW-04-062	Housing Aluminium Fixed Window Single Glazed		4.9	0.64	0.61	0.67						
HASDD-025-024	Housing Aluminium Sliding Door Double Glazed		2.5	0.23	0.22	0.24						
HASDS-045-062	Housing Aluminium Sliding Door Single Glazed		4.5	0.61	0.58	0.64						
HASWS-045-062	Housing Aluminium Sliding Window Single Glazed		4.5	0.61	0.58	0.64						
Custom* windows												
Window ID	Window Description		Maximum U-value*	SHGC*	SHGC substitution tolerance ranges lower limit upper limit							
None												
Window and glazed door schedule												
Location	Window ID	Window no.	Height (mm)	Width (mm)	Window type	Opening %	Orientation	Shading device*				
Bathroom	HAAWS-05-056	W11	1800	1000	Asewing	10	W	None				
Bedroom 1	HAAWS-05-056	W09	1800	600	Asewing	10	E	None				
Bedroom 1	HAAWS-05-056	W09	1800	600	Asewing	10	E	None				
Bedroom 2	HASWS-045-062	W10	900	2600	Sliding	10	W	None				
Bedroom 3	HASWS-045-062	W10	900	2600	Sliding	10	S	None				
Guest Bedroom	HAAWS-05-056	W01	2700	600	Asewing	45	E	None				
Guest Bedroom	HAAWS-05-056	W01	2700	600	Asewing	45	E	None				
Guest ENS	HASWS-045-062	W02	900	900	Sliding	45	S	None				
Kitchen/Living	HAAWS-05-056	W04	2100	900	Asewing	45	W	None				
Kitchen/Living	HAAWS-05-056	W04	2100	900	Asewing	45	W	None				
Kitchen/Living	HAAWS-05-056	W04	2100	900	Asewing	45	W	None				
Kitchen/Living	HASDS-045-062	SD02	2700	4000	Sliding Door	68	S	None				
Laundry	HAAWS-05-056	W03	2700	900	Asewing	45	S	None				

BHR-TVSW6-62 NETHERS Certificate		7.8 Star Rating as of 09 Mar 2025										
Window and glazed door <i>schedule</i>												
Location	Window ID	Window no.	Height (mm)	Width (mm)	Window % Sliding Door	Opening %	Orient-ation	Shading device ^a				
Master Bedroom	HASDD-025-024	SD04	2660	3320	60	E	None					
Master ENS	HAAWS-050-056	W11	1800	1000	Awning	10	W	None				
Rumpus	HAFWS-040-002	W06	2700	2000	Fixed	0	E	None				
Roof window type and performance value												
Default ^a roof windows												
Window ID	Window Description		Maximum U-value ^a		SHGC ^a	SHGC substitution tolerance ranges						
None						lower limit, upper limit						
Custom ^a roof windows												
Window ID	Window Description		Maximum U-value ^a		SHGC ^a	SHGC substitution tolerance ranges						
VEL-0111-W						lower limit, upper limit						
	FS - Fixed Skylight DG 3mm LoE 366 / 6.5mm Argon Gap / 5.35mm Clear La		2.6		0.24	0.23						
Roof window <i>schedule</i>												
Location	Window ID	Window no.	Height (mm)	Width (mm)	Orient-ation	Outdoor shade	Indoor shade					
Bathroom	VEL-011-W	SK01	0	1181	572	W	None	None				
Master WIR	VEL-011-W	SK01	0	572	1181	W	None	None				
Master ENS	VEL-011-W	SK02	0	900	900	W	None	None				
Rumpus_FF	VEL-011-W	SK01	0	572	1181	W	None	None				
Skylight type and performance												
Skylight ID						Skylight description						
None												
Skylight <i>schedule</i>												
Location	Skylight ID	Skylight no.	Skylight shaft length (mm)	Area (m ²)	Orient-ation	Outdoor shade	Diffuser	Shaft Reflection				
None												
External door <i>schedule</i>												
Location			Height (mm)	Width (mm)	Opening %	Orientation						

^a Refer to glossary.
Generated on 09 Mar 2026 using Neo 4.1 for A, 16 Heron Street, Maryland, NSW, 2160

Page 7 of 14

BH-TY5WBA-02 NATHRES Certificate		7.8 Star Rating as of 09 Mar 2025				
External door schedule						
Location	Height (mm)	Width (mm)	Opening %	Orientation		
Garage	2500	2900	0	E		
Kitchen/Living	2500	1520	90	E		
External wall type						
Wall ID	Wall Type	Solar Absorbance	Wall Colour	Bulk insulation (R-value)	Reflective wall wrap?	
MC-NONREFL-CAV	Brick Veneer Stud Wall with Non-Reflective Sarking	0.40	Light (Southern)	1.70	No	
CAV-BRICK-110-110-PB	Cavity Brick Wall - 110mm/110mm Plasterboard Internally	0.40	Light (Southern)	1.70	No	
MC-NONREFL-CAV	Metal Gull Battened Non-Hell Cavity Stud Wall	0.25	White (North)	2.70	No	
External window schedule						
Location	Wall ID	Height (mm)	Width (mm)	Orientation	Horizontal shading feature? projection (mm)	Vertical shading feature
Bathroom	MC-NONREFL-CAV	2700	2219	W	150	No
Bedroom 1	MC-NONREFL-CAV	2700	1721	E	500	Yes
Bedroom 2	MC-NONREFL-CAV	2700	4877	S	500	No
Bedroom 1	MC-NONREFL-CAV	2700	727	E	500	No
Bedroom 1	MC-NONREFL-CAV	2700	1150	E	500	Yes
Bedroom 2	MC-NONREFL-CAV	2700	3798	W	150	No
Bedroom 2	MC-NONREFL-CAV	2700	3004	N	300	Yes
Bedroom 3	MC-NONREFL-CAV	2700	3095	W	150	No
Bedroom 3	MC-NONREFL-CAV	2700	4032	S	500	No
Garage	BV-NONREFL-CAV	3000	3598	E	3450	Yes
Garage	CAV-BRICK-110-110-PB	3000	896	N	6890	Yes
Guest Bedroom	BV-NONREFL-CAV	3000	3709	E	300	Yes
Guest Bedroom	BV-NONREFL-CAV	3000	1185	N	4700	Yes
Guest ENS	BV-NONREFL-CAV	3000	1499	E	Yes	Yes
Guest ENS	BV-NONREFL-CAV	3000	3085	S	Yes	Yes
Kitchen/Living	BV-NONREFL-CAV	3000	6896	W	150	Yes

#BR-TYSWA-02: Numbers Certificates		7.5 Star Rating as of 09 Mar 2025				
External wall schedule						
Location	Wall ID	Height (mm)	Width (mm)	Orientation	Horizontal shading feature projection (mm)	Vertical shading features
Kitchen/Living	BV-MC-NREFL-CAV	3000	698	N		Yes
Kitchen/Living	BV-MC-NREFL-CAV	3000	3099	W	150	Yes
Kitchen/Living	BV-MC-NREFL-CAV	3000	2523	E	1485	Yes
Kitchen/Living	BV-MC-NREFL-CAV	3000	7417	S	3600	Yes
Laundry	BV-MC-NREFL-CAV	3000	1703	S	3600	Yes
Master Bedroom	MC-MC-NREFL-CAV	2700	3598	E	1200	Yes
Master Bedroom	CAV-BRICK-110-115-PB	2700	2492	N		Yes
Master ENS	MC-MC-NREFL-CAV	2700	1604	W	150	Yes
Master WR	MC-MC-NREFL-CAV	2700	2701	W	150	Yes
Pantry	BV-MC-NREFL-CAV	3000	3598	W	150	Yes
Pantry	CAV-BRICK-110-115-PB	3000	2109	N	6800	Yes
Pantry	MC-MC-NREFL-CAV	2700	2523	E	1685	Yes
Rumpus	MC-MC-NREFL-CAV	2700	2593	S		No
Stairs_FF	MC-MC-NREFL-CAV	2700	1981	E	500	Yes
Stairs_FF	MC-MC-NREFL-CAV	2700	1185	S	900	Yes
Stairs_FF	MC-MC-NREFL-CAV	2700	1185	N	3600	Yes
Stairs_GF	BV-MC-NREFL-CAV	3000	1981	E	300	Yes
Stairs_GF	BV-MC-NREFL-CAV	3000	1185	S	6550	Yes
Stairs_GF	BV-MC-NREFL-CAV	3000	3484	N	3450	Yes
WR 1	MC-MC-NREFL-CAV	2700	1605	E	500	No
WR 1	MC-MC-NREFL-CAV	2700	1185	N	900	Yes

Internal wall type			
Wall ID	Wall Type	Area (m²)	Bulk insulation
CAV-BRICK-110-115-PB neighbour	Cavity Brick Wall - 110mm/110mm Plasterboard Internally	28.6	0.00
INT-PB	Internal Plasterboard Stud Wall	74.3	2.50

* Refer to glossary

Generated on 09 Mar 2028 using HERS 4.1 for a 16 Heron Street, Maryland, NSW, 2160

Page 9 of 14

HSH-TYSWA-02 NARCHERS Certificate		7.5 Star Rating as of 09 Mar 2026			
Internal wall type					
Wall ID	Wall Type	Area (m ²)		Bulk Insulation	
INT-PB	Internal Plasterboard Stud Wall	135.8		0.00	
Floor type					
Location	Construction	Area (m ²)	Sub-floor ventilation	Added Insulation (R-value)	Covering
Bathroom	TIMB-001: Suspended Timber Floor	6.7	N/A	3.50	Tile (Btm)
Bedroom 1	TIMB-001: Suspended Timber Floor	17.6	N/A	3.50	Cork
Bedroom 2	TIMB-001: Suspended Timber Floor	11.4	N/A	3.50	Cork
Bedroom 3	TIMB-001: Suspended Timber Floor	12.5	N/A	3.50	Cork
Garage	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	21.6	Enclosed (Disc.)	3.50	Exposed
Guest Bedroom	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	11.4	Enclosed (Disc.)	3.50	Cork
Guest ENS	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	4.6	Enclosed (Disc.)	3.50	Tile (Btm)
Kitchen/Living	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	77.5	Enclosed (Disc.)	3.50	Cork
Laundry	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	6.0	Enclosed (Disc.)	3.50	Tile (Btm)
Linen	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	2.9	Enclosed (Disc.)	3.50	Cork
Master Bedroom	TIMB-001: Suspended Timber Floor	6.1	N/A	3.50	Cork
Master Bedroom	TIMB-001: Suspended Timber Floor - Lined Below	6.3	N/A	3.50	Cork
Master ENS	TIMB-001: Suspended Timber Floor	5.5	N/A	3.50	Tile (Btm)
Master WVR	TIMB-001: Suspended Timber Floor	11.7	N/A	3.50	Cork
Pantry	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	7.6	Enclosed (Disc.)	3.50	Cork
Rumpus	TIMB-001: Suspended Timber Floor	43.7	N/A	3.50	Cork
Stairs_FF	TIMB-001: Suspended Timber Floor	6.1	N/A	3.50	Cork
Stairs_GF	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	0.7	Enclosed (Disc.)	3.50	Cork
WC	SUSP-CONC-200-UNED: Suspended Concrete Slab Floor (200mm) - Lined Below	3.6	Enclosed (Disc.)	3.50	Tile (Btm)
WIR 1	TIMB-001: Suspended Timber Floor	5.0	N/A	3.50	Cork

9 Refer to glossary

Generated on 09 Mar 2026 Using HERS 4.10 by A. Henson Street, Maryland, NSW 2160

Page 10 of 14

2604

INHAUSDESIGNS

bdoo

4 STAR RATED BUILDING DESIGNER

COPYRIGHT

THE DRAWING AND DESIGN IS SUBJECT TO COPYRIGHT AND SHALL NOT BE COPIED OR REPRODUCED WITHOUT THE WRITTEN PERMISSION OF INHAUS DESIGNS NOR ITS LTD OR ITS AGENT

RESIDENTIAL / COMMERCIAL / INTERIORS

DESIGNER NAME: JUSTIN ELAZZI

MEMBERSHIP NO: 6605

EMAIL: ADMIN@INHAUSDESIGNS.COM.AU

BROWSE: WWW.INHAUSDESIGNS.COM.AU

CORNER BLOCK DUAL-OCCUPANCY

16 HENSON STREET, MERRYLANDS

DAVID BOURCHAN

14.01.2026

NORTH POINT

SCALE

AS INDICATED @ A1

NOTES

. ALL WORKS TO COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS

. ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE OF AUSTRALIA

. ALL DIMS TO BE VERIFIED BY BUILDER PRIOR TO CONSTRUCTION.

. BOUNDARY DIMENSIONS & ALL LEVELS SUBJECT TO CONFIRMATION BY BUILDER.

. USE FIGURED DIMENSIONS ONLY, DO NOT SCALE FROM PLANS.

REV/DATE	DESCRIPTION
A 22.01.26	ISSUED FOR CLIENT REVIEW
B 04.02.26	ISSUED FOR CONSULTANTS
C 17.02.26	REISSUED FOR CONSULTANTS
D 06.03.26	ISSUED FOR CDC APPROVAL
E XXXX	XXXX
F XXXX	XXXX

LEGEND

TITLE

NCC/AS - STAIRS

CHECKED BY

JE

DWG #

INHAUS-29

PROJECT #

2604

11.2.2 Stairway construction

(1) A stairway must be designed to take loading forces in accordance with AS/NZS 1170.1 and must have—

(a) not more than 18 and not less than 2 *risers* in each *flight*; and

(b) *goings* (G), *risers* (R) and a slope relationship quantity (2R + G) in accordance with Table 11.2.2a, except as permitted by (2) and (3); and

(c) *landings* and *risers* throughout each *flight*, except as permitted by (3) and (4), and the dimensions of *goings* (G) and *risers* (R) in accordance with Table 11.2.2b, except as permitted by (2) and (3); and

(d) adjacent *risers*, or between adjacent *goings*, is not more than 5 mm; and

(i) the largest and smallest *riser* within a *flight*, or the largest and smallest *going* within a *flight*, is not more than 10 mm; and

(d) *landings* and *risers* throughout each *flight*, except as permitted by (3) and (4), and the dimensions of *goings* (G) and *risers* (R) in accordance with Table 11.2.2b, except as permitted by (2) and (3); and

(e) treads of solid construction (not mesh or other perforated material) if the stairway is more than 10 m high or connects more than 3 storeys.

(2) In the case of a stairway serving only non-habitable rooms, such as attics, storerooms and the like that are not used on a regular or daily basis—

(a) the *going* (G), *riser* (R) and slope relationship quantity (2R + G) in accordance with Table 11.2.2a may be substituted with those in Table 11.2.2b; and

(b) need not comply with (1)(d).

(4) The point of measurement of the *going* (G) in the slope relationship quantity (2R + G) for *tapered treads* and treads in *spiral stairways* as described in Table 11.2.2a (see Figure 11.2.2a, Figure 11.2.2b and Figure 11.2.2c) must be—

(a) for *tapered treads*, other than treads in a *spiral stairway*—

(i) not more than 1 m in width, the middle of the unobstructed width of the stairway (see Figure 11.2.2b); and

(ii) more than 1 m in width, 400 mm from the unobstructed width of each side of the stairway (see Figure 11.2.2c); and

(b) for treads in *spiral stairways*, the point seven tenths of the unobstructed width from the face of the centre pole or support towards the handrail side (see Figure 11.2.2d and Figure 11.2.2e).

(5) *Riser* and *going* dimensions must be measured in accordance with Figure 11.2.2f.

Table 11.2.2a Riser and going dimensions (mm)

Stair type	<i>Riser</i> (R) (see Figure 11.2.2f)		<i>Going</i> (G) (see Figure 11.2.2f)		Slope relationship (2R+G)	
	Max	Min	Max	Min	Max	Min
Stairs (other than spiral)	190	115	355	240	700	550
Spiral	220	140	370	210	680	590

Table Notes

Riser and *going* dimensions must be measured in accordance with Figure 11.2.2f.

Table 11.2.2b Riser and going dimensions (mm) — stairways serving

The *going* (G) must be not more than the tread depth plus a maximum gap of 30 mm between the rear edge of one tread and the nosing of the tread above.

Figure 11.2.2a Measurement of slope relationship — Plan view — Stair with 2 flights

Figure 11.2.2c Measurement of slope relationship — Plan view —Tapered treads more than 1 m wide

Figure 11.2.2d Spiral stairs — Measurement for slope relationship

Figure 11.2.2f Riser and going dimensions — Measurement

Explanatory information: Not more than 18 and not less than 2 risers

11.2.2(1)(a) states that a stairway must have not more than 18 and not less than 2 *risers* in each *flight*. Where there are less than 2 *risers* in a *flight*, it

Explanatory information: Going and riser dimensions

The purpose of 11.2.2 is to achieve constant *going* and *riser* dimensions deemed safe for people to walk up and down. This minimises the risk of people overstepping during descent on uneven stairs (due to short *goings*) and tripping on ascent (due to high *risers*). Table 11.2.2a and Table 11.2.2b express ratios between *going* and *riser* dimensions which are considered safe for use. 11.2.2(1)(c) accounts for conditions such as movement of materials due to atmospheric moisture changes or minor deviations related to variations in materials which affect finished stair dimensions.

Explanatory Figure 11.2.2a illustrates adjacent *risers* within a *flight* with minor deviations in the materials affecting the finished stair dimensions. The nominated *riser* height is exceeded by *riser* A. As a consequence *riser* height B is less than the nominated *riser* height. The difference between *riser* A and *riser* B cannot exceed 5 mm.

Explanatory Figure 11.2.2b illustrates an entire *flight* with minor deviations in the materials affecting the finished *riser* dimensions. In addition to the 5 mm difference permitted between adjacent *goings* or *risers*, the maximum difference between the smallest and largest *going* or *riser* within a *flight* must not exceed 10 mm. Despite the deviations shown in both diagrams, the stairs in the *flight* are deemed constant. Irrespective of any minor deviations permitted by 11.2.2(1)(c), finished *going* and *riser* dimensions must not exceed the limitations stipulated in Table 11.2.2a.

Figure 11.2.2a (explanatory) Minor deviations in a stairway — deviation in adjacent risers

Figure Notes

1. A = larger *riser* of two adjacent *risers*.

2. B = smaller *riser* of two adjacent *risers*.

3. This diagram only shows deviations in *risers*, however the same principle can apply for *goings*.

Figure 11.2.2b (explanatory) Minor deviations in a stairway — deviations over a flight

Figure Notes

1. C = largest *riser* of the *flight*.

2. D = smallest *riser* of the *flight*.

3. This diagram only shows deviations in *risers*, however the same principle can apply for *goings*.

Explanatory information: Openings in stair risers

11.2.2(1)(d) allows the use of open *riser* stairs. However, it limits the openings to 125 mm to minimise the risk of a person (especially a young child) falling through the opening created by the open *riser*.

Explanatory information: Stairways with winders

- 11.2.2(3) allows the use of *winders* in stairways. However, 11.2.2(3) places a restriction on the number of allowable *winders* in a stairway *flight*, this restriction would apply equally to not permit a stairway incorporating a consecutive series of *winders* in a *flight*.
- This also means the maximum number of consecutive *winders* in any stairway

11.3.4 Construction of barriers to prevent falls

(1) A barrier *required* by 11.3.3¹⁴ must comply with (2) to (11).

(2) The height of a barrier must be in accordance with the following:

(a) The height must not be less than 865 mm above the nosings of the stair treads, the floor of a ramp or the like (see Figure 11.3.4a).

(b) The height must not be less than—

(i) 1 m above the floor of any *landing*, *corridor*, *hallway*, *balcony*, *deck*, *verandah*, *access path*, *mezzanine*, *access bridge*, *roof top space* or the like to which general access is provided (see Figure 11.3.3b and Figure 11.3.4a); or

(ii) 865 mm above the floor of a *landing* to a stairway or ramp where the barrier is provided along the inside edge of the *landing* and does not exceed a length of 500 mm.

(3) A transition zone may be incorporated where the barrier height changes from 865 mm on the stairway *flight* or ramp to 1 m at the *landing* (see Figure 11.3.4b).

(4) Openings in barriers (including decorative balustrades) must be constructed so that they do not permit a 125 mm sphere to pass through it and for stairways, the opening is measured above the nosing line of the stair treads (see Figure 11.3.4a).

(5) Where a *required* barrier is fixed to the vertical face forming an edge of a *landing*, *balcony*, *deck*, *stairway* or the like, the opening formed between the barrier and the face must not exceed 40 mm.

(6) For the purposes of (5), the opening is measured horizontally from the edge of the trafficable surface to the nearest internal face of the barrier.

(7) A barrier to a stairway serving a non-habitable room, such as an attic, storeroom or the like that is not used on a regular or daily basis, need not comply with (4) if—

(8) Restriction on horizontal elements:

(a) Where it is possible to fall more than 4 m, any horizontal elements within the barrier between 150 mm and 760 mm above the floor must not facilitate climbing.

(b) For the purpose of (a), the 4 m is measured from the floor level of the trafficable surface to the surface beneath.

(9) A barrier constructed of wire is deemed to meet the requirements of (4) if it is constructed in accordance with 11.3.6¹⁵.

(10) A glass barrier or *window* serving as a barrier must comply with H1D8¹⁶ and the relevant provisions of this Part.

(11) A barrier, except a *window* serving as a barrier, must be designed to take loading forces in accordance with AS/NZS 1170.1.

Figure 11.3.4a Barrier construction

Figure 11.3.4b Measuring heights for barriers and handrails and where transition zones are allowed

Explanatory information

For a *window* forming part of a barrier, any horizontal elements such as a *window* sill, transom or rail between 150 mm and 760 mm above the floor is deemed to facilitate climbing.

Section 8 contains the glazing assembly provisions for glass barriers and

11.3.5 Handrails

(1) Handrails to a stairway or ramp must—

(a) be located along at least one side of the stairway *flight* or ramp; and

(b) be located along the full length of the stairway *flight* or ramp, except in the case where a handrail is associated with a barrier the handrail may terminate where the barrier terminates; and

(c) have the top surface of the handrail not less than 865 mm vertically above the nosings of the stair treads or the floor surface of the ramp (see Figure 11.3.4b); and

(d) be continuous and have no obstruction on or above them that will tend to break a handhold, except for newel posts, ball type stanchions, or the like.

(2) The requirements of (1) do not apply to—

(a) a stairway or ramp providing a change in elevation of less than 1 m; or

(b) a *landing*; or

(c) a *winder* where a newel post is installed to provide a handhold.

Explanatory information

(a) 11.3.5 addresses requirements regarding location, height and extent of handrails. Where a barrier and handrail are installed together, 11.3.5 is to be read in conjunction with 11.3.3¹⁷, 11.3.4¹⁸ and 11.3.6¹⁹.

(b) A handrail is *required* on at least one side of the stairway *flight* or ramp. The top rail of a barrier may be suitable as a handrail if it meets 11.3.5 and is able to be grasped by hand to provide support to the person using the stairway or ramp.

(c) 11.3.5(1)(b) requires a continuous handrail which must extend the full length of the stairway *flight* or ramp except where the handrail is associated with the barrier, in which case the handrail can terminate where the barrier is allowed to terminate. This allows for the barriers to geometric stairways such as elliptical, spiral, circular or curved stairways to finish a few treads from the bottom of the stairway.

(d) 11.3.5(1)(c) requires a minimum handrail height of 865 mm. This height provides comfort, stability, support and assistance for most users.

(e) 11.3.5(2) outlines where a handrail need not be provided, this includes—

(i) where a stairway or ramp is providing a change in elevation less than 1 m; or

(ii) a *landing* for a stairway or ramp; or

(iii) a *winder* in a stairway if a newel post is installed to provide a handhold.

