

PROPOSED SINGLE STOREY DWELLING
#26,Octans Street,Austral

PARAGON

Paragon Building Certifiers Pty Ltd

RBC00045

Registered Certifier


APPROVED

Reference: 260477/01

Date: 20/08/2026



Page No	Title
1	Coverpage
2	Safety in Design Notes
3	Building Specification
4	Building Specification
5	Basix Notes
6	Cut and Fill Plan
7	Site Plan
8	Ground Floor Plan
9	Roof Plan
10	Elevation
11	Side Elevation
12	Section
13	Door Schedule & SOF
14	Window Schedule
15	Landscape Plan
16	Sediment Control Plan
17	GFA Calculation
18	Slab Plan
19	Floor Finish

SAFETY IN DESIGN NOTES: THESE NOTES MUST BE READ AND UNDERSTOOD BY ALL INVOLVED IN THE PROJECT. THIS INCLUDES (BUT IS NOT EXCLUDED TO): OWNER, BUILDER, SUB-CONTRACTORS, CONSULTANTS, RENOVATORS, OPERATORS, MAINTAINORS, DEMOLISHERS.				
BUILDING SPECIFICATIONS:				
National Construction Code - Volume 2 Amendment 2 - Building Code of Australia 2022 & Housing Provisions Standard 2022				
1. FALLS, SLIPS, TRIPS a) WORKING AT HEIGHTS DURING CONSTRUCTION Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than 2 m. However, construction of this building will require workers to be working at heights where a fall in excess of 2m is possible and injury is likely to result from such a fall. The builder should provide a suitable barrier wherever a person is required to work in a situation where falling more than 2m is a possibility. DURING MAINTENANCE For houses or other low-rise buildings where scaffolding is appropriate: Cleaning and maintenance of windows, walls, roof or other components of this building will require persons to be situated where a fall from a height in excess of 2m is possible. Where this type of activity is required, scaffolding, ladders or trestles should be used in accordance with relevant codes of practice, regulations or legislation. FLOOR FINISHES BY OWNER b) SLIPPERY OR UNEVEN SURFACES Designer has not been involved in the selection of surface finishes, the owner is responsible for the selection of surface finishes in the pedestrian trafficable areas of this building. Surfaces should be selected in accordance with AS HB 197:1999 and AS/NZ 4586:2004. c) STEPS, LOOSE OBJECTS AND UNEVEN SURFACES Due to design restrictions for this building, steps and/or ramps are included in the building which may be a hazard to the workers carrying objects or otherwise occupied. Steps should be clearly marked with both visual and tactile warning during construction, maintenance, demolition and at all times when the building operates as a workplace. Building owners and occupiers should monitor the pedestrian access ways and in particular access to areas where maintenance is routinely carried out to ensure that surfaces have not moved or cracked so that they become uneven and present a trip hazard. Spills, loose material, stray objects or any other matter that may cause a slip or trip hazard. Spills, loose material, stray objects or any other matter that may cause a slip or trip hazard should be cleaned or removed from access ways. Contractors should be required to maintain a tidy work site during construction, maintenance or demolition to reduce the risk of trips and falls in the workplace. Materials for construction or maintenance should be stored in designated areas away from access ways and work areas.	4. SERVICES Rupture of services during excavation or other activity creates a variety of risks including release of hazardous materials. Existing services are located on and around this site. Where known, these are identified on the plans but the exact location and extent of services may vary from that indicated. Services should be located using an appropriate excavation practice should be used and, where necessary, specialist contractors should be used. LOCATIONS WITH UNDERGROUND POWER: Underground power lines MAY be located in or around this site. All underground power lines must be disconnected or carefully located and adequate warning signs used prior to any construction, maintenance or demolition commencing. LOCATIONS WITH OVERHEAD POWER LINES: Overhead power lines MAY be near or on this site. These pose a risk of electrocution if struck or approached by lifting devices or the plant and persons working above ground level. Where there is a danger of this occurring, power lines should be, where practical, disconnected or relocated. Where this is not practical adequate warning in the form of bright colored tape or signage should be used or a protective barrier provided. 5. MANUAL TASKS Components within the design with a mass excess of 45kg should be lifted by two or more workers or by mechanical lifting device. Where this is not practical, suppliers and fabricators should be required to limit the component mass. All material packaging, building and maintenance components should clearly show the total mass of packages and where practical all items should be stored on site in a way which minimises bending before lifting. Advice should be provided on safe lifting methods in all areas where lifting may occur. Construction, maintenance and demolition of this building will require the use of portable tools and equipment. These should be fully maintained in accordance with manufacturer's specifications and not used where faulty or (in the case of electrical equipment) not carrying a current electrical safety tag. All safety guards or devices should be regularly checked and Personal Protective Equipment should be used in accordance with manufacturer's specifications. 6. CONFINED SPACES EXCAVATION Construction of this building and some maintenance on this building will require excavation and installation of items within excavations. Where practical, installation should be carried out using methods which do not require workers to enter the excavation. Where this is not practical adequate support for the excavated area should be provided to prevent collapse. Warning signs and barriers to prevent accidental or unauthorised access to all excavations should be provided. ENCLOSED SPACES For buildings with enclosed spaces where maintenance or other access may be required. Enclosed spaces within this building may present a risk to persons entering for construction, maintenance or any other purpose. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the life of the building. Where workers are required to enter enclosed spaces, air testing equipment and Personal Protective Equipment should be provided. SMALL SPACES For buildings with small spaces where maintenance or other access may be required: Some small spaces within this building will require access by construction or maintenance workers. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the life of the building. Where workers are required to enter small spaces they should be scheduled so that access is for short periods. Manual lifting and other manual activity should be restricted in small spaces. 7. HAZARDOUS SUBSTANCES ASBESTOS For alterations to a building constructed prior to 1990- It may contain asbestos 1986- It is likely to contain asbestos either in cladding material or in fire retardant insulation material. In either case, the builder should check and, if necessary, take appropriate action before demolishing, cutting, sanding, drilling or otherwise disturbing the existing structure. POWDERED MATERIALS Many materials used in the construction of this building can cause harm if inhaled in powdered form. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective Equipment including protection against inhalation while using powdered material or when sanding, drilling, cutting or otherwise disturbing or creating powdered material. TREATED TIMBER The design of this building may include provision for the inclusion of treated timber within the structure. Dust or fumes from this material can be harmful. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective Equipment including protection against inhalation of harmful materials when sanding, drilling, cutting or using treated timber in any way that may cause harmful material to be released. Do not burn treated timber. VOLATILE ORGANIC COMPOUNDS Many types of glue, solvents, spray packs, paints, varnishes and some cleaning materials and disinfectants have dangerous emissions. Areas where these are used should be kept well ventilated while the material is being used and for a period after installation. Personal Protective Equipment may also be required. The manufacturer's recommendations for use must be carefully considered at all times.	SYNTHETIC MINERAL FIBRE Fibreglass, rockwool, ceramic and other material used for thermal or sound insulation may contain synthetic mineral fibre which may be harmful if inhaled or if it comes in contact with skin, eyes or other sensitive parts of the body. PPE including protection against inhalation of harmful materials should be used when installing, removing or working near bulk insulation material. TIMBER FLOORS This building may contain timber floors which have an applied finish. Areas where finishes are applied should be kept well ventilated during sanding and application and for a period after installation. PPE may also be required. The manufacturer's recommendations for use must be carefully considered at all times. 8. PUBLIC ACCESS Public access to construction and demolition sites and to areas under maintenance causes risk to workers and public. Warning signs and secure barriers to unauthorised access should be provided. Where electrical installations, excavations, plant or loose materials are present they should be secured when not fully supervised. 9. OTHER HIGH RISK ACTIVITY All electrical work should be carried out in accordance with the code of Practice: Managing Electrical risks at the Workplace, AS/NZ 30112 and all licensing requirements. All work using plant should be carried out in accordance with Code of Practice: Managing risks of Plant at the workplace. All work should be carried out in accordance with Code of Practice: Managing Noise and Preventing Hearing Loss at Work. Due to the history of serious incidents it is recommended that particular care be exercised when undertaking work involving steel construction and concrete placement. All the above applies. SITE PREPARATION - PART 3.1 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. EARTHWORKS - TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979 AND DEVELOPMENT CONSENT CONDITIONS - PART 3.2 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 4678:2002 - EARTH-RETAINING STRUCTURES DRAINAGE - PART 3.3 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING ROVISIONS STANDARD 2022. - AS/NZS 3500.1:2021 - PLUMBING & DRAINAGE - WATER SERVICES - AS/NZS 3500.2:2021 - PLUMBING & DRAINAGE - SANITARY PLUMBING & DRAINAGE - AS/NZS 3500.3:2021 - PLUMBING & DRAINAGE STORMWATER DRAINAGE - AS/NZS 3500.4:2021 - PLUMBING & DRAINAGE - HEATED WATER SERVICES STRUCTURAL WORK - Part 2.2 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 4100-2020- STEEL STRUCTURES CODES - AS/NZS 1170.0-2002 – GENERAL PRINCIPLES - AS/NZS 1170.1-2002 – PARTS 1 PERMANENT, IMPOSED AND OTHER ACTIONS - AS/NZS 1170.2-2021 – PART 2 WIND ACTIONS - AS 3700-2018- SAA MASONRY CODE - AS 1684.3-2021- RESIDENTIAL TIMBER FRAMED CONSTRUCTION FOOTINGS & SLABS - PART 4 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 2159:2009 - PILING - DESIGN & INSTALLATION - AS 2870:2011 - RESIDENTIAL SLABS & FOOTINGS - AS 3600:2018 - CONCRETE STRUCTURES MASONRY - PART 5 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 3700:2018 - MASONRY STRUCTURES FRAMING - PART 6 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 1684.2:2021 - RESIDENTIAL TIMBER- FRAMED CONSTRUCTION - NON- CYCLONIC AREAS - AS 1720.1:2010 - TIMBER STRUCTURES - DESIGN METHODS - AS 4100:2020 - STEEL STRUCTURES - AS 3660.1-2014 – TERMITE MANAGEMENT SYSTEM ROOF & WALL CLADDING - PART 7 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 1273:1991 - UNPLASTICIZED PVC (UPVC) DOWNPIPES & FITTINGS FOR RAINWATER - AS 1562.1:2018 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - METAL - AS/NZS 1562.3:2006 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - PLASTIC - AS 2049:2002 - ROOF TILES - AS 2050:2018 - INSTALLATION OF ROOF TILES - AS 4285:2019 – ROOFLIGHTS GLAZING - PART 8 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 1288:2021 - GLASS IN BUILDINGS - SELECTION & INSTALLATION - AS 2047:2014 - WINDOWS & EXTERNAL GLAZED DOORS IN BUILDINGS - AS/NZS 2208:1996 - SAFETY GLAZING MATERIALS IN BUILDINGS	FIRE SAFETY - PART 9 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 3786:2014 - SMOKE ALARMS USING SCATTERED LIGHT, TRANSMITTED LIGHT OR IONIZATION HEALTH & AMENITY - PART 10 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS/NZS ISO 717.1:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - AIRBORNE SOUND INSULATION - AS ISO 717.2:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - IMPACT SOUND INSULATION - AS 1668.2:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - MECHANICAL VENTILATION IN BUILDINGS - AS 1668.4:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - NATURAL VENTILATION OF BUILDINGS - AS/NZS 1680.0:2009 - INTERIOR LIGHTING - SAFE MOVEMENT - AS 3740:2021 - WATERPROOFING OF DOMESTIC WET AREAS - AS 3000-2018 – ELECTRICAL INSTALLATION - BCA Part 10.8.1, AS4200.1 & AS4200.2 – PLIABLE BUILDING MEMBRANE INSTALLED. WATERPROOFING - NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022 - AS 3740-2021– WATERPROOFING TO WET AREA - AS 4654-2012 – EXTERNAL WET AREAS SAFE MOVEMENT & ACCESS - PART 11 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 1428.1:2009 - DESIGN FOR ACCESS & MOBILITY - GENERAL REQUIREMENTS FOR ACCESS - NEW BUILDING WORK - AS 1657:2018 - FIXED PLATFORMS, WALKWAYS, STAIRWAYS & LADDERS - DESIGN, CONSTRUCTION & INSTALLATION HANDRAILS & BALUSTRADE - PART 11.3.3 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - PART 11.3.4 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - PART 11.3.5 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. - AS 1170.1-2002 – BALUSTRADE INSTALLATION PROTECTION OF OPENABLE WINDOW PART 11.3.7 AND 11.3.8 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022. ENERGY EFFICIENCY - PART 13 OF THE NCC VOLUME 2 BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022 & BASIX CERTIFICATE. MECHANICAL VENTILATION - EXHAUST FROM A BATHROOM, SANITARY COMPARTMENT TO DISCHARGE DIRECTLY TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 25L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM2. THIS EXHAUST SYSTEM MUST BE INTERLOCKED WITH LIGHT SWITCH AND INCLUDE RUN-ON TIMER SO THAT THE EXHAUST SYSTEM CONTINUES TO OPERATE FOR 10 MINUTES AFTER THE LIGHT SWITCH IS OFF. - ANY INSTALLED - KITCHEN RANGEHOOD EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM2. - LAUNDRY EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM2.	

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 **ABN**
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING : Safety in Design Notes
CLIENT : Sandstone Constructions
PROJECT : PROPOSED SINGLE STOREY DWELLING #26, Octans Street, Austral Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE:	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 2	

TERMITE SHEET

-TERMITE SHEET EXTENDS THROUGH THE ENTIRE MASONRY LEAF AND IS
VISIBLE AT THE FINISHED FACE OF THE WALL.

Figure 10.2.29 Typical membrane termination at drainage outlet







Figure 10.2.24 Typical bathroom door details for whole bathroom waterproofing



BASIN & BATHTUB:

Figure 10.2.5 Bath and vessel abutting wall — areas to be protected



ENCLOSED SHOWER AREA

Figure 10.2.17 Typical hobless construction






Figure 10.2.16: Typical hob construction — internal membrane



Typical detail of HOB Construction as per BCA ABCB Housing Provisions Part 10.2.16

Figure 10.2.2 Extent of treatment for shower areas — concrete compressed fibre-cement and fibre-cement sheet floors



(a) Enclosed shower

Typical detail of enclosed shower as per BCA ABCB Housing Provisions Part 10.2.2

10.2.12 Construction of wet area floors — falls


Where a floor waste is installed—

- (a) the minimum continuous fall of a floor plane to the waste must be 1:80; and
- (b) the maximum continuous fall of a floor plane to the waste must be 1:50.

Floor Waste

app.buildingtools.co

tools



Specified 21 Sep 2024 NCC 2022 • Tools v15 <https://buildingtools.co/2u8vG6>

You may not reproduce in any form, any part of this document except as expressly provided for in these Terms and Conditions



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING : **Building Specification**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE:
PAGE SIZE A3
DATE : 16-08-2026
APPLICATION : CDC
PAGE NO: 3
PROJECT NO. 2606 928
ISSUE A

TERMITE SHEET


- TERMITE SHEET EXTENDS THROUGH THE ENTIRE MASONRY LEAF AND IS VISIBLE AT THE FINISHED FACE OF THE WALL.



FIGURE 5.5 (in part) TYPICAL SHEET INSTALLATION TO EXTERNAL WALL WITH CONCRETE FLOOR SLAB

DPC FOR BRICKS

DAMP-PROOF COURSE (DPC) TO EXTENDS THROUGH THE ENTIRE MASONRY LEAF AND NEED TO BE VISIBLE AT THE FINISHED FACE OF THE WALL FROM OUTSIDE



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.
All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.
All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

Figure 10.8.3 (explanatory) Example of roof space with low level ventilation





Figure Notes

- (1) Minimum 20 mm gap maintained between insulation and sarking.
(2) Eave ventilation opening in accordance with Table 10.8.3.



10.8.3


Ventilation of roof spaces

[2019: 3.8.7.4]

- (1) In *climate zones* 6, 7 and 8, a roof must have a roof space that—
- (a) is located—
- (i) immediately above the *primary insulation layer*; or
- (ii) immediately above sarking with a *vapour permeance* of not less than 1.14 µg/N.s, which is immediately above the *primary insulation layer*; or
- (iii) immediately above ceiling insulation that meets the requirements of 13.2.3(3) and 13.2.3(4); and
- (b) has a height of not less than 20 mm; and
- (c) is either—
- (i) ventilated to *outdoor air* through evenly distributed openings in accordance with Table 10.8.3; or
- (ii) located immediately underneath the roof tiles of an unsarked tiled roof.
- (2) The requirements of (1) do not apply to a—
- (a) concrete roof; or
- (b) roof that is made of structural insulated panels; or
- (c) roof that is subject to Bushfire Attack Level FZ requirements in accordance with AS 3959.

Table 10.8.3: Roof space ventilation requirements

Roof pitch	Ventilation openings
< 10°	25,000 mm²/m provided at each of two opposing ends
≥ 10° and < 15°	25,000 mm²/m provided at the eaves and 5,000 mm²/m at high level
≥ 15° and < 75°	7,000 mm²/m provided at the eaves and 5,000 mm²/m at high level, plus an additional 18,000 mm²/m at the eaves if the roof has a cathedral ceiling



DRAWING : **Building Specification**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE:
PAGE SIZE A3
DATE : **16-08-2026**
APPLICATION : CDC
PAGE NO: 4

PROJECT NO. **2606 928**
ISSUE **A**

BASIX™ Certificate

Building Sustainability Index
www.planningportal.nsw.gov.au/development-and-assessment/basix

Single Dwelling

Certificate number: 1860269S_02

This certificate confirms that the proposed development will meet the NSW government's requirements for sustainability, if it is built in accordance with the commitments set out below. Terms used in this certificate, or in the commitments, have the meaning given by the document entitled "BASIX Definitions" dated 10/09/2020 published by the Department. This document is available at www.planningportal.nsw.gov.au/definitions

Secretary
Date of issue: Saturday, 15 August 2026
To be valid, this certificate must be submitted with a development application or lodged with a complying development certificate application within 3 months of the date of issue.





Paragon Building Certifiers Pty Ltd
RBC00045
Registered Certifier
APPROVED
Reference: 260477/01
Date: 20/08/2026

Basix-Commitments

/for details: See the Basix certificate/

Alternative water

- The applicant must install a rainwater tank of at least 2000 litres.
The rainwater tank to collect rain runoff from at least 180 m2 of the roof
The applicant must connect the rainwater tank to:
- all toilets in the development
 - the cold water tap that supplies each clothes washer
 - at least one outdoor tap in the development

Fixtures

- Shower heads 4 star (>6.0 but <= 7.5 L/min)
- Toilets.....3 star
- Kitchen tap.....3 star
- Basin Taps.....3 star

Hot Water System: gas instantaneous with a performance of 6.0 stars /or a system with a higher energy rating/

Heating/Cooling: In at least 1 living area and 1 bedroom: 1-phase Air-conditioning; Energy rating: 3 star (Average Zoned)

Ventilation

- At least 1 Bathroom: individual fan, ducted to façade or roof; Operation control: manual switch on/off
 - Kitchen: individual fan, ducted to façade or roof; Operation control: manual switch on/off
 - Laundry: individual fan, ducted to façade or roof; Operation control: n/a

Natural lighting

- The applicant must install a window and/or skylight in the kitchen of the dwelling for natural lighting.
- The applicant must install a window and/or skylight in 1 bathroom(s)/toilet(s) in the development for natural lighting.

Artificial lighting fluorescent or (LED)/DEDICATED/:

- The Applicant must ensure that a minimum of 80% of light fixtures are fitted with fluorescent, compact fluorescent, or light-emitting-diode(LED) lamps.

OTHER

- The applicant must install a gas cook top & electric oven in the kitchen of the dwelling.
- The applicant must install a fixed outdoor clothes drying line as part of the development.



**BEFORE
YOU DIG**
www.byda.com.au
Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



**INNOVATIVE
ECO DESIGNS**
Your Home Your Style

37604191460 **ABN**
(02) 8710 3852

SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au

www.iedesigns.com.au



**ACCREDITED
BUILDING DESIGNER**

A	16-08-2026	Issue for CDC

DRAWING : Basix Notes
CLIENT : Sandstone Constructions
PROJECT : PROPOSED SINGLE STOREY DWELLING #26,Octans Street,Austral Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE:	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 5	

Cut and Fill is only under Slab.
Cut and Fill on the site is minimal, Hence does not
required Retaining wall.

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260477/01

Date: 20/08/2026



Cut and Fill Plan
1:200



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC


DRAWING : **Cut and Fill Plan**

CLIENT : **Sandstone Constructions**

PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE: 1:200	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 6	

Gross Floor Area		
No	Name	Area SQM
01	Ground floor	146.19
		146.19 m ²



Date: 20/08/2026



DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE: 1:200	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO : 7	

Total Built up			
No.	Name	Area SQM	Area SQ
01	Ground floor	160.11	17.23
02	Garage	19.63	2.11
03	Porch	1.61	0.17
04	Alressco	8.65	0.93
		190.00 m ²	20.44

External Walls with vapour permeable membrane as per manufacturer detail.

(ME)-All exhaust from sanitary compartment to discharge directly to outside and exhaust system must be in interlocked with light switch and include run -on timer so the exhaust system continues to operate for 10 minutes after the light switch is off.

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260477/01

Date: 20/08/2026



Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.


All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC
---	------------	---------------



DRAWING : **Ground Floor Plan**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE: 1:100
PAGE SIZE: A3
DATE : 16-08-2026
APPLICATION : CDC
PAGE NO: 8
PROJECT NO. 2606 928
ISSUE **A**

Riser and going dimensions (mm)

Stair type	Riser (R)		Going (G)		Slope relationship (2R+G)	
	Max	Min	Max	Min	Max	Min
Stairs	190	115	355	240	700	550




Figure Notes
1. Min 20 mm gap maintained between insulation and sarking
2. Eave ventilation opening in accordance with Table 10.8.3.





Figure 7.2.3: Minimum pitch requirements for metal roofing profiles



1. Roof
1:100




NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.
All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au





A	16-08-2026	Issue for CDC



DRAWING : **Roof Plan**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE: 1:100	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 9	

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING : **Elevation**

CLIENT : **Sandstone Constructions**



PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE: 1:100
PAGE SIZE A3

DATE : **16-08-2026**
APPLICATION : CDC
PAGE NO: 10

PROJECT NO. **2606 928**
ISSUE **A**

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au




A	16-08-2026	Issue for CDC

DRAWING : **Side Elevation**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278


DRAWN BY:
M.T
SCALE:
1:100
PAGE SIZE
A3

DATE :
16-08-2026
APPLICATION :
CDC
PAGE NO:
11

PROJECT NO.
2606 928
ISSUE
A



A Section
1:100



07 Fire Rated Wall
1:50



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING :Section

CLIENT : Sandstone Constructions

PROJECT : PROPOSED SINGLE STOREY DWELLING

#26, Octans Street, Austral

Lot- 234 D.P 1285278

DRAWN BY:
M.T

SCALE:
1:100, 1:50

PAGE SIZE
A3

DATE :
16-08-2026

APPLICATION :
CDC

PAGE NO:
12

PROJECT NO.
2606 928

ISSUE
A

Door Schedule								
ID	D1	D2	D3	D3/L./up	D4	OPEN	OPEN	
Wallhole Dimensions(W x H)	980×2,370	880×2,410	780×2,410	780×2,410	980×2,410	1,500×2,400	900×2,400	
Leaf Dimensions	920×2,340	820×2,340	720×2,340	720×2,340	920×2,340	---	---	
Elevation								
Total Glazed Area SQM	0.00	0.00	0.00	0.00	0.00	---	---	0.00
Position	Exterior	Interior	Interior	Interior	Interior	Interior	Interior	
Quantity	1	4	2	1	1	1	2	12

Aluminium Door Schedule				
ID	D5	Panel Lift	SD6	
Frame Dimensions (W X H)	850×2,410	2,520×2,400	2,410×2,400	
Elevation				
Total Glazed Area SQM	1.21	0.63	3.98	5.82
Glazed Area SQM	---	---	---	0.00
Position	Exterior	Exterior	Exterior	
Quantity	1	1	1	3

SCHEDULE OF FINISHES		
Element	SPECIFICATION	COLOUR
Walls	PGH Brick - Thunder	
Render Finish Facade	Beige Royal Half	
Feature Wall	Wallaby	
Roof	Colorbond - Wallaby	
Gutter	Wallaby	
Fascia	Surfmist	
Window	Monument	
Garage Door	Surfmist	
Copping	Surfmist	

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au




A	16-08-2026	Issue for CDC

DRAWING : **Door Schedule & SOF**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE:
PAGE SIZE A3
DATE : **16-08-2026**
APPLICATION : CDC
PAGE NO: 13
PROJECT NO. **2606 928**
ISSUE **A**

Window Schedule								
ID	W1/C	W2/C	W3	W4	W5	W6	W7	W8
Frame Dimensions	810×2,100	810×2,100	1,210×2,100	850×1,800	1,210×500	2,410×1,800	2,410×1,800	610×1,800
Elevation								
Glass	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear
Glazed Area SQM	0.00	0.00	1.99	0.96	0.29	3.32	3.32	0.74
Quantity	1	1	1	1	1	1	1	1

Window Schedule							
ID	W9	W10	W11	W12	W13	W14	
Frame Dimensions	610×1,800	2,410×600	1,810×1,200	1,810×1,200	1,810×1,200	1,810×900	
Elevation							
Glass	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	Glass - Clear	
Glazed Area SQM	0.74	1.16	1.56	1.56	1.56	1.09	18.29
Quantity	1	1	1	1	1	1	14

NOTE:
- TO BE CHECKED AND CONFIRMED BY BUILDER ON SITE BEFORE PLACING ORDER.
-FALL PREVENTION FROM WINDOWS
-WINDOWS TO BE MANUFACTURED IN ACCORDANCE WITH REQUIREMENTS OF NCC 2022 vol. 2 part 11.3.7
1- If Opening withing 1700mm above the floor; and climable elements between 150 and 750 mM above the floor, opening must be permanently restricted to 125mm; or fitted withn a non-removable robust screen.
2-If opening between 865 and 1700mm above the floor; and no climable elements between 150 and 760mm bove the floor, opening must be restricted to 125mm; or fitted with a removable robust screen.
3- If opening between 865 of the floor; and climable elements between 150 and 760mm above the floor;or fitted with a non-removable robust screen.
4-If no opening within 1700mm of the floor. No restrictions apply.

Part 11.3.7 Protection of openable windows - bedrooms
(1) A window opening in a bedroom must be provided with protection, where the floor below the window is 2 m or more above the surface beneath.
(2) Where the lowest level of the window opening covered by (1) is less than 1.7 m above the floor, the window opening must comply with the following:
(a) The openable portion of the window must be protected with-
(i) a device capable of restricting the window opening; or
(ii) a screen with secure fittings.
(b) A device or screen required by (a) must-
(i) not permit a 125 mm sphere to pass through the window opening or screen; and
(ii) resist an outward horizontal action of 250 N against the-
(A) window restrained by a device; or
(B) screen protecting the opening; and
(iii) have a child resistant release mechanism if the screen or device is able to be removed, unlocked or overridden.
(3) Where a device or screen provided in accordance with (2)(a) is able to be removed, unlocked or overridden, a barrier with a height not less than 865 mm above the floor is required to the openable window in addition to window protection.
(4) A barrier covered by (3) must not-
(a) permit a 125 mm sphere to pass through it; and
(b) have any horizontal or near horizontal elements between 150 mm and 760 mm above the floor that facilitate climbing.
11.3.8 Protection of openable windows - rooms other than bedrooms
(1) A window opening in a room other than a bedroom must be provided with protection where the floor below the window is 4 m or more above the surface beneath.
(2) The openable part of the window covered by (a) must be protected with a barrier with a height of not less than 865mm above the floor.
(3) A barrier required by (b) must not-
(a) permit a 125 mm sphere to pass through it; and
(b) have any horizontal or near horizontal elements between 150 mm and 760 mm above the floor that facilitate climbing.

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.
All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.
All documents here within are subject to Australian Copyright Laws.



37604191460 **ABN**
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW,2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING : **Window Schedule**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26,Octans Street,Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE:	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 14	



Paragon Building Certifiers Pty Ltd

RBC00045

Registered Certifier

APPROVED

Reference: 260477/01

Date: 20/08/2026

All Landscape to be done by owner.

LANDSCAPE SCHEDULE

Refrence Image	ABB	NAME	TYPE	HEIGHT	POT. SIZE	QUA.
	(ML)	MELALEUCA LINARIIFOLIA	Tree	8-15m	75LT.	1
	(PC)	PYRUS CALLERYANA (CHANTICLEER)	Tree	5m	45LT.	1
	(BS)	BANKSIA SPINULOSA	Shrub	1-3m	300mm	10
		BUFFALO GRASS	Grass			
		AGGREGATE				

LEGEND

Ref.img

Name



Tree



Shrub



Grass (Landscape Area)




Aggregate

GE:- GARDEN EDGING AS SELECTED
TREATED PINE SPLITS 90 MM 2.4 MT LENGTH,
FASTENED TO HARWOOD STAKES, MINIMUM DEPTH
IN GROUND OF 300 MM WITH GALVANISED TREATED
PINE SCREWS(SIZE 75 MM X 8G)

LAWN:- BUFFALO WITH SHIRLEYS NO.17 FERTILISER
ALL PLANTS TO HAVE 35 MM OF BARK CHIP MULCH
SPREAD OVER TOP SOIL TURF TO BE WATERED
MORNING AND EVENING FOR A PERIOD OF TWO
WEEKS OR AD NECESSARY.

As per section 88b restriction no.5, Roof other than clay tiles, cement tiles, slate or non reflective surface corrugated iron.



Landscape Plan
1:200



Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.


All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC
---	------------	---------------



DRAWING : **Landscape Plan**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE: 1:200
PAGE SIZE A3
DATE : **16-08-2026**
APPLICATION : CDC
PAGE NO: 15
PROJECT NO. **2606 928**
ISSUE **A**



Paragon Building Certifiers Pty Ltd

RBC00045

Registered Certifier


APPROVED

Reference: 260677/01

Date: 20/08/2026

Ground floor

A: 146.19 m²



GFA - Ground Floor

1:100



Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC

DRAWING : **GFA Calculation**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE: 1:100	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 17	

- NOTE
- CONCRETE SLAB AS PER ENGINEERS DETAILS
 - CONCRETE FOOTINGS AS PER ENGINEER'S DETAILS
 - EDGE BEAM DETAILS AS PER ENGINEER'S DETAILS
 - ALL BRICK REBATES AS PER ENGINEER'S DETAILS

PARAGON

Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260477/01

Date: 20/08/2026



NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.


All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A	16-08-2026	Issue for CDC



DRAWING : Slab Plan

CLIENT : Sandstone Constructions

PROJECT : PROPOSED SINGLE STOREY DWELLING

#26, Octans Street, Austral

Lot- 234 D.P 1285278

DRAWN BY: M.T	DATE : 16-08-2026	PROJECT NO. 2606 928
SCALE: 1:100	APPLICATION : CDC	ISSUE A
PAGE SIZE A3	PAGE NO: 18	



Paragon Building Certifiers Pty Ltd


RBC00045

Registered Certifier

APPROVED

Reference: 260477/01

Date: 20/08/2026



Floor Finish (Ground Floor)
1:100



Zero Damage - Zero Harm

NOTE
The Builder shall check all dimensions and levels on site prior to construction. Notify any errors, discrepancies or omissions to the building designer. Refer to written dimensions only. Do not scale drawings. Drawings shall not be used for construction purposes until issued for construction. This drawing reflects a design by Innovative Eco Designs and is to be used only for work when authorised in writing by Innovative Eco Designs.

All boundaries and contours are subject to survey drawing. All levels to Australian Height Data. It is the contractors responsibility to confirm all measurements on site and locations of any services prior to work on site.

All documents here within are subject to Australian Copyright Laws.



37604191460 ABN
(02) 8710 3852
SUITE 7, 4-10 SELEMS PDE
REVESBY, NSW, 2212
design@iedesigns.com.au
www.iedesigns.com.au



A 16-08-2026 Issue for CDC

DRAWING : **Floor Finish**
CLIENT : **Sandstone Constructions**
PROJECT : **PROPOSED SINGLE STOREY DWELLING**
#26, Octans Street, Austral
Lot- 234 D.P 1285278

DRAWN BY: M.T
SCALE: 1:100
PAGE SIZE A3
DATE : **16-08-2026**
APPLICATION : CDC
PAGE NO: 19

PROJECT NO. **2606 928**
ISSUE **A**

LEGEND	
Ref.img	Name
	Indoor Tiles
	Outdoor Tiles
	Concrete finish
	Tile for wet area
	Timber finish

BUILDING SPECIFICATIONS

National Construction Code – Volume 2, Amendment 1 – Building Code of Australia 2022 & Housing Provisions Standard 2022

SITE PREPARATION

- PART 3.1 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022

EARTHWORKS

- TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979 AND DEVELOPMENT CONSENT CONDITIONS
- PART 3.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 4678:2002 - EARTH-RETAINING STRUCTURES

DRAINAGE

- PART 3.3 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS/NZS 3500.1:2021 - PLUMBING & DRAINAGE - WATER SERVICES
- AS/NZS 3500.2:2021 - PLUMBING & DRAINAGE - SANITARY PLUMBING & DRAINAGE
- AS/NZS 3500.3:2021 - PLUMBING & DRAINAGE - STORMWATER DRAINAGE
- AS/NZS 3500.4:2021 - PLUMBING & DRAINAGE - HEATED WATER SERVICES

STRUCTURAL WORK

- Part 2.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 4100-2020– STEEL STRUCTURES CODES
- AS/NZS 1170.0-2002 – GENERAL PRINCIPLES
- AS/NZS 1170.1-2002 – PARTS 1 PERMANENT, IMPOSED AND OTHER ACTIONS
- AS/NZS 1170.2-2021 – PART 2 WIND ACTIONS
- AS 3700-2018– SAA MASONRY CODE
- AS 1684.3-2021- RESIDENTIAL TIMBER FRAMED CONSTRUCTION

FOOTINGS & SLABS

- PART 4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 2159:2009 - PILING - DESIGN & INSTALLATION
- AS 2870:2011 - RESIDENTIAL SLABS & FOOTINGS
- AS 3600:2018 - CONCRETE STRUCTURES

MASONRY

- PART 5 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 3700:2018 - MASONRY STRUCTURES

FRAMING

- PART 6 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1684.2:2021 - RESIDENTIAL TIMBER-FRAMED CONSTRUCTION - NON- CYCLONIC AREAS
- AS 1720.1:2010 - TIMBER STRUCTURES - DESIGN METHODS
- AS 4100:2020 - STEEL STRUCTURES
- AS 3660.1-2014 – TERMITE MANAGEMENT SYSTEM

ROOF & WALL CLADDING

- PART 7 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1273:1991 - UNPLASTICIZED PVC (UPVC) DOWNPIPES & FITTINGS FOR RAINWATER
- AS 1562.1:2018 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - METAL
- AS/NZS 1562.3:2006 - DESIGN & INSTALLATION OF SHEET ROOF & WALL CLADDING - PLASTIC
- AS 2049:2002 - ROOF TILES
- AS 2050:2018 - INSTALLATION OF ROOF TILES
- AS 4285:2019 – ROOFLIGHTS

GLAZING

- PART 8 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1288:2021 - GLASS IN BUILDINGS - SELECTION & INSTALLATION
- AS 2047:2014 - WINDOWS & EXTERNAL GLAZED DOORS IN BUILDINGS
- AS/NZS 2208:1996 - SAFETY GLAZING MATERIALS IN BUILDINGS

FIRE SAFETY

- PART 9 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 3786:2014 - SMOKE ALARMS USING SCATTERED LIGHT, TRANSMITTED LIGHT OR IONIZATION

HEALTH & AMENITY

- PART 10 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS/NZS ISO 717.1:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - AIRBORNE SOUND INSULATION
- AS ISO 717.2:2004 - ACOUSTICS - RATING OF SOUND INSULATION IN BUILDINGS & OF BUILDING ELEMENTS - IMPACT SOUND INSULATION
- AS 1668.2:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - MECHANICAL VENTILATION IN BUILDINGS
- AS 1668.4:2012 - THE USE OF VENTILATION & AIR CONDITIONING IN BUILDINGS - NATURAL VENTILATION OF BUILDINGS
- AS/NZS 1680.0:2009 - INTERIOR LIGHTING - SAFE MOVEMENT
- AS 3740:2021 - WATERPROOFING OF DOMESTIC WET AREAS
- AS 3000-2018 – ELECTRICAL INSTALLATION
- BCA Part 10.8.1, AS4200.1 & AS4200.2 – PLIABLE BUILDING MEMBRANE INSTALLED.

WATERPROOFING

- PART 10.2 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022
- AS 3740-2021– WATERPROOFING TO WET AREA
- AS 4654-2012 – EXTERNAL WET AREAS

SAFE MOVEMENT & ACCESS

- PART 11 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1428.1:2009 - DESIGN FOR ACCESS & MOBILITY – GENERAL REQUIREMENTS FOR ACCESS - NEW BUILDING WORK
- AS 1657:2018 - FIXED PLATFORMS, WALKWAYS, STAIRWAYS & LADDERS - DESIGN, CONSTRUCTION & INSTALLATION

HANDRAILS & BALUSTRADE

- PART 11.3.3 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- PART 11.3.4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- PART 11.3.5 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.
- AS 1170.1-2002 – BALUSTRADE INSTALLATION

PROTECTION OF OPENABLE WINDOW

PART 11.3.7 AND 11.3.8 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.

ENERGY EFFICIENCY

- PART 13 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022 & BASIX CERTIFICATE.

HEATING APPLIANCES, FIREPLACES, CHIMNEYS AND FLUES

- PART 12.4 OF THE NCC VOLUME 2, AMENDMENT 1 - BUILDING CODE OF AUSTRALIA 2022 & HOUSING PROVISIONS STANDARD 2022.

MECHANICAL VENTILATION

- EXHAUST FROM A BATHROOM, SANITARY COMPARTMENT TO DISCHARGE DIRECTLY TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 25L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM². THIS EXHAUST SYSTEM MUST BE INTERLOCKED WITH LIGHT SWITCH AND INCLUDE RUN-ON TIMER SO THAT THE EXHAUST SYSTEM CONTINUES TO OPERATE FOR 10 MINUTES AFTER THE LIGHT SWITCH IS OFF.
- ANY INSTALLED - KITCHEN RANGEHOOD EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM².
- LAUNDRY EXHAUST TO DISCHARGE DIRECTLY OR VIA DUCT TO OUTDOOR AIR WITH MINIMUM FLOW RATE OF 40L/S & MAKE-UP AIR VIA OPENINGS TO AN ADJACENT ROOM WITH A FREE AREA OF 14,000 MM².

