GENERAL

G1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS' DRAWINGS, SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE SUPERINTENDENT FOR DECISION BEFORE PROCEEDING WITH THE WORK.

G2. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE STRUCTURAL DRAWINGS.

G3. SETTING OUT DIMENSIONS SHOWN ON THE DRAWINGS SHALL BE VERIFIED BY THE BUILDER.

G4. DURING CONSTRUCTION THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART SHALL BE OVERSTRESSED. TEMPORARY BRACING SHALL BE PROVIDED BY THE BUILDER AS REQUIRED, EXCEPT FOR TEMPORARY WORKS DETAILED IN THESE DRAWINGS.

G5. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE SAA CODES AND THE BY-LAWS AND ORDINANCES OF THE RELEVANT BUILDING AUTHORITIES.

G6. REFER TO ARCHITECTURAL DRAWINGS FOR BRICK WALL THICKNESSES WHERE NOT MENTIONED ON THESE DRAWINGS AND FOR FALLS IN SLABS, EXTRA PACKING, WATERPROOFING MEMBRANES, CONTRACTION JOINT FILLING MATERIALS AND ALL OTHER ARCHITECTURAL FEATURES SUCH AS DRIP GROOVES, POUR BREAKS IN OFF-FORM CONCRETE, FILLETS AND THE LIKE.

G7. UNLESS NOTED OTHERWISE, ALL LEVELS ARE IN METRES AND ALL DIMENSIONS ARE IN MILLIMETRES.

G8. THE STRUCTURAL COMPONENTS DETAILED ON THESE DRAWINGS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE RELEVANT SAA CODES AND LOCAL GOVERNMENT ORDINANCES FOR THE FOLLOWING LOADINGS :-

CLASSIFICATION	LIVE LOAD (KPa)
BALCONY	2.0
RESIDENCE	1.5
CARPARK	2.5

G9. THE RELEVANT PROVISIONS OF AS.1170.4 HAVE BEEN APPLIED FOR EARTHQUAKE DESIGN.

G10. THE RELEVANT PROVISIONS OF AS 1170.2 HAVE BEEN APPLIED FOR WIND LOADS WITH THE FOLLOWING PARAMETERS.
REGION A2
BASIC WIND SPEED Vu = 45m/s
TERRAIN CATEGORY 3

REINFORCEMENT

R1. REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY. IT IS NOT NECESSARILY SHOWN IN TRUE PROJECTION.

R2. SPLICES IN THE REINFORCEMENT SHALL BE MADE ONLY IN THE POSITIONS SHOWN. THE WRITTEN APPROVAL OF THE ENGINEER SHALL BE OBTAINED FOR ANY OTHER SPLICES. WHERE THE LAP LENGTH IS NOT SHOWN IT SHALL BE SUFFICIENT TO DEVELOP THE FULL STRENGTH OF THE REINFORCEMENT.

R3. WELDING OF REINFORCEMENT WILL NOT BE PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED IN WRITING BY THE ENGINEER

R4. REINFORCEMENT SYMBOLS:-


N - DENOTES GRADE 500 NORMAL DUCTILITY DEFORMED BARS (D500N) TO AS/NZS 4671

R - DENOTES GRADE 250 NORMAL DUCTILITY ROUND BARS (R250N) TO AS/NZS 4671

SL - DENOTES GRADE 500 LOW DUCTILITY DEFORMED BAR SQUARE WELDED MESH (D500SL) TO AS/NZS 4671


RL - DENOTES GRADE 500 LOW DUCTILITY DEFORMED BAR RECTANGULAR WELDED MESH (D500RL) TO AS/NZS 4671

THE FIGURES FOLLOWING WELDED MESH SYMBOLS `SL' OR 'RL' ARE THE REFERENCE NUMBER FOR THE MESH TYPE IN ACCORDANCE WITH AS/NZS 4671



R5. ALL WELDED MESH SHALL COMPLY WITH AS/NZ 4671 AND SHALL BE SUPPLIED AS FLAT SHEETS.

TYPICAL WELDED MESH LAP:-



WELDED MESH SHALL BE LAPPED 2 TRANSVERSE WIRES PLUS 50mm. BUNDLED BARS SHALL BE TIED TOGETHER AT 30 BAR DIAMETER CENTRES WITH 3 WRAPS OF WIRE.

R6. PLACE SUFFICIENT BAR CHAIRS UNDER BOTTOM REINFORCING RODS AND TOP CROSS RODS IN SLABS TO ALLOW THEM TO BE SUPPORTED IN THEIR CORRECT POSITIONS DURING CONCRETING (NOT GREATER THAN 900mm CENTRES BOTH WAYS FOR BARS, 750mm FOR FABRIC).

R7. BAR CHAIR TYPE TO BE USED AS FOLLOWS:

EXPOSURE CLASSIFICATION	BAR CHAIR TYPE
A1, A2 & B1	PLASTIC-TIPPED WIRE OR PLASTIC
B2 & C	PLASTIC ONLY

R8. REINFORCEMENT LAYERS DENOTED THUS; (UNLESS NOTED OTHERWISE)-
TT - DENOTES TOP BARS LAID LAST IN TOP
T - DENOTES TOP BARS LAID FIRST IN TOP
B - DENOTES BOTTOM BARS LAID SECOND IN BTM
BB - DENOTES BOTTOM BARS LAID FIRST IN BTM

R9. WHERE TRANSVERSE TIE BARS ARE NOT SHOWN PROVIDE N12-300 SPLICED WHERE NECESSARY AND LAP WITH MAIN BARS 450mm, UNLESS NOTED OTHERWISE.

R10. MINIMUM LAP LENGTHS UNLESS NOTED OTHERWISE SHALL BE
500 FOR SIZE 12 BARS
600 FOR SIZE 16 BARS
900 FOR SIZE 20 BARS
1000 FOR SIZE 24 BARS
1200 FOR SIZE 28 BARS
1500 FOR SIZE 32 BARS
1800 FOR SIZE 36 BARS

BRICKWORK & BLOCKWORK

B1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS.3700.

B2. STRENGTHS OF BRICKS AND TYPE OF MORTAR SHALL BE AS FOLLOWS:-

ELEMENT	MATERIAL	CHARACTERISTIC UNCONFINED COMPRESSIVE STRENGTH (f'uc)	MORTAR TYPE C : L : S
BRICKWORK BLOCKWORK	BURNT CLAY CONCRETE	20 MPa (MIN.) 12 MPa (MIN.)	1 : 1 : 6 1 : ¼ : 3

B3. MAXIMUM DEPTH OF RAKING OF THE MORTAR JOINTS = 3mm. (UNO)

B4. BRICKWORK SUPPORTING SLABS AND BEAMS SHALL HAVE GALVANISED SLIDING JOINT STRIPS COMPRISING OF 2 GALVANISED STRIPS WITH GRAPHITE GREASE BETWEEN THEM (`SWAN' JOINT STRIPS OR EQUIVALENT).

B5. ALL BRICKWORK SUPPORTING OR SUPPORTED BY CONCRETE FLOORS SHALL BE PROVIDED WITH VERTICAL JOINTS TO MATCH ANY CONTROL JOINTS IN THE CONCRETE.

B6. NO MASONRY WALLS ARE TO BE ERECTED ON SUSPENDED SLABS OR BEAMS UNTIL ALL PROPPING HAS BEEN REMOVED.

B7. BUILDER TO PROVIDE TEMPORARY PROPPING TO ALL WALLS WHERE REQUIRED FOR STABILITY DURING CONSTRUCTION.

B8. OPENINGS FOR CLEAN-OUTS AND INSPECTIONS ARE TO BE PROVIDED AT THE BOTTOM COURSE OF EACH WALL FOR ALL CORES CONTAINING REINFORCEMENT. MORTAR PROTRUSIONS FROM ALL CORES ARE TO BE CLEANED OUT PRIOR TO PLACING REINFORCEMENT.

B9. NO CHASES OR RECESSES ARE PERMITTED IN MASONRY WITHOUT THE APPROVAL OF THE ENGINEER.

B10. BACKFILL TO RETAINING WALLS TO BE FREE DRAINING GRANULAR MATERIAL. PROVIDE SUBSOIL DRAIN OR WEEP HOLES.

B11. GALVANISED MASONRY COURSE REINFORCEMENT EQUAL TO SMORGON A.R.C. PRODUCT SHALL BE PROVIDED AT VERTICAL SPACINGS OF EVERY 6TH COURSE TO EACH LEAF AS FOLLOWS:
110mm MRH3650
140mm MRH3690
190mm MRH3614.0
230mm MRH3614.0
COURSE REINFORCEMENT SHALL BE LAPPED 300mm. ONE ADDITIONAL RUN SHALL BE PROVIDED UNDER & OVER ALL WINDOW & DOOR OPENINGS BONDED 300mm PAST THE OPENING.

B12. PROVIDE CONTROL JOINTS V.J. AT A MAXIMUM 4 METRE SPACINGS TYPICALLY & 4 METRES FROM CORNERS UNLESS NOTED OTHERWISE IN THE SPECIFICATION OR ON THESE DRAWINGS.

B13. DURABILITY

	EXTERNAL MASONRY	INTERNAL MASONRY (ABOVE DAMP PROOF COURSE AND INCLUDES INTERNAL LEAF OF CAVITY WALL)
EXPOSURE ENVIRONMENT	MODERATE	INTERIOR
MINIMUM SALT ATTACK RESISTANCE GRADE OF MASONRY UNITS (AS/NZS 4456.10)	`EXPOSURE'	`PROTECTED'
MINIMUM CLASSIFICATION OF MORTAR	M3	M2
MINIMUM DURABILITY CLASSIFICATION OF BUILT IN COMPONENTS (REINF., WALL TIES, BOLTS, MASONRY ANCHORS ETC.)	R3	R1
MINIMUM COVER TO REINFORCEMENT	30mm	5mm
WALL TIES (IN ACCORDANCE WITH AS2699.1) AND REINFORCEMENT	TO AS2699.1	TO AS2699.1
LINTELS (ETC)	GALVANISED (DUPLEX COATED) TO TABLE 3 - AS 2699.3	HOT-DIP GALVANISED TO AS 4680 (300g/m2)

FOUNDATIONS

F1. FOOTINGS HAVE BEEN DESIGNED FOR AN ALLOWABLE INTENSITY OR BEARING PRESSURE OF:

ELEMENT	STRATA	ALLOWABLE BEARING PRESSURE kPa
	SHALE	700

NOTE
GEOTECHNICAL ENGINEER TO CONFIRM FOUNDING CAPACITY OF FOUNDATIONS PRIOR TO CONCRETE BEING PLACED.
BUILDER TO ALLOW FOR GEOTECHNICAL ENGINEERING COSTS.

F2. FOOTINGS SHALL BE LOCATED CENTRALLY UNDER WALLS AND COLUMNS UNLESS NOTED OTHERWISE.

F3. SITE IS DESIGNED TO BE M_SITE AS PER AS2870.

F4. EXCAVATE FOR FOOTINGS TO THE NOMINATED SIZE AND DEPTH. FOUNDING LEVELS ARE PROVISIONAL SUBJECT TO ACTUAL SIZE CONDITIONS AND APPROVAL BY THE GEOTECHNICAL ENGINEER.

F5. DO NOT BACKFILL RETAINING WALLS (OTHER THAN CANTILEVER WALLS) UNTIL FLOOR CONSTRUCTION AT TOP AND BOTTOM IS COMPLETED (UNO). ENSURE FREE DRAINING BACKFILL AND DRAINAGE IS IN PLACE.

F6. FOOTINGS TO BE CONSTRUCTED AND BACKFILLED AS SOON AS POSSIBLE FOLLOWING EXCAVATION TO AVOID SOFTENING OR DRYING OUT BY EXPOSURE.

F7. THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH GEOTECHNICAL INVESTIGATION REPORT BY :

ELITE GEOSCIENCES

Project Number:
2026330

CONCRETE

C1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH ACSE CONCRETE SPECIFICATION AND AS.3600 WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.

C2. CONCRETE QUALITY (UNO ON PLANS):

ELEMENT	f'c MPa (28 DAYS)	SLUMP	MAX. AGG. SIZE	CEMENT TYPE	SHRINKAGE
FOOTING	32	80	20	GB	700
SUSPENDED SLAB	40	80	20	GB	700
SLAB ON GROUND	32	80	20	GB	700
GROUT IN BLOCKWORK	32	225	10	GB	-
COLUMNS	32	80	20	GB	-

PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 1379.

C3. NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING.

C4. CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE AS FOLLOWS, UNLESS SHOWN OTHERWISE :-

EXPOSURE CLASSIFICATION TO AS 3600	CONCRETE GRADE (MIN.)	CAST AGAINST GROUND	CAST IN FORMS AND EXPOSED	CAST IN FORMS NOT EXPOSED
A1 & A2	25	50mm	30mm	20mm (A1)
B1	32	60mm	40mm	
B2	40	65mm	45mm	

NOTE: (i) COVER REQUIREMENTS MAY NEED TO BE INCREASED TO SUIT FIRE RATING.

(ii) EXPOSURE CLASSIFICATION SHALL BE AS INDICATED BELOW OR ON THE DRAWINGS.

(iii) THE SURFACES OF MEMBERS PROTECTED FROM THE GROUND BY A DAMP-PROOF MEMBRANE HAVE EXPOSURE CLASSIFICATION A1, UNLESS NOTED OTHERWISE.

C5. FOR CHAMFERS, DRIP GROOVES, REGLETS, etc., REFER TO ARCH'S. DETAILS, MAINTAIN COVER TO REINFORCEMENT AT THESE DETAILS.

C6. SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED FINISHES.

C7. CONSTRUCTION JOINTS WHERE NOT SHOWN SHALL BE LOCATED TO THE APPROVAL OF THE ENGINEER.

C8. BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE SLAB THICKNESS, IF ANY.

C9. NO HOLES OR CHASES OTHER THAN THOSE SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT THE PRIOR APPROVAL OF THE ENGINEER.

C10. PIPES OR CONDUITS SHALL NOT BE PLACED WITHIN THE CONCRETE COVER TO REINFORCEMENT WITHOUT THE APPROVAL OF THE ENGINEER. THE CONCRETE COVER TO EMBEDDED PIPES OR CONDUITS SHALL BE A MINIMUM OF 20mm.

C11. ALL THE REQUIREMENTS OF THE CONCRETE SPECIFICATION SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE.

C12. THE CONCRETE WORK SHOWN ON THESE DRAWINGS HAS BEEN DESIGNED FOR THE FOLLOWING EXPOSURE CLASSIFICATION FOR DURABILITY IN ACCORDANCE WITH AS.3600.

ELEMENT	EXPOSURE CLASSIFICATION
INTERNAL	A1
EXTERNAL	B1

C13. THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS, COMPLETELY FILLING THE FORMWORK THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED WITH MECHANICAL VIBRATORS.

C14. CURING OF ALL CONCRETE IS TO BE ACHIEVED BY KEEPING SURFACES CONTINUOUSLY WET FOR A PERIOD OF 3 DAYS, AND PREVENTION OF LOSS OF MOISTURE FOR A TOTAL OF 7 DAYS FOLLOWED BY A GRADUAL DRYING OUT. APPROVED SPRAYED ON CURING COMPOUNDS MAY BE USED WHERE NO FLOOR FINISHES ARE PROPOSED. POLYTHENE SHEETING OR WET HESSIAN MAY BE USED IF PROTECTED FROM WIND AND TRAFFIC.

C15. CONSTRUCTION SUPPORT PROPPING IS TO BE LEFT IN PLACE WHERE NEEDED TO AVOID OVERSTRESSING THE STRUCTURE DUE TO CONSTRUCTION LOADING. NO BRICKWORK OR PARTITION WALLS ARE TO BE CONSTRUCTED ON SUSPENDED LEVELS UNTIL PROPPING IS REMOVED AND THE SLAB HAS ABSORBED ITS DEAD LOAD DEFLECTION.

C16. THE ENGINEER SHALL BE GIVEN 48 HOURS NOTICE FOR REINFORCEMENT INSPECTION AND CONCRETE SHALL NOT BE DELIVERED UNTIL FINAL APPROVAL IS OBTAINED.

C17. CONDUITS, PIPES, etc., SHALL ONLY BE LOCATED IN THE MIDDLE ONE THIRD OF SLAB DEPTH AND SPACED AT NOT LESS THAN 3 DIAMETERS.

C18. PROVIDE UPWARD CAMBER TO FORMWORK OF CANTILEVERS OF l/120, WHERE `l' IS THE SHORTEST PROJECTION BEYOND COLUMN OR WALL FACE, AND TO FORMWORK OF SLABS WHERE NOTED ON PLAN. MAINTAIN THE SLAB AND BEAM DEPTHS AS SHOWN.

TIMBER

T1. ALL TIMBER DESIGN, CONSTRUCTION, WORKMANSHIP AND MATERIAL SHALL BE IN STRICT ACCORDANCE WITH AS 1720.1 SAA TIMBER STRUCTURES CODE.

T2. AS1684 - NATIONAL TIMBER FRAMING CODE SHALL BE APPLIED WHERE APPROPRIATE TO DOMESTIC CONSTRUCTION

T3. ALL SOFTWOOD TIMBER SHALL BE MINIMUM F7 STRESS GRADE UNLESS NOTED OTHERWISE. ALL HARDWOOD TO BE MINIMUM GRADE F11 (UNO)

T4. UNLESS NOTED OTHERWISE ALL BOLTS IN TIMBER CONSTRUCTION TO BE COMMERCIAL BOLTS OF GRADE 4.6 SNUG TIGHT (M16-4.6/S) CONFORMING TO AS 1111 WITH WASHERS AS SPECIFIED.

T5. END AND EDGE DISTANCES FOR BOLTS WHERE NOT SPECIFIED SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF AS 1720.1.

T6. ALL BOLTS, NUTS & WASHERS TO BE HOT DIP GALVANISED, OR STAINLESS STEEL GRADE A4 (316), NOT ZINC OR CADMIUM PLATED.

T7. EXTERNAL TIMBER TO BE EITHER HARDWOOD DURABILITY CLASS I OR II TO AS1720.2 OR IMPREGNATED PINE GRADE F7, PRESSURE TESTED TO AS1604 AND RE-DRIED PRIOR TO USE. SUPPLEMENTARY TREATMENT SHALL BE APPLIED TO CUT SURFACES.

STEELWORK

S1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH ACSE STRUCTURAL STEELWORK SPECIFICATION AND AS.4100 AND AS.1554 EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.

S2. UNLESS OTHERWISE NOTED, ALL STEEL SHALL BE IN ACCORDANCE WITH:-
AS/NZS.3679.1 GRADE FOR BHP-300 PLUS ROLLED SECTIONS AND MERCHANT BAR EXCEPT WHERE NOTED.
AS/NZS.3679.2 GRADE 300 FOR ALL WELDED SECTIONS (WB & WC)
AS.1163 GRADE C350 FOR RECTANGULAR AND SQUARE HOLLOW SECTIONS.
AS.1163 GRADE C350 FOR CIRCULAR HOLLOW SECTIONS GREATER THAN 88.9Φ.
AS.1163 GRADE C250 FOR REMAINDER OF CIRCULAR HOLLOW SECTIONS.
AS.1397 COLD FORMED STEEL PURLINS AND GIRTS.
AS.3678 GRADE 250 FOR ALL PLATE

S3. THE BUILDER SHALL PREPARE WORKSHOP DRAWINGS AND SHALL SUBMIT COPIES OF EACH DRAWING FOR REVIEW. ALLOW 7 DAYS FOR SHOP DRAWING REVIEW. FABRICATION SHALL NOT COMMENCE UNTIL REVIEW HAS BEEN COMPLETED. REVIEW DOES NOT INCLUDE DIMENSIONS.

S4. HIGH STRENGTH STRUCTURAL BOLTS AND WASHERS SHALL COMPLY WITH AS.1252. COMMERCIAL GRADE BOLTS, NUTS AND WASHERS SHALL COMPLY WITH AS.1111, AS.1112 AND AS.1237 RESPECTIVELY. HIGH STRENGTH FRICTION GRIP BOLTS, NUTS AND WASHERS SHALL BE INSTALLED IN ACCORDANCE WITH AS.4100 AND SHALL BE TIGHTENED TO THE CORRECT TENSION USING APPROVED LOAD INDICATING WASHERS. CONTACT SURFACES OF ALL HIGH STRENGTH FRICTION GRIP BOLTED CONNECTIONS SHALL BE LEFT UNPAINTED. UNLESS NOTED OTHERWISE, ALL BOLTS TO BE 20 DIAMETER HIGH STRENGTH STRUCTURAL BOLTS OF GRADE 8.8 SNUG TIGHT (M20-8.8/S) (EXCEPT PURLIN & H.D BOLTS) BOLTS - DESIGNATED BY THE NUMBER, DIAMETER, GRADE AND TIGHTENING PROCEDURE.
eg. 4M16-4.6/S MEANS 4M16 DIA. COMMERCIAL GRADE BOLTS SNUG TIGHT.
6M20-8.8TF MEANS 6M20 HIGH STRENGTH STRUCTURAL BOLTS FULLY TENSIONED IN A FRICTION JOINT.
6M24-8.8TB MEANS 6M24 HIGH STRENGTH STRUCTURAL BOLTS FULLY TENSIONED IN A BEARING JOINT. (SOME SLIP ALLOWED.)
ALL CONNECTIONS TO HAVE 2 BOLTS MIN. PER CONNECTION WITH GUSSET PLATES 10 THICK UNLESS NOTED OTHERWISE.

S5. ALL WELDING DESIGN AND FABRICATION SHALL CONFORM TO AS.1554. UNLESS OTHERWISE NOTED, ALL WELDS TO BE 6mm CONTINUOUS FILLET FROM E48XX ELECTRODES.
ALL STRUCTURAL WELDS SHALL BE CATEGORY SP UNLESS NOTED OTHERWISE.
GENERAL PURPOSE WELDS SHALL BE DENOTED THUS `GP'.
BUTT WELDS WHERE INDICATED IN THE DRAWINGS ARE TO BE COMPLETE PENETRATION BUTT WELDS AS DEFINED IN AS.1554.
WELDING SYMBOLS TO AS.1101 PART 3.

S6.(a) INTERNAL STEELWORK (U.N.O. IN SPECIFICATION/DRAWINGS)

STRUCTURAL STEELWORK WHICH WILL REMAIN FULLY ENCLOSED WITHIN BUILDING FOR THE DESIGN LIFE OF STRUCTURE SHALL RECEIVE A CORROSION PROTECTION SYSTEM APPROVED BY ARCHITECT/PROJECT SUPERINTENDENT, BUT NOT LESS THAN ON THE FOLLOWING:

IZS1 (INORGANIC ZINC SILICATE 75 um)
ILG300 (IN-LINE GALVANISED 42 um)
PGS300 (ELECTRO GALVANISED 42 um)

(b) EXTERNAL STEELWORK (EXTERIOR AND BUILT INTO EXTERNAL WALLS) - U.N.O. IN SPECIFICATION/DRAWINGS.

STRUCTURAL STEELWORK SHALL RECEIVE A CORROSION PROTECTION SYSTEM IN ACCORDANCE WITH AS/NZS2312 AND FOLLOWING PARAMETERS:

DURABILITY - YEARS TO FIRST MAINTENANCE: VERY LONG TERM (15-25 YEARS)

ATMOSPHERIC CORROSIVITY CATEGORY: D (HIGH)

WRITTEN STATEMENT OF COMPLIANCE WITH ABOVE SHALL BE SUBMITTED TO PROJECT SUPERINTENDENT PRIOR TO STEELWORK BEING DELIVERED TO SITE. AREAS WITH DAMAGED COATING SHALL BE REPAIRED SO THAT THE REPAIRED AREA HAS A DURABILITY EQUAL OR EXCEEDING THAT SPECIFIED.

S7. THE BUILDER SHALL PROVIDE ALL CLEATS AND DRILL ALL HOLES NECESSARY FOR FIXING STEEL TO STEEL AND TIMBER TO STEEL WHETHER OR NOT DETAILED IN THE DRAWINGS.

S8. ALL THE REQUIREMENTS OF THE STRUCTURAL STEEL SPECIFICATION SHALL APPLY. (U.N.O.)

S9. THE BUILDER IS TO BE PRESENT WHEN ALL HOLDING DOWN BOLTS ARE INSTALLED TO ENSURE THEY ARE NOT DISPLACED DURING CONCRETE PLACEMENT.

S10. THE BUILDER IS TO MAKE GOOD AND/OR REPAIR ALL DAMAGED SURFACES DURING PERFORMANCE OF THE WORK.

S11. UNLESS SHOWN ON THE DRAWINGS THE ROOF STRUCTURE HAS BEEN DESIGNED FOR NORMAL ROOF LOADS ONLY AND DOES NOT ALLOW FOR ANY EXTRANEOUS LOADS SUCH AS HOISTS, MONORAILS etc.

S12. PROVIDE SEAL PLATES TO ALL HOLLOW SECTIONS, WITH 'BREATHER' HOLES IF MEMBERS ARE TO BE HOT DIPPED GALVANISED.

S13. WELD INSPECTIONS SHALL BE CARRIED OUT AS FOLLOWS:-

VISUAL SCANNING - 100% OF ALL WELDS (U.N.O. ON DRAWINGS)

NON-DESTRUCTIVE EXAMINATION (AS 1554.1)

WELD CATEGORY	WELD APPLICATION	VISUAL EXAMINATION	ULTRASONIC OR MAGNETIC PARTICLE
GP	PURLIN CLEAT FILLET WELDS STIFFENER FILLET WELDS	10%	-
SP	BUTT WELDS	50%	5%
	ALL OTHER WELDS (UNO)	25%	-

ALL WELD INSPECTIONS SHALL BE CARRIED OUT BY AN INDEPENDENT NATA REGISTERED/CERTIFIED WELDING INSPECTOR. A REPORT APPROVING ALL WELDING SHALL BE FORWARDED TO THE ENGINEER FOR REVIEW PRIOR TO STRUCTURAL STEELWORK LEAVING THE FABRICATION FACILITIES.

DRAFTING ABBREVIATIONS

B.E.L.	BULK EXCAVATION LEVEL
B.I.F.B.	BITUMEN IMPREGNATED FIBRE BOARD
BLK.	BLOCKWORK
BWK.	BRICKWORK
B/W.	BOTH WAYS
CONC.	CONCRETE
C/C.	CENTRES
C/S.	COURSES
D.J.	DOWELLED JOINT
E.F.	EACH FACE
F.F.	FAR FACE
F.F.L.	FINISHED FLOOR LEVEL
F.G.L.	FINISHED GROUND LEVEL
F.R.L.	FIRE RESISTANCE LEVEL
K.J.	KEYED JOINT
MAX.	MAXIMUM
MIN.	MINIMUM
N.F.	NEAR FACE
N.S.O.P	NOT SHOWN ON PLAN
N.T.S.	NOT TO SCALE
REINF.	REINFORCEMENT
TYP.	TYPICAL
U.N.O.	UNLESS NOTED OTHERWISE
V.B.M.	VAPOUR BARRIER MEMBRANE
V.J.	VERTICAL JOINT

NOTE


DETAILS AND SECTIONS ON THESE DRAWINGS ARE CROSS-REFERENCED BY THE FOLLOWING SYSTEM:-



client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: STRUCTURAL NOTES
date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S01
job no. 2026056 | drafted: J.Z.
scale 1:100;1:20




FOOTINGS & ON GROUND SLAB PLAN (BASEMENT)


120mm ON GROUND SLAB; SL82 MESH TOP; 0.2mm POLYTHENE MEMBRANE ON 50mm LEVELING SAND,UNO




CC1 DETAIL
USE 32MPA CONCRETE




CC2 DETAIL
USE 32MPA CONCRETE




BASE DIMENSIONS			
H	B	D	W
800	700	400	300
1000	800	400	300
1200	900	400	300



BASE DIMENSIONS			
H	B	D	W
1400	1000	500	400
1600	1100	500	400
1800	1300	600	400
2000	1400	650	450



BASE DIMENSIONS	
H	B
800	600
1000	700
1200	800



BASE DIMENSIONS	
H	B
1400	1000
1600	1100
1800	1200
2000	1300

TYPICAL RETAINING WALL

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					
	23.09.2026	C	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: BASEMENT FLOOR PLAN & DETAILS


date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S02

job no. 2026056 | drafted: J.Z.


scale 1:100;1:20




1 SECTION




2 SECTION




3 SECTION




4 SECTION




5 SECTION




6 SECTION




7 SECTION




8 SECTION




9 SECTION




DINCEL WALL CORNER ADDITIONAL BARS
SCALE NTS PLAN




DINCEL WALL ALTERNATIVE CORNER ADDITIONAL BARS
SCALE NTS PLAN



DINCEL WALL T – JUNCTION ADDITIONAL BARS
SCALE NTS PLAN




DINCEL WALL ALTERNATIVE T – JUNCTION ADDITIONAL BARS
SCALE NTS PLAN



NOTE: STARTER BARS – SAME NUMBER, DIAMETER AND ARRANGEMENT AS COLUMN OVER
REFER COLUMN SCHEDULE FOR COLUMN SIZES AND REINFORCEMENT

COLUMN DETIAL AT FOOTING




COLUMN DETAIL AT TERMINATION

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: BASEMENT FLOOR PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S03



20,115

SUSPENDED SLAB NOTES:


1. ALL SLABS TO BE 180 THICK UNO.
2. 200 DENOTES SLAB/BEAM THICKNESS.
3. ALL DRIP GROOVES,REGLETS,CHAMFERS,FILLETS, FALLS AND WATERPROOF TO ARCHITECH'S DETAIL. ENSURE CORRECT COVER TO ALL REINFORCEMENT.
4. FOR LOCATION AND DETAILS OF ALL STEPS&HOBS REFER TO ARCHITECT'S DETAIL.
5. DEPTH OF SETDOWN TO MEASURE FROM TOP OF STRUCTUARL SLAB LEVEL.
6. CONCRETE COVER FOR THE REINFORCEMENT INTERNAL AREA : 25MM;EXTERNAL AREA:45MM

FOOTINGS & ON GROUND SLAB PLAN (GROUND FLOOR)


150mm ON GROUND SLAB; SL82 MESH TOP&BOT; 0.2mm POLYTHENE MEMBRANE ON 50mm LEVELING SAND,UNO

USE 40MPA CONCRETE,


LEGEND
- DW1 LOAD BEARING BLOCK WALLS ON LOWER GROUND FLOOR
- SINGLE BRICK LOAD BEARING WALLS ON LOWER GROUND FLOOR
- DOUBLE BRICK EXTERNAL WALLS ON GROUND FLOOR
- SINGLE BRICK INTERNAL WALLS ON GROUND FLOOR




DETAIL A




CC1 DETAIL
USE 40MPA CONCRETE




CC3 DETAIL





CC4 DETAIL



FOOTING TYPE SF








TOOTHING DETAIL
SCALE 1:20

TYPICAL CONCRETE STAIR DETAILS



TYPICAL STRAIGHT LANDING

MAX. SPAN 'L' (mm)	THICKNESS 'T' (mm)	LONGITUDINAL BARS PER METER WIDTH		LAP LENGTH (mm)
		BOTTOM	TOP	
2800	200	6-N12	6-N12	600
3600	200	7-N12	7-N12	600
4300	200	5-N16	5-N16	800
5000	200	6-N16	6-N16	800
5600	225	7-N16	7-N16	800
6300	250	5-N20	5-N20	1000

NOTE: NUMBER OF RISERS MAY VARY - REFER TO ARCHITECTS DRAWING FOR SETOUT OF STAIRS

client


date	issue	amendment	checked
15.09.2026	A	ISSUED FOR CDC	JZ
20.09.2026	B	ISSUED FOR CDC	JZ

project: 16 TRENTINO RD TURRAMURRA


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: GROUND FLOOR PLAN & DETAILS

date 15/09/2026 | job no. 2026056 | scale 1:100;1:20 | designed: C.Z.(BE,MIE 3928680) | drafted: J.Z. | drawing no. S04




FOR SLOPES < 1:10




FOR SLOPES > 1:10


STRIP FOOTING STEP DETAILS



BRICK JOINT DETAIL




FOOTING CORNER DETAIL




Articulation Joint Ties (at every 4th course)


LOCATION TO FOLLOW BCA-2010-3.3.1.8
(MAX. 4M SPACING)




SECTION 1




SECTION 1
ALTERNATIVE




SECTION 1
ALTERNATIVE
BACKFILL MORE THAN 1.5M




SECTION 2




SECTION 3




SECTION 4




SECTION 5




SECTION 6



SECTION 7



SECTION 8




SECTION
WET AREA SET DOWN DETAILS


client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227


drawing title: GROUND FLOOR PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S05




SECTION 9




SECTION 10




SECTION 11




SECTION 12




SECTION 13




SECTION 14




SECTION 15




SECTION 16




SECTION 17




SECTION 18



SECTION 19



SECTION 20



SECTION 21

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: GROUND FLOOR PLAN & DETAILS

date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S06

job no. 2026056 | drafted: J.Z.

scale 1:100;1:20




GROUND FLOOR BOTTOM REINFORCMENT PLAN

NOTES:
- DISTRIBUTION REINFORCEMEN TO BE N12-300 U.N.O. ▼ - DENOTE INTEGRATED REINFORCEMENT

LAY 1ST

LAY 2ND

BAR LAYING SEQUENCE U.N.O.



TYPICAL INTEGRITY REINFORCEMENT
N.T.S.


INTEGRITY BAR LENGTH SCHEDULE

BARSIZE	'LP' = LENGTH FROM FACE OF COLUMN (mm)
N12	1000
N16	1300
N20	1600
N24	2000
N28	2300
N32	2600
N36	2900
N40	3200


NOTES:
1: INTEGRITY REINFORCEMENT MUST BE PLACED WITHIN COLUMN / WALL CORES AT BOTTOM LAYER

REINFORCEMENT NOTES:


1. SLAB REINFORCEMENT LAYING SEQUENCE U.N.O.:




2. TYPICAL TRIMMERS AT PENETRATION DETAIL:



3. TYPICAL TRIMMERS AT RE-ENTRANT CORNERS





GROUND FLOOR TOP REINFORCMENT PLAN

NOTES:
- DISTRIBUTION REINFORCEMEN TO BE N12-300 U.N.O.

LAY 4TH


LAY 3RD

BAR LAYING SEQUENCE U.N.O.

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: GROUND FLOOR PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S07



FIRST FLOOR CONCRETE PROFILE PLAN


USE 32MPA CONCRETE,


LEGEND


- DOUBLE BRICK LOAD BEARING WALLS ON GROUND FLOOR
- SINGLE BRICK LOAD BEARING WALLS ON GROUND FLOOR
- BRICK VENEER EXTERNAL WALLS ON FIRST FLOOR
- NGR EXTERNAL WALLS ON GROUND FLOOR
- TIMBER STUD INTERNAL WALLS ON FIRST FLOOR

SUSPENDED SLAB NOTES:

1. ALL SLABS TO BE 180 THICK UNO.
2. 200 DENOTES SLAB/BEAM THICKNESS.
3. ALL DRIP GROOVES,REGLETS,CHAMFERS,FILLETS, FALLS AND WATERPROOF TO ARCHITECH'S DETAIL. ENSURE CORRECT COVER TO ALL REINFORCEMENT.
4. FOR LOCATION AND DETAILS OF ALL STEPS&HOBS REFER TO ARCHITECT'S DETAIL.
5. DEPTH OF SETDOWN TO MEASURE FROM TOP OF STRUCTUARL SLAB LEVEL.
6. CONCRETE COVER FOR THE REINFORCEMENT INTERNAL AREA : 25MM,EXTERNAL AREA:45MM








TOOTHING DETAIL

SCALE 1:20

TYPICAL CONCRETE STAIR DETAILS



TYPICAL STRAIGHT LANDING

MAX. SPAN 'L' (mm)	THICKNESS 'T' (mm)	LONGITUDINAL BARS PER METER WIDTH		LAP LENGTH (mm)
		BOTTOM	TOP	
2800	200	6-N12	6-N12	600
3600	200	7-N12	7-N12	600
4300	200	5-N16	5-N16	800
5000	200	6-N16	6-N16	800
5600	225	7-N16	7-N16	800
6300	250	5-N20	5-N20	1000

NOTE: NUMBER OF RISERS MAY VARY - REFER TO ARCHITECTS DRAWING FOR SETOUT OF STAIRS

client

date	issue	amendment	checked
15.09.2026	A	ISSUED FOR CDC	JZ
20.09.2026	B	ISSUED FOR CDC	JZ

checked

project


16 TRENTINO RD TURRAMURRA

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227


drawing title

FIRST FLOOR PLAN & DETAILS


date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S08




1 SECTION




2 SECTION




3 SECTION




4 SECTION




5 SECTION




6 SECTION




7 SECTION




8 SECTION




9 SECTION




10 SECTION




11 SECTION



12 SECTION



13 SECTION



14 SECTION

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: FIRST FLOOR PLAN & DETAILS


date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S09

job no. 2026056 | drafted: J.Z.


scale 1:100;1:20




15 SECTION




16 SECTION




17 SECTION




18 SECTION



19 SECTION



20 SECTION



21 SECTION

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: FIRST FLOOR PLAN & DETAILS

date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S10

job no. 2026056 | drafted: J.Z.

scale 1:100;1:20




FIRST FLOOR BOTTOM REINFORCEMENT PLAN

NOTES:
- DISTRIBUTION REINFORCEMENT TO BE N12-300 U.N.O. ▼ - DENOTE INTEGRATED REINFORCEMENT

LAY 1ST

LAY 2ND

BAR LAYING SEQUENCE U.N.O.




FIRST FLOOR TOP REINFORCEMENT PLAN

NOTES:
- DISTRIBUTION REINFORCEMEN TO BE N12-300 U.N.O.

LAY 4TH

LAY 3RD

BAR LAYING SEQUENCE U.N.O.



TYPICAL INTEGRITY REINFORCEMENT
N.T.S.

INTEGRITY BAR LENGTH SCHEDULE


BARSIZE	'LP' = LENGTH FROM FACE OF COLUMN (mm)
N12	1000
N16	1300
N20	1600
N24	2000
N28	2300
N32	2600
N36	2900
N40	3200

NOTES:


1: INTEGRITY REINFORCEMENT MUST BE PLACED WITHIN COLUMN / WALL CORES AT BOTTOM LAYER

REINFORCEMENT NOTES:


1. SLAB REINFORCEMENT LAYING SEQUENCE U.N.O.:



2. TYPICAL TRIMMERS AT PENETRATION DETAIL:



3. TYPICAL TRIMMERS AT RE-ENTRANT CORNERS



client

date	issue	amendment	checked
15.09.2026	A	ISSUED FOR CDC	JZ
20.09.2026	B	ISSUED FOR CDC	JZ

date	issue	amendment	checked

project


16 TRENTINO RD TURRAMURRA

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title

FIRST FLOOR PLAN & DETAILS

date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S11




BEAM SCHEDULE

MARK No.	SIZE
B1	2/240x42 SMARTLVL 15
B2	2/240x42 SMARTLVL 15
B3	2/200x42 SMARTLVL 15
B4	240x42 SMARTLVL 15
B5	2/200x42 SMARTLVL 15
B6	2/240x42 SMARTLVL 15
B7	2/200x42 SMARTLVL 15
B8	2/200x42 SMARTLVL 15
B9	2/200x42 SMARTLVL 15
B10	2/200x42 SMARTLVL 15
B11	2/200x42 SMARTLVL 15
B12	2/200x42 SMARTLVL 15
B13	2/200x42 SMARTLVL 15
B14	200x42 SMARTLVL 15


ALL EXTERNAL STEEL BEAM TO BE H.D.GALV.
SURFACE PREPARATION & FINISH TO COMPLY WITH AS/NZS 2312/1994
ALL EXTERNAL TIMBER BEAM TO BE TREATED AS H3

ROOF LEVEL FRAMING PLAN


ALL TIMBER BRACING AND TIE DOWN REFER TO AS1684
REFER TO TIMBER MANUFACTURER'S SEPCIFICATION AND DETAILS




ROOF BRACING FIXING TO RAFTERS AT EAVES
SCALE 1:5




TIE DOWN DETAIL (TYPICAL)
SCALE 1:5




UNDERPURLIN TO TOP PLATE TIE-DOWN DETAIL
TOP PLATE TO STUD WORK TIE-DOWN
SCALE 1:5



TYPICAL RAFTER TIE-DOWN DETAIL






TIMBER BEAM CONNECTION

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: ROOF FLOOR PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S12




POOL PLAN

USE 32 MPA CONCRETE




TYPICAL WALL CORNER DETAIL

SCALE 1:20




TYPICAL BONDBEAM CORNER DETAIL

SCALE 1:20




PLAN – TYPICAL SKIMMER BOX

SCALE 1:20




E SECTION




TYPICAL STEPS DETAIL

SCALE 1:20




TYPICAL SECTION AT WALL LIGHT

SCALE 1:20



ELEVATION – SKIMMER BOX

SCALE 1:20



HYDROSTATIC PRESSURE RELIEF VALVE

SCALE 1:20

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					
	23.09.2026	C	ISSUED FOR CDC	JZ					
	29.09.2026	D	ISSUED FOR CDC	JZ					


MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: POOL PLAN & DETAILS


date 15/09/2026 | designed: C.Z.(BE,MIE 3928680) | drawing no. S13

job no. 2026056 | drafted: J.Z.

scale 1:100;1:20



A SECTION




B SECTION


client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					
	23.09.2026	C	ISSUED FOR CDC	JZ					

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227


drawing title
POOL PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S14



C SECTION



D SECTION



E SECTION

client	date	issue	amendment	checked	date	issue	amendment	checked	project
	15.09.2026	A	ISSUED FOR CDC	JZ					16 TRENTINO RD TURRAMURRA
	20.09.2026	B	ISSUED FOR CDC	JZ					
	23.09.2026	C	ISSUED FOR CDC	JZ					
	29.09.2026	D	ISSUED FOR CDC	JZ					

MBC ENGINEERING PTY LTD
BUILDING CIVIL & STRUCTURAL ENGINEERS
PO BOX 269
PARRAMATTA NSW 2124
MBCCONSULTING@LIVE.COM
MOBILE:0432546227

drawing title: POOL PLAN & DETAILS
date 15/09/2026
job no. 2026056
scale 1:100;1:20
designed: C.Z.(BE,MIE 3928680)
drafted: J.Z.
drawing no. S15