PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

GENERAL NOTES

THESE DRAWINGS MUST BE READ IN CONCURRENCE WITH ALL ARCHITECTURAL AND OTHER CONSULTANT DRAWINGS, SPECIFICATIONS AND OTHER WRITTEN INSTRUCTIONS AS ISSUED DURING THE DURATION OF THE CONTRACT. IF ANY DISCREPANCIES ARISE YOU MUST INFORM THE SITE'S ARCHITECT/BUILDER BEFORE PROCEEDING WITH ANY WORK. ANY AMENDMENTS FROM THE ORIGINAL INFORMATION PROVIDED, INCLUSIVE OF SITE PREPARATION OR PROPOSED CONSTRUCTION CHANGES, THIS CONSULTANCY MUST BE NOTIFIED, IF THE AMENDMENTS ARE CONSIDERED NECESSARY ONLY THEN THE AMENDMENTS CAN BE MADE. THE SITE'S CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT APPROPRIATE EXPECTATIONS ARE PROVIDED AND MAINTAINED THROUGHOUT ALL ASPECTS OF THE STRUCTURE.

THESE DRAWINGS MUST NOT BE SCALED TO ATTAIN DIMENSIONS. CONSTANTLY CITE THE ARCHITECTURAL DRAWINGS FOR DIMENSIONS.

ALL LEVELS AND SETTING OUT DIMENSIONS SHOWN IN THESE DRAWINGS MUST BE CONFIRMED BY THE BUILDER ONSITE.

THE SITE'S CONTRACTOR IS ACCOUNTABLE TO ORGANISE THE LOCATION, SIZE AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT DATE OF THE STRUCTURE.

THE STRUCTURE MUST BE MAINTAINED IN A STABLE CONDITION WITH NO PART
BEING OVERSTRESSED. THIS CONSULTANCY IS NOT ACCOUNTABLE TO DAMAGES DURING ALL STAGES OF CONSTRUCTION, DURING BOTH CONSTRUCTION AND MAINTENANCE PERIODS ANY CLAIMS OF DAMAGE TO ANY NEIGHBOURING PROPERTIES OR BUILDINGS WILL NOT BE RECTIFIED BY THIS CONSULTANCY.

ALL WORKMANSHIP AND MATERIALS MUST MEET THE REQUIREMENTS OF THE
CURRENT EDITIONS OF THE RELEVANT SAA (AS) CODES, BY-LAWS AND ORDINANCES OF THE RELEVANT AUSTRALIAN BUILDING AUTHORITIES.

IF ANY SUBSTITUTE MATERIALS ARE NEEDED TO CONSTRUCT THIS STRUCTURE IT MUST BE APPROVED BY AN ENGINEER PRIOR TO USE.

THESE STRUCTURAL DRAWINGS ARE DELIVERED WITH THE UNDERSTANDING THAT THE BUILDER MAINTAINS, ADEQUATE AND REGULATED CONTRACT WORKS INSURANCE, WORK SAFETY PROCEDURES AND PUBLIC LIABILITY INSURANCES.

THIS CONSULTANCY'S ENGINEERS DO NOT HAVE ANY ACCOUNTABILITY TO ANY PART OF THE STRUCTURE THAT IS NOT ESTABLISHED IN ARCHITECTURAL/ BUILDER DRAWINGS AND WRITTEN INSTRUCTIONS.

INSPECTIONS ARE ENFORCED TO BE COMPLETED BY AN ENGINEER FROM THIS
CONSULTANCY. ALL INSPECTIONS ARE NEEDED TO BE COMPLETED IN AGREEMENT WITH THE PROCEDURES OF INSPECTIONS PUT IN PLACE BY THIS CONSULTANCY.

DAMP PROOFING MEMBRANE

A 0.2 mm MIN POLYETHYLENE DAMP PROOF HIGH IMPACT RESISTANCE MEMBRANE MUST BE POSITIONED UNDER THE SLAB SO THAT THE BOTTOM SURFACE IS COMPLETELY UNDER-LAID AND TERMINATES AT GROUND LEVEL. THE MEMBRANE MUST BE BRANDED CONSTANTLY "AS2870 CONCRETE UNDERLAY,

0.2mm HIGH IMPACT RESISTANT" WITH THE MANUFACTURERS NAME/TRADEMARK OR RELEVANT CODE.

THE MEMBRANE LAPPING MUST BE 200mm JOINTS AND TAPED AND/OR SEALED AT PLUMBING INSERTION WITH CONTINUOUS CLOSE FITTING SLEAVE OR MADE CONTINUOUS WITH THE VAPOUR BARRIER BY TAPPING AND WATERPROOFING.

SITE CLASSIFICATION

AS INSTRUCTED BY THE BUILDER/CONTRACTED CLIENT, AN ASSUMPTION IS MADE ON THE GEOTECHNICAL CLASSIFICATION BASED ON AS2870. WE ADVISE A GEOTECHNICAL ENGINEER TO BE ENGAGED IN THE SITE CLASSIFICATION PROCESS AND PROVIDE PRECISE SITE SPECIFICATIONS.

IF SOIL CONDITIONS FOUND ON SITE ESTABLISH A DISCREPANCY FROM THOSE INDICATED IN THE GEOTECHNICAL INVESTIGATION, THE ENGINEER MUST BE INFORMED PRIOR TO PROCEEDING TO MAKING ANY AMENDMENTS TO THE STRUCTURAL DESIGN.

THE GEOTECHNICAL INVESTIGATION MAY BE CONSIDERED IRRELEVANT IF THE LOCATION OF PROPOSED STRUCTURES INDICATES A DISCREPANCY FROM THE IDENTIFIED TIME OF THE PROVIDED GEOTECHNICAL REPORT. THE DESIGN IS BASED UPON THE CUT AND FILL INFORMATION PROVIDED BY OUR CONTRACTED LIENT.

THIS DESIGN DOES NOT TAKE INTO ACCOUNT SLOPE STABILITY. IF REQUIRED BY
COUNCIL OR OTHER AUTHORITY, A SUITABLY QUALIFIED PERSON SHALL BE
ENGAGED TO UNDERTAKE A SLOPE STABILITY ASSESSMENT.

PILES

THE CONTRACTOR IS REQUIRED TO FAMILIARISE THEMSELVES WITH THE SITE AND ASSESS CONCERNS RELATED WITH NOISE, VIBRATION, GROUNDWATER, TRAFFICABILITY AND ANY OTHER CONCERNS WHICH COULD REQUIRE RISK ASSESSMENT.

BEFORE COMMENCEMENT OF PLACEMENT OF CONCRETE ALL PIER HOLES MUST BE CLEANED AND DEWATERED.

CLASS 4 ROCK WILL BE HIGHLIGHTED IN THE GEOTECHNICAL REPORT. THE CLASS 4 ROCK LEVELS FOR EVALUATING PILE TOE LEVELS WILL BE AGREED IN WRITING WITH THE CONTRACTED GEOTECHNICAL ENGINEER BEFORE COMMENCEMENT OF DRILLING.

ALL PILES ARE TO BE INSTALLED BY THE CONTRACTOR TO AS2159-1995 PILING DESIGN AND INSTALLATIONS CODE AND ANY OTHER RELEVANT CODES.
ALL PIER HOLES MUST BE POURED SEPARATE TO SLAB AND FOOTINGS.
PIERS AND FOUNDATIONS ARE TO BE FOUNDED ON AN IDENTICAL BEARING. THIS CONSULTANCY, PCA, AND/OR COUNCIL AUTHORITY WILL INSPECT THE BEARING MATERIAL OF PIERS AND/OR FOOTINGS BEFORE COMMENCEMENT OF PLACEMENT OF CONCRETE.
IF ANY OF THE PIERS AND /OR FOOTINGS COMES UPON SHALE OR ROCK, THEN ALL PIERS AND /OR FOOTINGS MUST BEAR ON SHALE OR ROCK.
UNLESS OTHERWISE NOTED SAFE WORKING LOAD MUST BE 80KN FOR SCREW PIERS.
SCREW AND TIMBER PILES MUST BE INSTALLED AND CERTIFIED BY A QUALIFIED AND LICENSED SITE CONTRACTOR.
ALL PILES ARE TO BE CUT DOWN TO LEVEL THAT THEY PROJECT 75MM INTO THE BASE OF CAPPING BEAMS AND REINFORCEMENT PROJECTS IN CAPPING BEAMS AS SHOWN ON DETAILS. THE PILING CONTRACTOR WILL GRADUALLY REMOVE AND DISPOSE OF ANY SOIL IF ANY FROM THE STRUCTURAL AREA. THIS INCLUDES GROUT/CONCRETE SPILLAGE IF ANY. THE PILING CONTRACTOR MUST SUPPLY OF ALL EQUIPMENT SUCH AS TRUCKS AND LOADERS AND ANY APPROVALS FOR DISPOSAL AS REQUIRED.

ALWAYS CITE NOTES ON THE FOUNDATION DRAWING FOR MINIMUM ALLOWABLE BEARING CAPACITY. THE FOUNDATION MATERIAL MUST BE APPROVED BY THE CONTRACTED GEOTECHNICAL ENGINEER FOR THIS BEARING CAPACITY BEFORE PLACING MEMBRANE, REINFORCEMENT OR CONCRETE. ANY ADDITIONAL EXAMINATION REQUIRED BY THE CONTRACTOR WILL BE AT THE CONTRACTOR'S EXPENSE.

FOUNDATIONS

ALWAYS CITE THE NOTES ON THE FOUNDATION DRAWING FOR MINIMUM ALLOWABLE BEARING CAPACITY. THE FOUNDATION MATERIAL SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER FOR THIS BEARING CAPACITY BEFORE PLACING MEMBRANE, REINFORCEMENT OR CONCRETE.

ALL WORKMANSHIP AND MATERIALS ARE TO ABIDE BY TO THE NATIONAL
CONSTRUCTION CODE AND AS 2870.

SITE IS TO BE CLEARED OF TOPSOIL AND OTHER ORGANIC MATTER FROM THE
AREA ON WHICH THE SLAB WILL REST.

FOOTINGS MUST BE SITUATED CENTRALLY UNDER WALLS AND COLUMNS UNLESS NOTED OTHERWISE. ADDITIONALLY, FOOTINGS AND PIERS ARE COMPULSORY WHERE UNCONTROLLED FILL UNDER EDGE BEAMS AND /OR SLAB IS EXISTENT.

ANY FILL MUST END PAST THE EDGE OF THE STRUCTURE/BUILDING BY AT
LEAST 1.0m AND MUST BE RETAINED OR BATTERED BEYOND THIS POINT BY A
SLOPE NOT STEEPER THAN A RATIO OF 1: 2. FORMWORK TO BE USED WHERE
SIDES OF THE FOUNDATION ARE NOT STABLE. LOOSE DEBRIS AND WATER MUST BE
REMOVED AND DRAINED OF THE FOUNDATION.

FILL USED TO SUPPORT THE SLAB ON GROUND MUST BE CONTROLLED OR ROLLED FILL IN ACCORDANCE WITH AS2870: CONTROLLED FILL CONSISTS OF WELL GRADED SAND FILL UP TO 800mm DEEP, WELL COMPACTED IN NOT MORE THAN 200mm LAYERS BY VIBRATING PLATE OR VIBRATING ROLLER. NO SAND FILL UP TO 400mm DEEP, WELL COMPACTED IN NOT MORE THAN 150mm LAYERS BY A MECHANICAL ROLLER, CLAY FILL SHOULD BE MOIST DURING COMPACTION. ANY DEPTHS STIPULATED IN THIS, ARE DEPTHS MEASURED AFTER COMPACTION. ANY DEPTHS WHICH FALL OUTSIDE THE PARAMETERS SPECIFIED ABOVE SHALL BE SUBJECT TO TESTING. ENGINEER IS TO BE CONTACTED PRIOR TO CONSTRUCTION WHERE TEST FAILS, AND ADDITIONAL PIERS WILL BE REQUIRED. CONTROLLED FILL SHALL BE PLACED, TESTED AND CERTIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER AS STIPULATED IN AS3798. ROLLED FILL MUST CONTAIN MATERIAL COMPACTED IN LAYERS BY REPEATED ROLLING WITH AN EXCAVATOR. ROLLED FILL SHALL NOT EXCEED 600mm COMPACTED IN LAYERS NOT MORE THAN
300mm FOR SAND MATERIAL OR 400mm COMPACTED LAYERS AND NOT MORE THAN 150mm FOR OTHER MATERIALS.
FILL MUST CONTAIN REACTIVE CLAYS, THE FILL MUST BE PLACED IN A MOIST CONDITION.
A 50mm MINIMUM BINDING LAYER SHOULD BE APPLIED TO THE BASE OF ALL FOUNDATIONS IMMEDIATELY AFTER AUTHENTICATION OF THE BEARING CAPACITY BY THE GEOTECHNICAL ENGINEER. WHERE THE FOUNDATION MATERIAL IS DEEPER THAN REQUIRED FOR THE FOOTING THE EXCAVATION IS TO BE BACKFILLED WITH A WEAK MIX CONCRETE N10 TO THE UNDERSIDE OF THE FOOTING. THE CONTRACTOR IS TO APPOINT A GEOTECHNICAL ENGINEER TO AUTHENTICATE THE BEARING CAPACITY OF THE FOUNDATIONS PRIOR TO PLACEMENT OF THE BINDING LAYER.

ALL FOOTINGS ARE TO BE ESTABLISHED ON MATERIAL THAT HAS A TOLERABLE
BEARING CAPACITY OF 200kPA. IF IT IS CHALLENGING TO REACH THE REQUIRED
BEARING CAPACITY, THIS CONSULTANCY MUST BE CONTACTED TO RE-ASSESS THE FOOTING DESIGN.

CONCRETE

ALL MATERIALS AND WORKMANSHIP MUST MEET THE REQUIREMENTS OF AS3600 AND THE PROJECT SPECIFICATIONS.

CONCRETE SHALL BE PLACED AND CURED MEET THE REQUIREMENTS OF AS3600. WHERE CURING COMPOUNDS ARE USED, COMPLIANCE BY MEETING THE REQUIREMENTS OF AS3799 MUST BE ACCOMPLISHED, AND APPLIED IN STRICT ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS AND AS SPECIFIED THROUGH ONTO SLAB WITHIN 24HRS OF FINISHING CONCRETE AND COLUMNS, STRAIGHT AFTER THE ABSTRACTION OF FORMWORK. NO ADMIXTURES ARE TO BE ADDED TO CONCRETE WITHOUT WRITTEN APPROVAL BY THIS CONSULTANCY'S ENGINEER.
ALL CONCRETE MUST BE COMPRESSED AT THE TIME OF PLACING USING A MECHANICAL VIBRATOR.
ADDITIONAL CONSTRUCTION JOINTS, WHERE NOT SHOWN ON THE DRAWINGS MUST BE APPROVED BY OUR CONSULTANCY'S ENGINEER AND/OR IN ACCORDANCE WITH AS3700.
THE FACE OF ALL CONCRETE AGAINST WHICH NEW CONCRETE IS TO BE CAST, IT IS ESSENTIAL THAT CONCRETE IS TO BE COMPREHENSIVELY MECHANICALLY SCABBLED, FULLY EXPOSING THE AGGREGATE INTERFACE.
ALL FORM WORK SHALL COMPLY WITH AS 3610.
EVERY FLOOR OF THE STRUCTURE MUST BE FULLY PROPPED TO THE FLOOR BELOW IN ACCORDANCE WITH AS3610 (FORM WORK CODE).
IT IS VITAL THAT THE FLOOR IS BACK-PROPPED THROUGH A MINIMUM OF TWO STOREYS BELOW. THIS RESULTS IN A MINIMUM OF THREE STOREYS PROPPED AT ALL TIMES.
PROPS MAY BE REMOVED AFTER 28 DAYS OF CURING OR AFTER 14 DAYS IF THE CONCRETE HAS REACHED ITS CHARACTERISTIC STRENGTH (AS VERIFIED BY CYLINDER TEST RESULTS).
UNLESS NOTED OTHERWISE NO ALLOWANCES WILL BE ARRANGED FOR STACKED MATERIALS OR MACHINERY ON THE CONCRETE STRUCTURE.
ALL THICKNESS DETAILED IN DRAWINGS ARE SHOWN AS MINIMUM REQUIREMENTS, NO REDUCTION IN THICKNESS DUE TO FALLS OR TOPPING IS TOLERABLE.
WITHOUT THE PRIOR APPROVAL OF THE ENGINEER, NO HOLES OR CHASES OTHER THAN THOSE SHOWN ON DRAWINGS WILL BE MADE IN CONCRETE ELEMENTS.
WELDING OF ANY REINFORCEMENT MUST BE PRE-APPROVED IN WRITTEN FORM BY THIS CONSULTANCY'S ENGINEER.
PIPES OR CONDUITS MUST NOT BE PLACED WITHIN THE CONCRETE COVER TO REINFORCEMENT, UNLESS APPROVED BY ENGINEER.
CONDUITS GREATER THAN 25mm DIAMETER CAST INTO CONCRETE MEMBERS SHALL BE SPACED AT A MAXIMUM DISTANCE POSSIBLE AND UNDER NO CIRCUMSTANCES CLOSER THAN A CLEAR SPACING OF TWICE THE LARGER CONDUIT DIAMETER FROM PARALLEL REINFORCEMENT OR ANY OTHER CONDUIT.

TIMBER

ALL WORK IN STRUCTURAL TIMBER MUST MEET THE REQUIREMENTS THE CURRENT EDITION OF AS 1684, SAA TIMBER FRAMING CODE AS 1720, SAA TIMBER ENGINEERING CODE AS 1320 – GLUED LAMINATED STRUCTURAL TIMBER.
SOFTWOOD TO BE MINIMUM GRADE F7 AND HARDWOOD MINIMUM GRADE F14 UNLESS NOTED OTHERWISE.
EXTERNAL TIMBER TO BE EITHER HARDWOOD DURABILITY CLASS I OR II MPREGNATED GRADE F7. PRESSURE TREATED TO AS1684 AND RE-DRILLED BEFORE USE. SUPPLEMENTARY TREATMENT MUST BE APPLIED TO ALL CUT SURFACES. SUPPORTING DOCUMENTATION FOR PRESERVATIVE TREATMENT MUST BE SUPPLIED TO THIS CONSULTANCY.
ALL BOLTS IN TIMBER CONSTRUCTION TO BE MIN. M16 UNLESS NOTED OTHERWISE BOLT HOLES MUST BE DRILLED EXACT SIZE.
WASHERS UNDER HEADS AND NUTS TO BE AT LEAST 2.5 TIMES BOLT DIAMETER. BOLTS AN ALL NUTS TO BE PROVIDED WITH WASHERS. ALL BOLTS TO BE
TIGHTENED BEFORE HANDOVER.
ALL TIMBER JOINT NOTCHES ARE TO BE 160mm MINIMUM AWAY FROM LOOSE KNOTS, SEVERE SLOPING, GRAIN, GUM VENTS OR OTHER MINOR DEFECTS.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS

DRAWING NUMBER: CS101GAS	SHEET NUMBER: S0	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: GENERAL NOTES

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

STEEL

MATERIALS FABRICATIONS AND ERECTION TO BE STRICTLY IN ACCORDANCE WITH AS 4100 THE COMPANIION AUSTRALIAN STANDARDS CITED IN AS 4100 AND WITH THE SPECIFICATIONS.

UNLESS NOTED OTHERWISE ALL STEEL SHALL BE IN ACCORDANCE WITH BHP 300 PLUS TO ASNZ3679.1 (1996)– HOT ROLLED SECTIONS GRADE 300 TO AS3679.2 (1991)– WELDED SECTIONS.

GRADE 250 TO AS3678 (1996)– HOT ROLLED PLATES & SLABS.
GRADE 350 TO AS1163 (1993)– HOLLOW SECTIONS

WELDING SHALL COMPLY WITH AS 1554.

WELDS SHALL BE 6mm CONTINUOUS FILLET UNLESS NOTED OTHERWISE. WELDS TO PURLIN CLEATS SHALL BE 4mm cfw.

ELECTRODES SHALL BE E41XX OR E48XX.

BOLTS DENOTED 46/S – ARE COMMERCIAL BOLTS OF STRENGTH GRADE 46 TO AS1111 – SNUG TIGHT.

BOLTS DENOTED 8.8/S,8.8/TB AND 8.8/TF ARE HIGH STRENGTH STRUCTURAL BOLTS OF STRENGTH GRADE 8.8 TO AS 1252; 8.8/S DENOTED BOLTS SNUG TIGHT; 8.8/TB AND 8.8/TF DENOTES BOLTS FULLY TENSIONED TO AS1511; 8.8/TB DENOTES BEARING JOINT; 8.8/TF DENOTES FRICTION JOINT.

LOAD INDICATOR WASHERS SHALL BE USED UNDER THE THE BOLT HEAD FOR ALL 8.8/TF 8.8/TB BOLTS.

BOLTS SHALL BE M20 UNLESS NOTED NOTED OTHERWISE. BOLTS SHALL BE 4.6/S UNLESS NOTED OTHERWISE.

BOLT HOLES SHALL BE BOLT DIAMETER. +2mm FOR STEEL TO STEEL CONNECTIONS. +4mm FOR STEEL TO CONCRETE CONNECTIONS.
+6mm FOR BASE PLATES.

ALL PLATES AND STIFFENERS SHALL BE 10mm THICK U.N.O.

CORROSION PROTECTION.

	SURFACE PREPARATION	PRIMER
ALL U.N.O.	POWER WIRE BRUSH TO AS1627:2 CLASS 3	R.O.Z.C.
EMBEDDED ITEMS, SHELF ANGLES & EXPOSED STEELWORK		HOT DIPPED GALVANISED TO AS1650

CONCRETE ENCASED STEELWORK TO BE WRAPPED IN ACCORDANCE WITH AS 4100 AND TO HAVE 50mm MINIMUM COVER TO CONCRETE.

LOCATION OF PURLINS AND GIRTS TO BE OBTAINED FROM ARCHITECTS DRAWINGS OR ROOFING CONTRACTORS.

PROVIDE SEAL PLATES TO ENDS OF HOLLOW SECTIONS.
ALL STRUCTURAL STEELWORK WHICH IS EXPOSED OR IN CONTACT WITH EXPOSED BRICKWORK OR BLOCKWORK AND ALL LINTELS, SHALL BE HOT DIP GALVANIZED UNLESS NOTED OTHERWISE.

ALL STEELWORK TO BE TEMPORARILY BUT SECURELY BRACED UNTIL ALL FINAL BRACING, CLADDING,AND STABILIZING BRICKWORK OR BLOCKWORK HAVE BEEN COMPLETED.

ARRANGE FOR CERTIFICATION FROM A QUALIFIED CONSULTANCY THAT THE TRUSSES ARE STRUCTURALLY SATISFACTORY.

CLAY BRICK MASONARY

MASONRY, MORTAR AND BUILT MASONRY COMPONENTS MUST COMPLY WITH AS3700 AND AS4773.

THE SLAB IS PLANED FOR ARTICULATION REQUIREMENTS. ARTICULATION JOINTS
SHALL BE CARRIED OUT IN ACCORDANCE WITH AS4773 AND CEMENT, CONCRETE AND
AGGREGATES AUSTRALIA BOOKLET TECHNICAL NOTE 61 (ARTICULATED WALLING) AND AS3700 SECTION 12 16.4.

MASONRY UNITS TO HAVE A MINIMUM CHARACTERISTIC UNCONFINED STRENGTH OF 20MPa IN ACCORDANCE WITH AS2733.

MASONRY ARTICULATION JOINTS SHALL BE POSITIONED AT ANY POSITION WHERE NEW BRICKWORK ALIGNS WITH OLD BRICKWORK.

WHERE MASONRY ARTICULATION IS INDICATED AT THE SIDE OF OPENINGS WITH BRICKWORK ABOVE THE OPENING, A SLIP JOINT AROUND THE END OF THE LINTEL MUST BE DELIVERED WITH CARE.

MASONRY MUST BE LAYED IN FRESHLY PRIMED MORTAR.
CONCRETE BLOCKS: MORTAR MIX TO BE UNIFORMLY MIXED TO A RATIO OF
ONE–PART CEMENT, ONE–PART LIME AND SIX PARTS SAND CONFORMING TO
AS2701.
CLAY BLOCKS: MORTAR MIX TO BE UNIFORMLY MIXED TO A RA 110 OF ONE–PART CEMENT, THREE PARTS SAND AND ONE FOURTH PART LIME CONFORMING TO AS2701.

GROUT MUST HAVE A COMPRESSIVE STRENGTH (F'C) OF 20 MPa AT 28 DAYS, A
SLUMP PF 125mm IN A 150mm SLUMP CONE, A MAXIMUM AGGREGATE SIZE OF
10mm AND MUST BE IN ACCORDANCE WITH AS3700.

THE LAYING OF MASONRY MUST BE FULL FACE WITH CROSS JOINTS ENTIRLY FILLED, JOINT THICKNESS SHALL NOT EXCEED 12mm.

THE CAVITY MUST NOT SURPASS 100mm AND SHALL NOT BE SMALLER THAN 40mm
UNLESS NOTED OTHERWISE. CAVITY MUST BE KEPT CLEAN AND CLEAR OF IMPEDIMENTS AND COMPLIANT WITH NCC.

VERTICAL JOINTS UNLESS NOTED OTHERWISE BRICKS WITH A POTENTIAL FIVE YEAR EXPANSION OF 1 mm/m. BUILDER MUST NOTIFY PACE STRUCTURAL IF DISTINGUISHING EXPANSION OF BRICK UNITS IS DIFFERENT BY 10% OR MORE.

RAKING OF JOINTS IS NOT ALLOWABLE WITHOUT AUTHORISATION FROM AN ENGINEER.

ALL WALLS ARE TO BE KEPT STEADY AT ALL STAGES OF CONSTRUCTION AND MUST NOT BE OVER STRESSED AT ANY POINT DURING DEVELOPMENT.

UNLESS NOTED OTHERWISE, NO CHASES OR RECESSES IS ACCEPTABLE IN MASONRY WALLS WITHOUT THE APPROVAL OF THE ENGINEER.

WALL TIES TO BE DEVELOPED IN AND FLEXED TO THE TIMBER FRAME 300 EACH SIDE OF
ANY ARTICULATION JOINT, AT EVERY THIRD (3RD) COURSE.

NON LOAD BEARING WALLS MUST BE DISCONNECTED FROM CONCRETE ABOVE BY 12MM THICK CLOSE CELL POLYETHELENE STRIPS.

STEEL FIXING

THIS CONSULTANCY'S ENGINEER MUST BE GIVEN 24 HOURS NOTICE FOR REINFORCEMENT INSPECTION.

REINFORCEMENT IS SHOWN IN DRAWINGS AND IS NOT NECESSARILY IN TRUE PROJECTION. CONNECTIONS TO REINFORCEMENT MUST BE MADE ONLY AT THE LOCATIONS SHOWN. IF REINFORCEMENT IS NEEDED ELSEWHERE IT MUST BE APPROVED BY THE PROJECT ENGINEER.

MODIFYING REINFORCEMENT/S IS NOT PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED BY THE PROJECT ENGINEER.

ALL REINFORCEMENT BARS AND FABRIC MUST FULFIL WITH AS4671. FABRIC MUST BE
BE SOURCED IN THE FORM OF FLAT SHEETS.

REINFORCEMENT MATERIAL IS INDICATED BY THE SYMBOLS BELOW:

5.1 Y – DEFORMED BAR GRADE 400
5.2 N– DEFORMED BAR GRADE 500 (NORMAL DUCTILITY)
5.3 R– PLAIN ROUND BAR GRADE 250
5.4 W– PLAIN WIRE GRADE 450
5.5 F– FABRICS GRADE 450
5.6 TM– TRENCH MESH

FABRIC REINFORCEMENT MUST BE LAPPED ONE MESH PLUS 30 mm AT SPLICES AND
PLACED ON BAR CHAIRS AT 1m CTS.

REINFORCING BARS MUST HAVE A LAP LENGTH AT SPLICES NOT LESS THAN
500mm UP TO A BAR DIA. OF 12mm, AND 700mm UP TO A BAR DIA. OF 16mm.
UNLESS NOTED OTHERWISE.

BENEATH THE SLAB FABRIC REINFORCING BARS SHOULD BE TIED IF USED OR
OTHERWISE PLACED ON CHAIRS.

SPLICES IN REINFORCEMENT MADE IN POSITIONS OTHER THAN SHOWN, MUST BE APPROVED BY THIS CONSULTANCY'S ENGINEER. WHERE LAP LENGTH IS NOT SHOWN, LAPPING MUST BE APPROPRIATE TO IMPROVE THE FULL STRENGTH OF THE REINFORCEMENT.

PRIOR TO POURING CONCRETE REINFORCEMENT AND VOID FORMERS MUST BE FIXED INTO POSITION THROUGH PROPRIETARY SPACERS, BAR CHAIRS AND LIGATURES TO ACCOMPLISH THE REQUIRED REINFORCEMENT POSITION AND COVER. ALL REINFORCEMENT MUST BE SUPPORTED ON A PLASTIC SPREAD OR STEEL CHAIRS AT A MAXIMUM OF 4 PER POD.

BRICK LINTEL SCHEDULE

OPENING SIZE (mm)	INTERNAL SKIN	EXTERNAL SKIN	END BEARING
UP TO 900mm	100 x 8mm FLAT BAR	100 x 6mm FLAT BAR	100 mm
1200	100 x 10mm FLAT BAR	100 x 8mm FLAT BAR	100 mm
1500	100 x 100 x 8mm ANGLE	100 x 100 x 6mm ANGLE	150 mm
2100	150 x 100 x 8mm ANGLE	150 x 100 x 6mm ANGLE	150 mm
2400	150 x 100 x 8mm ANGLE	150 x 100 x 8mm ANGLE	150 mm
2700	150 x 100 x 10mm ANGLE	150 x 100 x 10mm ANGLE	150 mm
3000	150 x 100 x 12mm ANGLE	150 x 100 x 12mm ANGLE	150 mm

NOTES
- ALL STEEL LINTELS TO BE HOT DIPPED GALVANIZED.
- ABOVE ALL LINTELS, PROVIDE M.E.T MASONARY REINFORCEMENT FOR 2 COURSES AND CONTINUE 1000mm PAST OPENING.

GENERAL MAINTAINCE

IN ACCORDANCE TO AS3660 IT IS PERMITTED TO PROTECT THE RESIDENCE FROM TERMITES IF IT IS NECESSARY.

INSPECTIONS OF THE RESIDENCE AND IMMEDIATE SURROUNDINGS MUST BE CARRIED OUT BY A FULLY QUALIFIED PEST PROFESSIONAL YEARLY BY THE OWNER.

THE MAINTENANCE OF THE SITE IS WHOLLY THE RESPONSIBILITY OF THE OWNER. ALL SANCTIONS OUTLINED IN THE FOLLOWING SHOULD BE CARRIED OUT IN ITS ENTIRETY:

CISRO BOOKLET FOUNDATION MAINTENANCE AND FOOTING PERFORMANCE: A HOME OWNERS GUIDE.

S2870 APPENDIX B 'PERFORMANCE CRITERIA AND FOUND AII ON MAINTENANCE' AND APPENDIX C 'CLASSIFICATION OF DAMAGE DUE TO FOUNDATION MOVEMENTS'.

THE ENDORSED DISTANCE OF A NEW TREE ON SITE MUST BE EQUAL OR GREATER THAN 75% OF THE MATURE TREE HEIGHT FOR M SITES, 100% OF THE MATURE HEIGHT FOR H1 AND H2 SITES, AND 150% OF THE MATURE HEIGHT FOR E SITES.

GARDEN BEDS ADJACENT TO THE HOUSE SHOULD BE REMOVED. ADDITIONALLY, AVOID OVER WATERING GARDENS CLOSE TO THE RESIDENTIAL FOOTINGS.

ANY FUTURE CRACKING OCCURING IN THE SLAB AND/OR FOOTINGS MUST BE ASSESSED BY A QUALIFIED PEST EXPERT AND THIS CONSULTANCY.

FOUNDATION MAINTENANCE AND DRAINAGE

ALL WORKMANSHIP AND MATERIALS MUST BE IN ACCORDANCE WITH AS2870.

SURFACE DRAINAGE MUST BE PLANNED AND DEVELOPED TO AVOID WATER ENTERING AGAINST OR NEAR THE FOOTING. THE GROUND IN THE DIRECT LOCALITY OF THE PERIMETER FOOTING, INCLUDING THE FOUND UPHILL FROM THE SLAB ON CUT–AND–FILL SITIES, MUST BE GRADED TO FALL 50MM MINIMUM AWAY FROM THE FOOTING OVER A DISTANCE OF 1 M AND SHAPED TO PREVENT THE ENTRANCE OF WATER. FILLING MUST BE PLACED ADJACENT TO THE BUILDING, THE FILLING MUST BE COMPACTED AND GRADED TO SAFEGUARD DRAINAGE OF WATER AWAY FROM THE BUILDING.

ANY PRIVATE SERVICE TRENCHES MUST BE SLOPED AWAY FROM THE BUILDING AND SUITABLY BACKFILLED, IN ACCORDANCE WITH AS2870.

MODERATELY & HIGH REACTIVE SITES REQUIRE SUPPLEMENTARY PLUMBING SERVICES & REQUIREMENTS.

AVOID PENETRATIONS OF FOOTINGS AND EDGE BEAMS. HOWEVER, NECESSARY PENETRATIONS MUST BE SLEEVED TO ALLOW FOR MOVEMENT.

AVOID DRAINAGE & PLUMBING BELOW THE SLAB UNLESS REQUIRED. REFER TO AS/NZS 3500 CLAUSE 4.10

IT IS ESSENTIAL THAT THE CELL POLYETHYLENE MEMBRANE MUST BE SURROUNDING ALL PIPEWORK INCLUDING STORMWATER & SANITARY PLUMBING DRAIN PIPE PENETRATIONS

ROOF SUPPORT AND LOADING

ROOF LOADINGS MUST BE SUPPORTED BY PATENTED TRUSSES ONTO EXTERNAL WALLS ONLY UNLESS NOTED OTHERWISE.

PITCHED ROOF REQUIREMENTS MUST BE DELIVERED BY THE CONTRACTOR TO THIS CONSULTANCY IN ADVANCED OF DETAILING.

THE BASIS OF DESIGN MUST BE SAA LOADING CODE AS1170.1, AS 1170.2 AND SAA TIMBER STRUCTURE CODE AS1720.1.

PLAN OF THE ROOF TRUSSES MUST BE IN ACCORDANCE WITH THE WIND CLASSIFICATIONS AS SPECIFIED.

PROVIDE ANY TEMPORARY BRACING NEEDED TO MAINTAIN THE STRENGTH OF THE TURUSSES AT ALL STAGES OF PRODUCTION.

MAKE ALLOWANCES FOR SIZE AND LOCATIONS OF MECHANICAL SERVICES AND AIR CONDITIONING DUCTWORK IF APPLICABLE.

ARRANGE FOR CERTIFICATION FROM A QUALIFIED CONSULTANCY THAT THE TRUSSES ARE STRUCTURALLY SATISFACTORY.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS


DRAWING NUMBER: CS101GAS	SHEET NUMBER: S00	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: GENERAL NOTES

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




GROUND FLOOR WAFFLE POD PLAN

SCALE 1:100

LEGEND	
STEP	DENOTES STEP IN CONCRETE SLAB
TR	DENOTES 2N12 1200 LONG TRIMMER BARS
	ø450 MASS CONCRETE PIERS @ MININMUM 1.5 DEEP INTO UNDISTURBED STIFF CLAY WITH A SAFE BEARING CAPACITY OF ALTEAST 150KPA
P1	ø450 MASS CONCRETE PIERS @ 2.5 DEEP
S.J.	SAWN CONTROL JOINT–REFER TO DETAIL
	DENOTES WALLS OVER
	DENOTES STARTING WAFFLE POD
S1	DENOTES WAFFLE SLAB 'S1'
S2	DENOTES DRIVEWAY SLAB 'S2'
S3	DENOTES PAVEMENT SLAB 'S3'
SP/A	DENOTES 89X89X6MM SHS STEEL POST ABOVE

DUE TO SOIL SALINITY CONCRETE PIERS TO BE f'c = 32 MPa.

BUILDER TO CONFIRM EXTERNAL FINISH LEVELS, DROP EDGE BEAMS MAY BE REQUIRED.



STRIP FOOTING 1
–SF1–

DRIVEWAY SLAB 'S2': 120 THICK, SL82 TOP

POUR DRIVEWAY SLABS ON 100 COMPACTED CRUSHED ROCK
ALL CONCRETE TO BE PLACED BY PUMPING AND COMPACTED WITH A VIBRATOR
NOTE: 1. MAX 6m SAWN CONTROL JOINT
2. MAX 15m KEYED CONSTRUCTION JOINT
3. MAX 30m EXPANSION JOINT

SITE

SITE IN ACCORDANCE WITH AS2870 CLASS H1
PIERED FOOTINGS HAVE BEEN DESIGNED FOR AN ALLOWABLE BEARING INTENSITY OF 250 KPA ON NATURAL UNDISTURBED STIFF CLAY
GEOTECHNICAL REFERNCE NUMBER: 14601 PREPARED BY: GEOID ENGINEERING PTY LTD, DATED 1 OCTOBER 2026

450ø MASS CONCRETE PIERS

MASS CONCRETE PIERS AVERAGE BEARING DEPTH TO BE 1.5M INTO NATURAL UNDISTURBED STIFF CLAY WITH A SAFE BEARING CAPACITY OF ATLEAST 150kPa.
GEOTECHNICAL ENGINEER TO CONFIRM BEARING BEFORE PLACEMENT OF CONCRETE.
ALL FOOTING SHOULD BE FOUNDED IN NATURAL UNDISTURBED STIFF CLAY WITH A SAFE BEARING CAPACITY OF ATLEAST 150kPa.

EXPOSURE CLASSIFICATION

INTERNAL SURFACES : A1
EXTERNAL SURFACES : B1

CONCRETE PIERS SPECIFICATIONS

1: STRENGTH TO BE 32 MPA INTERNAL SLAB
2: SLUMP OF 100MM
3. AGGREGATE MINIMUM SIZE 20MM.

WAFFLE SLAB 'S1'
100 THICK SLAB, SL82 MESH TOP

ALL SLABS LAID ON MIN. 50 THICKNESS OF CONSOLIDATED SAND COVERED WITH A 0.3 THICK POLYTHENE MEMBRANE WITH ALL JOINTS PROPERLY LAPPED AND TAPED
PROVIDE VERTICAL JOINT IN BRICKWORK AT 6M. MAX. CENTRES TO BCA REQUIREMENTS.
SLAB TO BE CURED BY ONE OF THE FOLLOWING METHODS
1. WETTING TWICE DAILY FOR THE FIRST THREE DAYS
2. USING AN APPROVED CURING COMPOUND
ALL CONCRETE IS TO BE PLACED BY PUMPING & COMPACTED WITH A VIBRATOR
ALL INTERNAL PODS TO BE 300
ALL EXTERNAL PODS TO BE 225
CONCRETE :
1: STRENGTH TO BE 32MPA
2: SLUMP OF 100MM
3: AGGREGATE MINIMUM SIZE 20MM.

REINFORCEMENT COVER SCHEDULE

FOOTING : (50MM)
INTERNAL SLAB : (30MM)
EXTERNAL SLAB : (40MM)
REINFORCED CONCRETE PIERS : (N/A)

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS


DRAWING NUMBER: CS101GAS	SHEET NUMBER: S1	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: WAFFLE POD PLAN SECTIONS AND DETAILS


PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3


0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




EDGE BEAM DETAIL EB1




EDGE BEAM DETAIL EB2




INTERNAL BEAM DETAIL IB1




TYPICAL TILE (40mm) SETDOWN DETAIL




INTERNAL STEP BEAM DETAIL SB1



INTERNAL STEP BEAM DETAIL SB2



EXTERNAL RIB BEAM DETAIL



INTERAL RIB BEAM DETAIL

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.


COMPASS CONSULTING ENGINEERS

DRAWING NUMBER: CS101GAS	SHEET NUMBER: S2	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	


PROJECT TITLE: WAFFLE POD PLAN SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143


0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




EXTERNAL DEEPENED
EDGE BEAM




INTERNAL DEEPENED
STEP BEAM




EXTERNAL DEEPENED
EDGE BEAM



EXTERNAL DEEPENED
EDGE BEAM




THROUGH BEAMS




THROUGH RIBS


PIPE PENETRATIONS



PIPE PENETRATION THROUGH SLAB



CORNER



INTERSECTION

WAFFLE POD DETAILS

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS


DRAWING NUMBER: CS101GAS	SHEET NUMBER: S3	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE
WAFFLE POD PLAN
SECTIONS AND DETAILS

PROJECT TITLE
PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143


A3

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




TYPICAL STEEL COLUMN DETAIL

WHERE STEEL POSTS EMBEDDED IN MASONRY ADOPT MET 5-1 COLUMN EXPANSION TIES OR APPROVED EQUIVALENT EVERY 4TH. COURSE





TYPICAL BASE PLATE DETAIL
(ADOPT AS REQUIRED)




ARTICULATION DETAILS

BRICKWORK CONTROL JOINTS AS PER AS4773.2 MASONRY IN SMALL BUILDINGS






REINFORCED CONCRETE PIER DETAIL (ADOPT IF REQUIRED)




BF1 BRIDGE FOOTING

SCALE 1:20




SECTION THROUGH PIER




LOCAL WIDENING OF EDGE BEAM


APPLICABLE UNDER ENGAGED BRICK COLUMNS, HOTWATER UNIT PADS, ETC.




PAVING SAW JOINT DETAIL 'SJ'




DRIVEWAY SAW CUT DETAIL 'SC'



TYPICAL PAVING ABUTTING STRUCTURE DETAILS



TYPICAL PAVING SLAB DETAIL



TYPICAL GRATED DRAIN DETAIL

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS. IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS


DRAWING NUMBER: CS101GAS	SHEET NUMBER: S4	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	


PROJECT TITLE: WAFFLE POD SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150






SECTION X
SCALE1:20

GRW – TIMBER RETAINING WALL DETAIL

TIMBER RETAINING WALL SCHEDULE	
TIMBER SLEEPERS	SIZE
UP TO 2000 mm	USE 200 x 75 TREATED PINE TIMBER SLEEPER

ENGINEER TO CONFIRM RETAINING WALLS LOCATION AND FOOTING PRIOR TO CONSTRUCTION



RETAINING WALL – RW1
SCALE 1:20

DIM 'H'	DIM 'A'	BARS 'B'	BARS 'C'	BARS 'D'
800	600	N12–400	N12–400	N12–400
1200	800	N12–400	N12–400	N12–400
1600	1000	N12–400	N16–400	N16–400
2000	1400	N16–400	N16–200	N16–400

DESIGN LOADS:
8.0 kPa EQUIVLENT FLUID PRESSURE
2t/sqm BACKFILL DENSITY
MAX 1:4 SLOPE BEHIND WALL
MIN ALLOWABLE BEARING CAPACITY 100 kPa

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.


COMPASS CONSULTING ENGINEERS

DRAWING NUMBER	SHEET NUMBER	ORIGINAL SIZE
CS101GAS	S4A	A3
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.

PROJECT TITLE: SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3
0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



FIRST FLOOR PLAN

SCALE 1:100

LEGEND	
J1	DENOTES TIMBER JOIST DIRECTION
	DENOTES VOID
	DENOTES LOWER ROOF TO AS1684
	DENOTES WALLS UNDER
SP/A&B	DENOTES 89X89X6MM SHS STEEL POST ABOVE AND BELOW

ALL BRACING & ROOF TIE DOWNS TO BE CONSTRUCTED IN ACCORDANCE WITH AS1684

REFER TO BRICK LINTEL SCHEDULE ON (S0) FOR ANY BRICK LINTELS MAX SPAN TO BE 3M OR LESS

TIMBER STAIRS TO MANUFACTURER'S SPECIFICATIONS.

ALL BEAMS TO BE SUPPORTED BY DOUBLE STUDS IF NO HARDWOOD POST IS DENOTED ON PLAN

NOTE: ALL EXTERNAL/EXPOSED STEEL BEAMS, POSTS, PLATES, BOLTS, WELDS TO BE FULLY GALVANIZED

FIRST FLOOR FRAMING PLAN		
GENERAL NOTES		
ALL EXPOSED TIMBER TO BE PRESSURE TREATED TO AS1684 ALL DETAILS TO BE CONFIRMED DURING CONSTRUCTION ALL TIMBER TO BE IN ACCORDANCE TO AS1684 ROOF TO BE BUILT IN ACCORDANCE TO AS1684		
ASSUMED FIRST FLOOR LOADS		
MAIN ROOF AS PER BUILDER'S SPECS		
LOWER ROOF AS PER BUILDER'S SPECS		
FIRST FLOOR (FLOOR BOARDS)		
ASSUMED ROOF LOADS		
MAIN ROOF – SHEET ROOF (40kg/m^2)		
GF LOWER ROOF – SHEET ROOF (40kg/m^2)		
TIMBER/JOIST/STEEL MEMBER SCHEDULE		
TB1	TIMBER BEAM	200X45 MEYSPAN13
TB2	TIMBER BEAM	240X45 MEYSPAN13
TB3	TIMBER BEAM	2/240X45 MEYSPAN13
TB4	TIMBER BEAM	240X63 MEYSPAN13
TB5	TIMBER BEAM	2/240X63 MEYSPAN13
TB6	TIMBER BEAM	300X45 MEYSPAN13
TB7	TIMBER BEAM	2/360X63 MEYSPAN13
SB1	STEEL BEAM	150X100X10UA
SB2	STEEL BEAM	250pfc+10MMPL
SB3	STEEL BEAM	310UC96.8
J1	FLOOR JOIST	300X45 MEYJOIST @ 450 CTS
J2	FLOOR JOIST	300X45 MEYJOIST @ 450 CTS
BJ1	BALCONY JOIST	200X45 HYJOIST @ 450 CTS
SHS	STEEL POST	89X89X6MM SHS

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS


DRAWING NUMBER: CS101GAS	SHEET NUMBER: S4 B	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: FIRST FLOOR FRAMING PLAN SECTIONS AND DETAILS


PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3


0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




TYPICAL CAVI-T-BAR DETAIL




TYPICAL PFC+PLATE DETAIL




TYPICAL UB + PLATE DETAIL




TYPICAL PFC + EA DETAIL




DOUBLE TIMBER BEAM DETAIL




TRIPLE TIMBER BEAM DETAIL




DETAIL A




TIMBER BEAM TO BRICKWORK CONNECTION




NAILING BEAM DETAIL



TYPICAL TIMBER BEAM TO STEEL BEAM CONNECTION DETAIL



TIMBER BEAM CONNECTION DETAILS



TYPICAL TIMBER BEAM TO STEEL BEAM CONNECTION DETAIL

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS

DRAWING NUMBER: CS101GAS	SHEET NUMBER: S5	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: ROOF SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



ROOF SUPPORT PLAN

SCALE 1:100

LEGEND	
	DENOTES LOWER ROOF TO AS1684
⊏⊐⊏⊐⊏⊐	DENOTES WALLS UNDER
SP/B	DENOTES 89X89X6MM SHS STEEL POST BELOW

TIMBER STAIRS TO MANUFACTURER'S SPECIFICATIONS.

ALL BEAMS TO BE SUPPORTED BY DOUBLE STUDS IF NO HARDWOOD POST IS DENOTED ON PLAN

ALL BRACING & ROOF TIE DOWNS TO BE CONSTRUCTED IN ACCORDANCE WITH AS1684

ROOF SUPPORT PLAN		
GENERAL NOTES		
ALL EXPOSED TIMBER TO BE PRESSURE TREATED TO AS1684 ALL DETAILS TO BE CONFIRMED DURING CONSTRUCTION ALL TIMBER TO BE IN ACCORDANCE TO AS1684 ROOF TO BE BUILT IN ACCORDANCE TO AS1684		
ASSUMED ROOF LOADS		
SHEET ROOF (40kg/m²) MAIN ROOF		
TIMBER/JOIST/STEEL MEMBER SCHEDULE		
TB1	TIMBER BEAM	240X63 MEYSPAN13
TB2	TIMBER BEAM	2/240X63 MEYSPAN13
TB3	TIMBER BEAM	2/300X45 MEYSPAN13
TB4	TIMBER BEAM	300X63 MEYSPAN13
SHS	STEEL POST	89X89X6MM SHS

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.


COMPASS CONSULTING ENGINEERS

DRAWING NUMBER: CS101GAS	SHEET NUMBER: S6	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	


PROJECT TITLE: ROOF SUPPORT FRAMING PLAN SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143


0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



MAXI BRACE
1.5kN/m BRACING TYPE



MAXI–SPEEDBRACE
3.0kN/m BRACING TYPE



PLYWOOD BRACING
3.4kN/m BRACING TYPE

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REVISION	DATE	AMENDMENT	ISSUE DATE	ISSUE
A	22.09.2026	ISSUED FOR CDC APPROVAL	22.09.2026	A

NORTH

COMPASS CONSULTING ENGINEERS
PHONE : 0411245988
E-MAIL: INFO@CCEENG.COM.AU
ABN:89 634 314 837

COPYRIGHT
THIS DRAWING REMAINS REMAINS THE PROPERTY OF COMPASS CONSULTING ENGINEERS.
IT MAY NOT BE ALTERED IN ANY WAY. UNAUTHORIZED USE IS PROHIBITED.

COMPASS CONSULTING ENGINEERS

DRAWING NUMBER: CS101GAS	SHEET NUMBER: S7	ORIGINAL SIZE: A3	
DESIGNED: S.N.	DATE: 22.09.2026	CHECKED: S.N.	
DRAWN: S.S.	SCALE: AS SHOWN	APPROVED: S.N.	

PROJECT TITLE: BRACING SECTIONS AND DETAILS

PROJECT TITLE: PROPOSED ATTACHED DUAL OCCUPANCY
101 GASCOIGNE RD BIRRONG NSW 2143

A3

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150