




NOTE
Lintel for W05 (4.5m slider)
2/300 x 45 LVL or 180 PFC.
(4.6m max. span) Units 4–6.



FIRST FLOOR BEAM LAYOUT FOR UNITS 4 – 6 (1:100)
TIMBER MEMBERS



FIRST FLOOR BEAM LAYOUT FOR UNITS 4 – 6 (1:100)
STEEL MEMBERS



FIRST FLOOR JOIST LAYOUT FOR UNITS 4 – 6 (1:100)

MEMBER SCHEDULE
POSTS

- P.1 — 2/90 x 45 MGP12 studs nailed or screwed together
P.2 — 2/90 x 45 LVL studs nailed or screwed together
P.3 — 140 x 140 F7, treated pine post
on HD galvanised post shoe.
P.4 — 89 x 6 SHS, post

UNIT No.4

FLOOR BEAMS

- 4FB.1 — 300 x 45 LVL. (2.6m max. span)
4FB.2 — 250 UB 31.4 (6.2m max. span)
4FB.3 — 2/300 x 45 LVL. (3.2m max. span)
4FB.4 — 2/300 x 45 LVL. (3.7m max. span)
4FB.5 — 2/300 x 45 LVL. (3.7m max. span)
4FB.6 — 2/300 x 45 LVL. (3.7m max. span)
4FB.7 — 300 x 45 LVL. (1.5m max. span)
4FB.8 — 200 UB 25 (4.0m max. span) or load bearing joist by others
4FB.9 — 300 x 45 LVL. or 2/FJ1 joists. (2.6m max. span)

DECK BEAMS

- 4DB.1 — 250 PFC. (6.4m max. span)
4DB.2 — 250 PFC. (2.6m max. span)

GARAGE LINTEL

- 4GL.1 — 250 PFC. (5.6m max. span)
4GL.2 — 2/240 x 45 LVL. (2.4m max. span)

WINDOW LINTELS

- 4LW.1 — 2/200 x 45 LVL. (1.8m max. span)
4LW.2 — 150 x 63 LVL. (1.8m max. span)

CANTILEVERED BEAM

- 4CB.1 — 250 PFC. (4.0m max. span) (1.9m max. cantilever)
4CB.2 — 200 UC 46 (4.0m max. span) (1.9m max. cantilever)
4CB.3 — 250 PFC (4.0m max. span) (0.6m max. cantilever)

UNIT No.5

FLOOR BEAMS

- 5FB.1 — 300 x 45 LVL. (2.6m max. span)
5FB.2 — 250 UB 31.4 (6.2m max. span)
5FB.3 — 2/300 x 45 LVL. (3.2m max. span)
5FB.4 — 2/300 x 45 LVL. (3.7m max. span)
5FB.5 — 2/300 x 45 LVL. (3.7m max. span)
5FB.6 — 2/300 x 45 LVL. (3.7m max. span)
5FB.7 — 300 x 45 LVL. (1.5m max. span)
5FB.8 — 200 UB 25 (4.0m max. span) or load bearing joist by others
5FB.9 — 300 x 45 LVL. or 2/FJ1 joists. (2.6m max. span)

DECK BEAMS

- 5DB.1 — 250 PFC. (6.4m max. span)
5DB.2 — 250 PFC. (2.6m max. span)

GARAGE LINTEL

- 5GL.1 — 250 PFC. (5.6m max. span)
5GL.2 — 2/240 x 45 LVL. (2.4m max. span)

WINDOW LINTELS

- 5LW.1 — 2/200 x 45 LVL. (1.8m max. span)
5LW.2 — 150 x 63 LVL. (1.8m max. span)

CANTILEVERED BEAM

- 5CB.1 — 250 PFC. (4.0m max. span) (1.9m max. cantilever)
5CB.2 — 200 UC 46 (4.0m max. span) (1.9m max. cantilever)
5CB.3 — 250 PFC (4.0m max. span) (0.6m max. cantilever)

NOTE 1

Deeper joists than those specified may be required to suit drainage pipe fixtures located within the floor space or provide dropped ceiling or bulkhead in room below.

NOTE 2

LVL. beams shall be equivalent to Hyspan LVL.14 or LVL.13
Lintels for openings of less than 3.6m width shall be determined from AS 1684.
Timber framing shall be in accordance with AS 1684 'Residential Timber Framed Construction'.

FIRST FLOOR LEVEL FRAMING

Wall framing and Lintels for openings widths less than 3.6m on the first floor level together with roof trusses shall be designed by the frame supplier.

Internal walls on first floor level have been assumed to be non-loadbearing (trussed roof)

UNIT No.6

FLOOR BEAMS

- 6FB.1 — 300 x 45 LVL. (2.6m max. span)
6FB.2 — 250 UB 31.4 (6.2m max. span)
6FB.3 — 2/300 x 45 LVL. (3.2m max. span)
6FB.4 — 2/300 x 45 LVL. (3.7m max. span)
6FB.5 — 2/300 x 45 LVL. (3.7m max. span)
6FB.6 — 2/300 x 45 LVL. (3.7m max. span)
6FB.7 — 300 x 45 LVL. (1.5m max. span)
6FB.8 — 200 UB 25 (4.0m max. span) or load bearing joist by others
6FB.9 — 300 x 45 LVL. or 2/FJ1 joists. (2.6m max. span)

DECK BEAMS

- 6DB.1 — 250 PFC. (6.4m max. span)
6DB.2 — 250 PFC. (2.6m max. span)

GARAGE LINTEL

- 6GL.1 — 250 PFC. (5.6m max. span)
6GL.2 — 2/240 x 45 LVL. (2.4m max. span)

WINDOW LINTELS

- 6LW.1 — 2/200 x 45 LVL. (1.8m max. span)
6LW.2 — 150 x 63 LVL. (1.8m max. span)

CANTILEVERED BEAM

- 6CB.1 — 250 PFC. (4.0m max. span) (1.9m max. cantilever)
6CB.2 — 200 UC 46 (4.0m max. span) (1.9m max. cantilever)
6CB.3 — 250 PFC (4.0m max. span) (0.6m max. cantilever)

FLOOR JOISTS

- FJ.2 — MJ255–63 meyJOIST or 240 x 45 LVL. at 450 spacing.
(3.0m max. span)
FJ.3 — MJ300–45 meyJOIST at 450 spacing (4.0m max. span)
Dj.2 — 200 x 45 LVL. at 450 spacing (2.6m max. span)
(may be ripped down to 170 deep to create fall)

(1:100) 0 2 4 6 8 10 METRES

ORIGINAL SIZE = A1

ISSUE: DATE: DETAILS OF AMENDMENT:

HALCROW & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS
A.C.N. 003 805 374

108 Avoca Drive,
Kincumber, N.S.W. 2251.
P.O. Box 6349 Kincumber, 2251
Phone: (02) 4369-0977
Email: design@halcrow.com.au

DESIGN: H.M.H.

DATE: 11.11.25

SCALE: 1:100

APPROVED:

DRAWN: B.N.

CHECKED: HMH

BE MIEAUST CPENG

CLIENT: Khouri Projects

PROJECT: Proposed Multi Dwelling Housing – 6 Units

SITE: Lots 258 & 259 (No. 59–61) Memorial Ave., BLACKWALL

TITLE:

FIRST FLOOR FRAMING PLANS – SHEET 2

DA/1115/2024

DRAWING NUMBER:

24.06.010

No. IN SET:

S6 of 9

AMENDMENT: